

1                                   **SECTION 641 – HYDRO-MULCH SEEDING**

2  
3     Make the following amendments to said Section:

4  
5     **(I)**     Amend **Subsection 641.02(B) – Fertilizer** by revising the section from  
6     line 33 to 36 to read:

7  
8             **“(B) Fertilizer.** Proper fertilizer shall be used in hydro-mulch mix,  
9             depending on condition of soil. Apply at rates and in amounts consistent  
10            with manufacturer’s specifications. Contractor shall provide a Soil Analysis  
11            Report, if requested by Engineer, and shall use report to determine  
12            quantity and ratio of fertilizer for sustained growth of grass. Submit  
13            recommendations from a licensed Landscape Architect when deviating  
14            from the application rates and amounts above.”

15  
16    **(II)**    Amend **Subsection 641.03(A) – Seeding** by revising the first paragraph  
17    from line 100 to 103 to read:

18  
19            **“(A) Seeding.** Apply seeded mulch within the timeframe in Subsection  
20            209.03(B), if temporary stabilization will not be utilized, after completion of  
21            slopes or portion of slope when exposed face attains height of 15 feet.  
22            Notify Engineer not less than 24 hours ahead of hydro-mulch seeding  
23            operation. Do not hydro-mulch until the Engineer inspects and accepts  
24            areas for planting.”

25  
26    **(III)**   Amend **Subsection 641.03(A) – Seeding** by adding the following  
27    paragraph after line 103 to read as follows:

28  
29            “The designated areas to be seeded shall be coordinated in the field with  
30            the Engineer and shall include, but is not limited to, the area within the ring  
31            net drapery system limits, up to 25 feet beyond the top of slope, and all  
32            other areas disturbed by the Contractor during construction operations.  
33            Hydro-mulch seeding shall be performed in the following sequence:

- 34  
35            (1)    The two cable lashing areas. Hydro-seed shall be performed after  
36            the installation of anchors and just prior to installation of the two  
37            cable lashing systems.  
38  
39            (2)    The ring net drapery system area. Hydro-seed shall be performed  
40            just prior to installation of the meshing system.  
41  
42            (3)    Top and bottom of cliff areas and other disturbed areas shall be  
43            hydro-seeded upon completion of construction.”

44  
45    **(IV)**    Amend **641.04 Measurement** and **641.05 Payment** to read as follows:  
46

47 "641.04 **Measurement.** Hydro-mulch seeding shall be measured per square  
48 yard. All costs for material, labor, and equipment to perform hydro-mulch  
49 seeding work specified in this section shall be considered incidental to the  
50 contract unit price.

51

52 **641.05 Payment.** The cost for work specified under this section will be paid  
53 on a unit price basis per square yard of accepted hydro-seeded area in  
54 accordance with the contract documents.

55

56 **Pay Item**

**Pay Unit**

57

58 Hydro-Mulch Seeding

Square Yard"

59

60

**END OF SECTION 641**