

SECTION 507 - RAILINGS

Make the following amendments to said Section:

(I) Amend **507.03 Materials** by adding the following:

"Rock lining for aesthetic railing shall be moss rock in appearance, lining material shall not exceed three inches thick at the widest point. Submit manufacturer's product data sheets for all materials to be used, and manufacturer's recommended installation procedure for Engineer's approval prior to beginning work."

(II) Amend **507.04 Method of Measurement** to read as follows:

"507.04 Method of Measurement. The Engineer will measure railings per linear foot. The Engineer will make the measurement along the centerline and from end to end of the railing.

The metal railing, the rock lining and the concrete and reinforcing steel in the aesthetic railing shall be considered integral to the aesthetic railing and not be paid for separately."

(III) Amend **507.05 Basis of Payment** to read as follows:

"507.05 Basis of Payment. The Engineer will pay for the accepted railings at the contract unit price per linear foot complete in place.

The price includes full compensation for furnishing, placing, and constructing the railings; structure excavation and backfill; storing the material; furnishing and placing entrance posts, pylons, and other items integral with the railing and portion of the railing steel that extends into the slab or beams; and furnishing materials, labor, equipment, tools and incidentals necessary to complete the work.

The Engineer will make payment under:

Pay Item	Pay Unit
_____ Railing	Linear Foot"

END OF SECTION