

Amend **Section 603 - Culverts and Storm Drains** to read as follows:

**"SECTION 603 - CULVERTS AND STORM DRAINS**

**603.01 Description.** This section is for cleaning the inlet swale, apron, drop inlet, culvert and outlet channel of silt, trash, debris and vegetative growth according to the contract.

**603.02 Materials.** No materials are to be used.

**603.03 Construction Requirements.** The Contractor shall clean, remove, and dispose of any silt, trash, debris and vegetative growth from the existing storm drain system. The inlet swale and outlet channel shall be cleaned and re-graded for a distance of 50 feet from the respective culvert end. Cleaning shall be done by manual means. The Contractor shall not discharge debris or wash water during spillway cleaning into any stream or ocean.

**603.04 Method of Measurement.** The Engineer will measure cleaning existing culvert on a force account basis according to Subsection 109.04 – Extra and Force Account Work and as ordered by the Engineer.

**603.05 Basis of Payment.** The Engineer will pay for the accepted cleaning on a force account basis according to Subsection 109.04 – Extra and Force Account Work. An estimated amount for the force account work is allocated in the proposal schedule, but the actual amount to be paid will be the sum shown on the accepted force account records, whether this sum is more or less than the estimated amount allocated in the proposal schedule. The price includes full compensation for excavation, grading, cleaning, removing and disposing excavated material, silt, trash, debris and vegetative growth from the existing inlet and outlet swales, headwalls, and culvert according to the contract; and furnishing labor, tools, equipment, and incidentals necessary to complete the work.

The Engineer will make payment under:

<b>Pay Item</b>	<b>Pay Unit</b>
Cleaning Existing Culvert	Force Account"

**END OF SECTION**