

1 **SECTION 645 – WORK ZONE TRAFFIC CONTROL**

2
3 Make the following amendments to said Section:

4
5 **(I) Amend Subsection 645.03 Construction** by adding the following
6 paragraphs after line 170 to read as follows:

7
8 **“(1) Covers.** Use sign covers when existing signs confuse the public or
9 are in conflict with TCP signs installed. Sign covers shall be commercially
10 manufactured and accepted by the Engineer before use. Sign covers shall
11 at all times and under all conditions not allow any portion of the sign being
12 covered to be visible. If more than one side of the sign has words or
13 symbols cover all sides of the signs until needed. “Homemade” or “field
14 made” covers shall not be used. Cover both sides of the sign if both sides
15 have symbols or words. Covering of sign identification markings are not
16 required if that is the only markings on that side of the sign. Sign covers shall
17 be maintained.

18
19 Removal of the existing sign in lieu of the use of sign covers may be
20 acceptable to the Engineer provided the previously removed existing sign is
21 immediately reinstalled when directed. Removal of existing post(s) and
22 mounting hardware is required if not used by the new TCP sign. New
23 mounting hardware shall be used to mount the TCP signs if the existing
24 hardware is in an unacceptable condition in the opinion of the Engineer. In
25 addition, should the sign or post during storage, in the opinion of the
26 Engineer, become unacceptable or lost or stolen the Contractor shall replace
27 the sign or post with a new sign or post. Use new hardware to reinstall the
28 sign regardless whether it is an existing sign or new.”

29
30 **(II) Amend Subsection 645.03(F) Lane Closures** from lines 253 to 254 to read
31 as follows:

32
33 “For island of Kauai, no lane closures will be allowed during 24-hour
34 period as follows:”

35
36 **(III) Amend Subsection 645.03(H) Advertisement** from lines 391 to 392 to
37 read as follows:

38
39 “Place advertisement for three consecutive days and within one week
40 before traffic pattern changes, in publication as ordered by the Engineer. In
41 lieu of the advertisement(s), the Engineer may substitute the use of two
42 portable changeable message boards and accessories at no additional cost
43 for three days for each required advertisement.”

44
45 **(IV) Amend Subsection 645.04 Measurement** from lines 394 to 403 to read
46 as follows:

48 **"645.04 Measurement.**

49
50 **(A)** Traffic control as specified in Subsection 645.03 - Construction
51 including sign covers and the initial advertisement(s) will be measured on a
52 contract lump sum basis. Measurement for payment will not apply.
53

54 **(B)** The Engineer will measure additional police officers, additional traffic
55 control devices, and additional advertisements, if ordered by the Engineer,
56 on a force account basis, in accordance with Subsection 109.06 - Force
57 Account Provisions and Compensation."

58
59 **(V)** Amend **Subsection 645.05 Payment** from lines 405 to 428 to read as
60 follows:
61

62 **"645.05 Payment.** The Engineer will pay for the accepted traffic control,
63 additional police officers, additional traffic control devices, and additional
64 advertisements at the contract price per pay unit, as shown in the proposal
65 schedule. Payment will be full compensation for the work prescribed in this section
66 and the contract documents.
67

68 The Engineer will pay for the following pay items when included in the
69 proposal schedule:
70

71 Pay Item	72 Pay Unit
73 Traffic Control	74 Lump Sum
75 Additional Police Officers, Additional Traffic Control Devices, 76 and Additional Advertisements	77 Force Account

78 An estimated amount for the force account may be allocated in the proposal
79 schedule under "Additional Police Officers, Additional Traffic Control Devices, and
80 Additional Advertisements", but the actual amount to be paid will be the sum shown
81 on the accepted force account records, whether this sum be more or less than the
82 estimated amount allocated in the proposal schedule.
83

84 The Engineer will not pay for request submittals. The Engineer will not
85 consider claims for additional compensation of late submittals or requests by
86 Contractor."
87
88
89

90 **END OF SECTION 645**