

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15
- 16
- 17
- 18
- 19
- 20
- 21
- 22
- 23
- 24
- 25
- 26
- 27
- 28

(I) Amend **Section 407.03(D) – Application of Tack Coat**, from lines 63 to 72 to read:

Before placing HMA or PMA course, apply tack coat to contact surfaces of curbs, gutters, manholes, other structures, vertical faces of existing pavements, and exposed transverse and longitudinal edges of each course. Apply tack coat on all surfaces that will have an asphalt pavement placed on it in a uniform, full coverage manner, e.g., no visible streak, holidays in the application, no differences in the application rate, i.e., the thickness of the tack coat. The exception to this requirement shall be surfaces that will have pavement joint adhesive applied to it which shall not require any tack coat.”

5600-02-23M
407-1a

11/23/22