

#### TYPICAL SLAB-ON-GRADE DETAILS

NOT TO SCALE


Minimum Splice ♦ Embedment Lengths For Concrete						
	Lap Splice		Embedment			
			Straight			
Bar Size	Bot Bar Or Wall Bar	Top Bar	Bot Bar Or Wall Bar	Top Bar	w/ Std Hook	
#3, #4	29"	38"	22"	29"	11''	
#5	36"	47"	28"	36"	14"	
#6	43"	56"	33"	43"	17"	
#7	63"	82"	48"	63"	20"	

- 1. Lengths Are For Concrete Beams & Columns With Rebar Spaced in Bar Diameter Min O.C. And Concrete Walls with Rebars Spaced 2 Bar Diameters Min O.C. Increase Bar Length 50% For Bars Spaced Closer Than Minimums Specified.
- 2. "Top Bars" Are Horizontal Bars With 12" Or More Of Concrete Cast Below.

# 90 Degree Bend 180 Degree Bend Length └1.5d<sub>b</sub> Max or Place Bars In Contact Wire Together 135 Degree Bend

 $D = 6d_b$  For #8 and Smaller D = 8d<sub>b</sub> For #9 To #11

#### Minimum Embedment, See Schedule -




Bolt Diameter	Minimum Embedment		
1/2"	4"		
5/8"	5"		
3/4"	6"		


AT CONCRETE

### TYPICAL REBAR SPLICE & EMBEDMENT SCHEDULE

NOT TO SCALE




With Elastomeric Joint Sealant, See Civil Dwgs  $\int_{-3/4}^{-3/4} \mathbb{Z} \times 2'-0''$  Long Smooth Dowel At 12" Provide Plastic Sleeve One Side Only CONTROL JOINT CJ-2 (TYPICAL)



## TYPICAL SLAB JOINT DETAILS


NOT TO SCALE



TYPICAL ANCHOR BOLT DETAIL

NOT TO SCALE





STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION

TYPICAL DETAILS

MAUI DISTRICT BASEYARD OFFICE EXPANSION \$ RENOVATION, PART 2 Project No. HWY-M-03-21, Phase 2 Scale: Not to Scale Date: July 2022

SHEET No. *S501* OF *6* SHEETS

