

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	440A-02-72	1974	2	10

NOTE:

- (1) All chuck holes and large depressions shall be filled and compacted w/ bituminous material and aggregate prior to resurfacing as directed by the Engineer.
Payment incidental to Bituminous Surface Treatment.
- (2) The shoulders shall be graded, watered and rolled as directed by the Engr.
Payment incidental to Roadway Exc.
- (3) The Contractor shall keep at least one lane open to public traffic during his working hours and all lanes open to public traffic during his non-working hours.

PINEAPPLE

FIELD

Payment will be made under Roadway Exc.
Construct Drainage Ditch
(See X-Section)

PINEAPPLE

FIELD

(4) The Contractor shall clean the highway surface before installing the pavement markers by brooming off and/or as directed by the Engineer. Payment shall be incidental to Pavement Markers.

Passing Permitted Both Ways

Passing Permitted One Way

PAVEMENT MARKER SUMMARY			
STATIONS	D	H	J
0+35 to 6+50	16		26
6+50 to 21+50	37	37	222
21+50 to 22+50	6		
22+50 to 30+65	21	21	126

LANAI AIRPORT ROAD

(IMPROVEMENTS TO AIRPORT ROAD FROM KAUMALAPAU HIGHWAY)

PROJECT No. 440A-02-72

TYPICAL SECTION

Scale: $\frac{1}{4}'' = 1'-0''$

End of Proj. 440A-02-72
Sta. 30+65

Construct Drainage Ditch
(See X-Section)

Payment will be made
under Roadway Exc.

2'x4' Tel.
Handhole

AIRPORT

terminal
old'g.

Construct Drainage Ditch
(See X-Section)
Payment will be made
under Roadway Exc.

