

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	440B-01-98M	1998	12	12

ROUTE MARKER SUMMARY			
SIGN ASSEMBLY	SIGN NO. AND MESSAGE	W/POST	
		TYPE A ASSEMBLY	TYPE B ASSEMBLY
SRM-1	WEST 440 M3-4 M1-6 (440)	1	
SRM-2	EAST 440 M3-2 M1-6 (440)	2	
TOTAL		3	

REFLECTOR MARKER SUMMARY				
TYPE	QUANTITY			
	W/O POST	W/FLEXIBLE POST		W/STEEL POST
	YELLOW	WHITE	BI-DIRECTIONAL	YELLOW
RM-2		10		-
RM-3				24
TOTAL		10		24

CONSTRUCTION SIGN SUMMARY			
SIGN NO.	MESSAGE	W/POST	W/O POST
CW20-1Ad	ROAD WORK AHEAD	1	
CG20-2A	END ROAD WORK	1	
TOTAL		2	

TRAFFIC SIGN SUMMARY			
SIGN NO.	MESSAGE	QUANTITY	
		10 SQ. FT. OR LESS	
		W/POST	W/O POST
R1-1A	STOP	1	
R4-1	DO NOT PASS	3	
W1-2(L) & (R)		3	
W3-1a	STOP AHEAD	1	
W15-2	FALLING ROCKS	1	
TOTAL		9	

MILEPOST MARKER SUMMARY			
LOCATION	SIGN NO. AND MESSAGE	QUANTITY	
		W/POST	W/O POST
# Sta. 14+20± Rt.	D10-5 MILE 10	1	
	D10-7 440		
TOTAL		1	

PAVEMENT MARKING SUMMARY	
DESCRIPTION	QUANTITY
PAVEMENT MARKERS	
TYPE C _____	300 EA.
TYPE D _____	300 EA.
TAPE - TYPE I OR THERMOPLASTIC EXTRUSION DOUBLE 4-INCH PAVEMENT STRIPE (YELLOW) _____	5,700 L.F.
TAPE - TYPE II OR THERMOPLASTIC EXTRUSION 4-INCH PAVEMENT STRIPE (WHITE) _____	11,400 L.F.
TAPE - TYPE III OR THERMOPLASTIC EXTRUSION 12-INCH PAVEMENT STRIPE (WHITE) _____	50 L.F.

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTE BOOK	DRAWN BY	JAN. 1998
DESIGNED BY	CR	
QUANTITIES BY		
CHECKED BY		

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

MISCELLANEOUS SUMMARIES

MANELE ROAD RESURFACING
Palawai Basin Towards Manele Bay
MP 9.72 to MP 10.72
Project No. 440B-01-98M

Date: January, 1998

SHEET No. 1 OF 1 SHEETS