

ARTICLE XVI – PAVEMENT MARKINGS

16.1 GENERAL - The work to be done under this Article consists of furnishing and installing all new “YB” circular logo pavement markings for new pavement areas..

16.1 MATERIAL

- A. Pavement Marking Material information for white and orange “YB” circle logo paint shall be provided by the Harbors Divisions Maui District Manager and Harbors Construction Engineer and Harbor Agent.

16.2 CONSTRUCTION

- A. New pavement markings shall consist of new white and orange “YB” circle logos to show designated areas as shown on the plans. The Contractor shall match existing layout and verify dimensions and locations of new markings in the field.
- B. The Contractor shall establish control points throughout the project for the layout of pavement markings. The layout shall be done by the Contractor and approved by the Construction Engineer prior to any installation work.
- C. Pavement paints shall be applied to surfaces that are free of moisture and thoroughly cleaned of loose, foreign or other material that may adversely affect bonding. Clean, newly placed surfaces need not be blast cleaned unless otherwise directed by the Construction Engineer for removal of abnormal amounts of asphalt, dirt, grease, oil or other material that may adversely affect bonding. If necessary, the Contractor shall additionally clean a prepared surface that may become contaminated with moisture, dust or other foreign matter immediately prior to the installation of pavement paints. The Construction Engineer will determine the suitability of any surface for the installation of pavement paints.
- D. Pavement markings shall be applied no sooner than SEVEN (7) days nor later than FOURTEEN (14) days after completion of the pavement. Markings and striping shall be laid out and painted to match the existing layout.

16.3 PAYMENT - Payment for pavement markings shall be included in the Painting Item as described in Article X of these Specifications.