

LOCATION	RM-2		RM-2 BI-DIRECTIONAL		RM-3		RM-4
	W/POST	W/O POST	W/POST	W/O POST	W/POST	W/O POST	W/POST
Sta. 3+00 Rt.						2	
Sta. 4+90 - Sta. 5+75 Lt. & Rt.					8		
Sta. 6+18 Lt. & Rt.					2		2
Sta. 6+32 Lt. & Rt.							2
Sta. 6+60 - Sta. 7+50 Lt. & Rt.					8		
Sta. 7+35 Lt. & Rt.					2		
Sta. 10+00 Lt.						2	
Sta. 14+50 Rt.						2	
Sta. 16+20-Sta. 17+40 Lt. & Rt.	8						
Sta. 18+50 Rt.						2	
Sta. 19+25 - Sta. 20+50 Rt.			6				
Sta. 21+75 Lt.						2	
Sta. 22+30 Lt.						2	
Sta. 28+00 Rt.						2	
Sta. 29+00 Rt.						2	
Sta. 29+80 - Sta. 31+25 Rt.			7				
Sta. 31+90 - Sta. 33+15 Lt.			6				
Sta. 34+85 Rt.					1		
Sta. 36+00 Rt.					1		
Sta. 37+00 Lt.						2	
Sta. 38+50 Rt.						2	
Sta. 38+50 Lt.						2	
Sta. 39+75 - Sta. 43+50 Lt.			16				
Sta. 44+00 Lt.						2	
Sta. 44+00 - Sta. 49+00 Rt.			21				
Sta. 54+80 - Sta. 56+00 Rt.			6				
Sta. 58+00 Rt.						2	
Sta. 59+50 Rt.					1		
Sta. 59+50 - Sta. 101+00 Rt.	85						
Sta. 63+00 Lt.						2	
Sta. 82+00 Lt.						2	
Sta. 99+00 Lt.						2	
Sta. 101+00 Rt.					1		
Sta. 107+00 Rt.						2	
Sta. 109+70 - Sta. 110+90 Lt.			6				
Sta. 112+00 Lt.						2	
Sta. 136+60 Lt.						2	
Sta. 136+60 Rt.						2	
TOTAL	93		68		20	1/40	4

GUARDRAIL SCHEDULE				
STATION TO STATION	OFFSET	606.3160 G.RAIL,TYPE 3	APPROACH	TRAIL
		L.F.		
Sta. 5+65 - Sta. 7+35	Rt.	145	C	BCT
Sta. 5+65 - Sta. 7+35	Lt.	145	C	BCT
Sta. 34+85 - Sta. 36+00	Rt.	115	Gm	F
Sta. 59+50 - Sta. 101+00	Rt.	4,150	C	Gm
TOTAL		4,555		

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

MISCELLANEOUS SUMMARIES

KAMEHAMEHA V HIGHWAY RESURFACING
Puu-O-Hoku Ranch to Halawa Bay
Project No. 450B-01-92M

Date: April, 1993

SHEET No. 1 OF 1 SHEETS

14

ORIGINAL PLAN	SURVEY PLOTTED BY _____	DATE _____
	DRAWN BY _____	_____
	TRACED BY _____	_____
NOTE BOOK	DESIGNED BY _____	_____
	QUANTITIES BY _____	_____
	CHECKED BY _____	_____
	N _e _____	_____