FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	450B-01-03M	2003	39	39

RAISED PAVEMENT MARKERS AND STRIPING SUMMARY

STATION TO STATION	PAVEMENT STRIPING					DISTANCE (L.F.)	PAVEMENT MARKERS (EA.)					ARROW	CROSS WALK	COMMENTS
	4" YELLOW (L.F.)		4" WHITE	8" WHITE	12" YELLOW		TYPE "C"	TYPE "D"	TYPE "H"	TYPE "J"	TYPE DB			
	DOUBLE	SINGLE	L.F.	L.F.	L.F							EA.	LANE	
KAMEHAMEHA V HIGHWAY (M.P. 16.50 - M.P. 22.00)														
STA. 130+00 - STA. 160+50	3050		3100	3000		3050	153	153			10			No Passing Both Sides
160+50 - 172+50		1200	2400			1200	60	31	31	124	2			One Way Passing
172+50 - 205+00	3250		2000	4500		3250	164	164			8			No Passing Both Sides
205+00 - 209+00		400		800		400	20	11	11	44	1			One Way Passing
209+00 - 223+00			2100	700		1400	70	36		144	3			Passing Both Sides
223+00 - 228+00	500		1000			500	25	25			3			No Passing Both Sides
228+00 - 239+00		1100	2200			1100	55	29	29	116	1			One Way Passing
239+00 - 242+00	300		600			300	15	15			1			No Passing Both Sides
242+00 - 246+00		400	800			400	20	11	11	44	1			One Way Passing
246+00 - 251+00			1000			500	25	13	13	52	3			Passing Both Sides
251+00 - 265+00		1400	1300	1500		1400	70	36	36	144	4			One Way Passing
265+00 - 273+00	800		100	1500		800	40	40			3			No Passing Both Sides
273+00 - 280+00			1400			700	35	18		72	3			Passing Both Sides
280+00 - 297+00	1700		3400			1700	85	85			6			No Passing Both Sides
297+00 - 420+00			18600	6000		12300	615				6			No Centerline Striping
TOTAL	9600	4500	40000	18000		29000	1452	667	131	740	55			
ESTIMATED QTY.	9600	4500	40000	18000		29000	1500	700	150	800	55			

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
	DRAWN BY JD	Jan. 03
NOTE BOOK	TRACED BY	
	DESIGNED BY CF	
	QUANTITIES BY	
	CHECKED BY	

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

RAISED PAVEMENT MARKERS SUMMARY

KAMEHAMEHA V HIGHWAY RESURFACING

Pukoo to Waialua

Project No. 450B-01-03M

Date: January, 2003

SHEET No. 1 OF 1 SHEETS