



NOTES ON PAVEMENT AND BASE COURSE

CRUSHER RUN BASE COURSE:
6" (compacted thickness) of Crusher Run Material. (20% wear)

ASPHALT MACADAM SURFACE COURSE:
3" (compacted thickness) No. 1 Crushed Rock (3 1/2" to 1 1/4"); 14 pounds per square yard Asphalt (85-100) and sufficient No. 3 Crushed Rock (1/2" to 3/4") to cover.

SEAL COAT:
3 to 4 pounds per square yard Asphalt (85-100) and sufficient No. 6 Crushed Rock (1/4" to 1/8") to cover.

SPECIAL SHOULDER TREATMENT:
6" (compacted thickness) River Gravel (2" to 0"); see Special Provisions of Specifications.

BITUMINOUS FOOTPATH SURFACE:
2" (compacted thickness) of Crusher Run Material covered by a bituminous surface of asphalt and fine Crushed Rock; see Specifications

GENERAL NOTES:
Particular reference is made to the specifications covering these items of work.

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTE BOOK	DESIGNED BY	
	DRAWN BY	
	CHECKED BY	
	QUANTITIES BY	
	NO.	