

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	NH-0900(080)	2013	3	47

GENERAL NOTES

- The project consists of two locations of State Highways, Kuihelani Highway (Route 380), from (M.P. 0.93 to M.P. 6.18) and Honoapiilani Highway (Route 30), from (M.P. 4.88 to M.P. 6.36). The scope of work along Kuihelani Highway includes resurfacing of existing pavement, cold planing, application of longitudinal joint stabilizer, crack seal of existing pavement and installing pavement markings and striping, and the scope of work along Honoapiilani Highway includes the application of slurry seal over existing pavement, installing of pavement markings and striping.
- The Contractor's attention is directed to the following Sections of the Special Provisions: Subsection 107.13 - Public Convenience and Safety; Subsection 107.21 - Contractor's Responsibility For Utility Property and Services; Subsection 104.04 Maintenance of Traffic and Section 645 - Traffic Control.
- At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.
- The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.
- Existing drainage system will be functional at all times during construction. The Contractor is to furnish materials, equipment, labor, tools and incidentals necessary to maintain flow. This work shall be considered incidental to various contract items.
- No material or equipment shall be stockpiled or otherwise stored within highway right-of-way except at locations designated in writing and approved by the Engineer.
- After the project is completed, the Contractor shall restore grades and groundcover within the project limits to a condition equal or better than existing condition prior to construction.
- All excess materials not needed for this project shall become the property of the Contractor. If disposed of, it shall be in accordance with the Environmental Protection Agency's policies and guidelines. This work shall be considered incidental to various contract items and will not be paid for separately.
- The Contractor shall remove and dispose of all existing raised pavement markers and traffic tapes prior to applying of slurry seal and overlying of concrete asphalt. This work shall be considered incidental to slurry seal & Hot Mix Asphalt (HMA) Pavement and will not be paid for separately.
- Removal of existing pavement markers and eradicating of existing pavement striping shall be incidental to slurry seal, Type III and Hot Mix Asphalt (HMA) Pavement.
- The Contractor shall notify the Engineer in writing, two (2) weeks prior to starting paving operations.

REQUIREMENTS OF STATE HISTORIC PRESERVATION DIVISION

- Should historic sites such as walls, platforms, pavements and mounds, or remains such as artifacts, burials, concentration of charcoal or shells are encountered during construction work, work shall cease in the immediate vicinity of the find and the find shall be protected from further damage. The Contractor shall immediately contact the State Historic Preservation Division (243-5169), which will assess the significance of the find and recommend an appropriate mitigation measure, if necessary.

LEGEND

- Resurfacing Limits
- Cold Planing Areas
- Existing CS Pipe
- ep

Existing Edge of Pavement
- es

Existing Edge of Shoulder
- Existing Metal Guardrail
- gdi

Existing Grated Drop Inlet
- pp

Existing Power Pole
- tp

Existing Telephone Pole
- mon.

Existing Monument
- fmt

Existing Fiber Optics Manhole
- Existing Fence
- RM-3
- New Traffic Sign
- p

Existing Traffic Sign With 1 Post
- β

Existing Traffic Sign With 2 Posts
- Existing Highway Lighting Standard

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTED BOOK	DRAWN BY	7/12
DESIGNED BY	DESIGNED BY	
CHECKED BY	CHECKED BY	

STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION
GENERAL NOTES AND LEGEND
KUIHELANI HIGHWAY & HONOAPIILANI HIGHWAY PAVEMENT PREVENTIVE MAINTENANCE Puunene Avenue to Honoapiilani Highway and Kuihelani Highway to Kapioli Street Federal-Aid Project No. NH-0900(080) Date: May, 20012