
## FED. ROAD STATE FISCAL SHEET TOTAL YEAR NO. SHEETS FED. AID PROJ. NO. HAW. HES-STP-030-1(20) 1992 3 HAWAII

## GENERAL NOTES:


- 1. The Project begins on Honoapiilani Highway in the vicinity of Papawai Point at approximate milepost 8.63. The Project proceeds beyond Papawai Point, heading towards Wailuku, approximately 1000 feet. The Project consists of constructing a left turn lane, widening the existing roadway, signing, and installing metal guardrail and pavement markings.
- 2. Smooth riding connections shall be constructed at the beginning and end of the project, and at all connecting approaches as directed by the Engineer. Payment for this work shall be made under Item No. 401.0500, Asphalt Concrete Pavement, Mix No. V.
- 3. The Contractor's attention is directed to Sub-Sections 104.04, 107.13, 107.21, 108.01, and Section 645 of the Standard Specifications and the Special Provisions.
- 4. Saw-cut of existing pavement shall not be measured or paid for separately, but shall be considered incidental to Item No. 401.0500, Asphalt Concrete Pavement, Mix No. V.
- 5. The existence and location of underground utilities, manholes, monuments, and structures as shown on the plans are from the latest available data, but accuracy is not guaranteed. The encountering of other obstacles during the course of the work may be possible. The Contractor shall be held liable for any damages incurred to the existing facilities as a result of his operations. All damaged portions shall be replaced in accordance with the Standards and Specifications of the State and/or the affected utility company.
- 6. Existing signs and reflector markers shall be relocated in accordance with the applicable sections of the Standard Plans. The Contractor shall provide the anchor base to replace the damaged ones.
- 7. Within the following limits, Install New Type 3 Thrie Beam Guardrail with 8' Post:


費 Sta. 342+76± to 費 Sta. 343+65± 費 Sta. 347+25± to 獎 Sta. 350+40± (Right)

 $\bar{B}$  Sta. 347+50± to  $\bar{B}$  Sta. 350+70± (Left)



Scale: 1/4" = 1' -0"





CUT SECTION Scale: 1/4"=1'-0"

> STATE OF HAWAII
> DEPARTMENT OF TRANSPORTATION
> HIGHWAYS DIVISION TYPICAL SECTION HONOAPIILANI HIGHWAY Left-Turn Storage Lane at Papawai Lookout Project No. HES-STP-030-1(20) Date: Sept., 1992 Scale: As Shown

> > SHEET No. / OF

SHEETS