

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
201.0200	Clearing and Grubbing Including Removing 45 Large Trees (520,000 Sq. Ft.)	L.S.	L.S.	L.S.	\$
203.0100	Roadway Excavation	11,100	Cu. Yd.	\$	\$
203.0210	Borrow Excavation	19,500	Cu. Yd.	\$	\$
206.2020	Structural Excavation for Drainage Systems	2,675	Cu. Yd.	\$	\$
206.7000	Structure Backfill for Concrete Box Culverts	464	Cu. Yd.	\$	\$
206.8000	Filter Material	25	Cu. Yd.	\$	\$
209.1000	Water Pollution and Erosion Control	F.A.	F.A.	F.A.	\$ 50,000.00
305.1110	Aggregate Subbase Course	3,600	Cu. Yd.	\$	\$
306.1000	Untreated Permeable Base Course	3,900	Cu. Yd.	\$	\$
312.0100	Plant Mix Glassphalt Concrete Base Course	10,800	Ton	\$	\$
401.0400	Asphalt Concrete Pavement, Mix No. IV	11,040	Ton	\$	\$
503.1300	Concrete in Concrete Inlet and Outlet Structures (Class A)	111	Cu. Yd.	\$	\$
503.1301	Concrete in Concrete Box Culverts (Class A)	227	Cu. Yd.	\$	\$
602.0400	Reinforcing Steel for Concrete Inlet and Outlet Structures (14,960 Lb.)	L.S.	L.S.	L.S.	\$

NH-030-1(28)

r1/07/02

P-8

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
602.0401	Reinforcing Steel for Concrete Box Culverts (33,110 Lb.)	L.S.	L.S.	L.S.	\$
603.0010	Bed Course Material for Culvert	637	Cu. Yd.	\$	\$
603.1010	18-Inch Reinforced Concrete Pipe, Class III, or 18-Inch High Density Polyethylene Pipe, Type S, or 18-Inch Aluminum Spiral Rib Pipe, thickness = 0.105"	5	Lin. Ft.	\$	\$
603.1012	24-Inch Reinforced Concrete Pipe, Class III, or 24-Inch High Density Polyethylene Pipe, Type S, or 24-Inch Aluminum Spiral Rib Pipe, thickness = 0.105"	1,304	Lin. Ft.	\$	\$
603.1014	36-Inch Reinforced Concrete Pipe, Class III	18	Lin. Ft.	\$	\$
603.1024	29" x 18" Corrugated Aluminum Pipe Arch, thickness = 0.105"	317	Lin. Ft.	\$	\$
603.2100	Type "1" Reinforced Concrete Collar	1	Each	\$	\$
603.2200	Type "2" Reinforced Concrete Collar	1	Each	\$	\$
604.2300	Type "61614P" Grate	2	Each	\$	\$
604.5100	Type "A" Storm Drain Manhole, 4.00 feet to 4.99 feet	1	Each	\$	\$
604.5200	Type "A" Storm Drain Manhole, 6.00 feet to 6.99 feet	1	Each	\$	\$
604.5210	Type "61614P" Grated Drop Inlet, 3.00 feet to 3.99 feet	1	Each	\$	\$
604.5211	Type "61614P" Grated Drop Inlet, 4.00 feet to 4.99 feet	10	Each	\$	\$

NH-030-1(28)

r1/07/02

P-9

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
604.5212	Type "61614P" Grated Drop Inlet, 5.00 feet to 5.99 feet	1	Each	\$	\$
604.5220	Modified Type "61614P" Grated Drop Inlet, 5.00 feet to 5.99 feet	1	Each	\$	\$
604.5230	Special Type "61614P" Grated Drop Inlet, 4.00 feet to 4.99 feet	1	Each	\$	\$
605.1000	Perforated Underdrain Pipe	3,940	Lin. Ft.	\$	\$
605.2000	Non-Perforated Underdrain Pipe	160	Lin. Ft.	\$	\$
605.3000	Cleanout	7	Each	\$	\$
606.3000	Guardrail, Type 3 - Single with Steel Post	3,893	Lin. Ft.	\$	\$
606.7100	Terminal Section, Type FLEAT-350	9	Each	\$	\$
607.9030	5-Strand Barbed Wire Fence, 5-Feet High (With Metal Posts 10-Feet on Center)	2,200	Lin. Ft.	\$	\$
609.2200	Gutter, Type 2(61614)	3,772	Lin. Ft.	\$	\$
612.6400	Grouted Rubble Paving for Lined Channel	2,305	Lin. Ft.	\$	\$
612.6410	Grouted Rubble Paving for Inlet and Outlet Structures	44	Cu. Yd.	\$	\$
621.0200	Panel for Destination Sign	31	Sq. Ft.	\$	\$
621.0300	Relocate Existing Destination Sign	1	Each	\$	\$

NH-030-1(28)

r1/07/02

P-10

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
621.1000	Galvanized Steel Post (W6x12) for Relocated Ground Mounted Destination Sign	36	Lin. Ft.	\$	\$
621.1400	2.50 Lbs./Ft. Flanged Channel Post for Destination Sign	6	Each	\$	\$
621.3010	Type VI Footing for Relocated Destination Sign	2	Each	\$	\$
621.4120	Reflector Marker (RM-3) with Steel Post	28	Each	\$	\$
621.5100	Regulatory and Warning Sign (10 Sq. Ft. or Less) with Post	7	Each	\$	\$
621.5600	Relocate Existing Shoreline Access Sign with Post	1	Each	\$	\$
621.5700	Relocate Existing Adopt A Highway Sign with Post	2	Each	\$	\$
621.6100	State Route Marker Assembly with Post (Type A)	5	Each	\$	\$
621.7100	Construction Sign with Posts	6	Each	\$	\$
621.7600	Mile Post Marker and Highway Route Marker Plate with Post	2	Each	\$	\$
622.0010	Roadway Lighting Standard Foundation	9	Each	\$	\$
622.0020	2-Foot x 4-Foot MECO Pre-Cast Concrete Pullbox	9	Each	\$	\$
622.0030	3-Inch PVC Schedule 40 Concrete Encased Conduit (1,600 Lin. Ft.)	L.S.	L.S.	L.S.	\$
622.0040	3-Inch PVC Schedule 40 Conduit Elbow and Riser	1	Each	\$	\$
622.0050	MECO Charges for Street Light Installation	F.A.	F.A.	F.A.	\$ 21,500.00

NH-030-1(28)

r1/07/02

P-11

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
629.1010	4-Inch Pavement Striping (Tape - Type I or Thermoplastic Extrusion, 1,210 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
629.1011	4-Inch Pavement Striping (Tape - Type II or Thermoplastic Extrusion, 17,680 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
629.1012	4-Inch Pavement Striping (Tape - Type III or Thermoplastic Extrusion, 1,200 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
629.1015	8-Inch Pavement Striping (Tape - Type II or Thermoplastic Extrusion, 580 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
629.1016	12-Inch Pavement Striping (Tape - Type II or Thermoplastic Extrusion, 610 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
629.1017	12-Inch Pavement Striping (Tape - Type III or Thermoplastic Extrusion, 15 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
629.1018	Double 4-Inch Pavement Striping (Tape - Type I or Thermoplastic Extrusion, 870 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
629.1019	Double 4-Inch Pavement Striping (Tape - Type II or Thermoplastic Extrusion, 2,480 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
629.1031	Pavement Arrows (Tape - Type III, or Thermoplastic Extrusion)	14	Each	\$ _____	\$ _____
629.1041	Pavement Words (Tape - Type III, or Thermoplastic Extrusion)	6	Each	\$ _____	\$ _____
629.2010	Type A Pavement Markers (1,020 Each)	L.S.	L.S.	L.S.	\$ _____

NH-030-1(28)

r1/07/02

P-12

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
629.2030	Type C Pavement Markers (586 Each)	L.S.	L.S.	L.S.	\$ _____
629.2040	Type D Pavement Markers (44 Each)	L.S.	L.S.	L.S.	\$ _____
629.2070	Type H Pavement Markers (288 Each)	L.S.	L.S.	L.S.	\$ _____
630.0010	2-Foot x 4-Foot MECO Pre-Cast Concrete Handhole	1	Each	\$ _____	\$ _____
630.0020	3-Foot x 5-Foot HTCO Pre-Cast Concrete Handhole	1	Each	\$ _____	\$ _____
630.0030	2-Inch PVC Schedule 40 Concrete Encased Conduit (40 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
630.0040	4-Inch PVC Schedule 40 Concrete Encased Conduit (90 Lin. Ft.)	L.S.	L.S.	L.S.	\$ _____
630.0050	2-Inch PVC Schedule 80 Conduit Elbow and Riser	1	Each	\$ _____	\$ _____
630.0060	4-Inch PVC Schedule 80 Conduit Elbow and Riser	3	Each	\$ _____	\$ _____
630.0070	Meter Socket, Breaker and Electrical Connection	L.S.	L.S.	L.S.	\$ _____
630.0080	Electrical Equipment Demolition	L.S.	L.S.	L.S.	\$ _____
630.0090	MECO Service Connection Charge	F.A.	F.A.	F.A.	\$ 1,500.00
636.1000	Project Site Laboratory (Not to Exceed \$22,000.00)	L.S.	L.S.	L.S.	\$ _____
636.2000	Maintenance of Field Office and Project Site Laboratory	F.A.	F.A.	F.A.	\$ 30,000.00
641.0100	Hydro-Mulch Seeding (Approximately 200,000 Sq. Ft.)	L.S.	L.S.	L.S.	\$ _____

NH-030-1(28)

r1/07/02

P-13

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
645.2000	Additional Police Officers and/or Additional Traffic Control Devices	F.A.	F.A.	F.A.	\$ 100,000.00
656.1000	Dumped Riprap	140	Cu. Yd.	\$ _____	\$ _____
699.0100	Mobilization (Not to Exceed 10 Percent of the Sum of All Items Excluding This Item, Project Site Laboratory, and all Force Account Items)	L.S.	L.S.	L.S.	\$ _____
	A. SUM OF ALL ITEMS				\$ _____
	B. Either Furnish Foreign Steel Not to Exceed Minimal Amount (Insert "0") or Furnish Foreign Steel in Excess of Minimal Amount (Insert "25% x A")				\$ _____
	C. Amount for Comparison of Bids (A + B)				\$ _____
	*All Bidders must fill in B and complete C. NOTE: Bidders must complete all unit prices. Failure to do so may be grounds for rejection of bid.				

NH-030-1(28)

r1/07/02

P-14

PROPOSAL SCHEDULE

The bidder is directed to Subsection 108.01 - Subletting of Contract.

The bidder's attention is directed to Section 636 - Field Office and Project Site Laboratory for the limitation of the amount bidders are allowed to bid.

The bidder's attention is directed to Section 699 - Mobilization for the limitation of the amount bidders are allowed to bid.

If the bid price for any proposal item having a maximum allowable bid indicated therefor in any of the contract documents is in excess of such a maximum amount, the bid price for such proposal item shall be adjusted to reflect the limitation thereon. The comparison of bids to determine the successful bidder and the amount of contract to be awarded shall be determined after such adjustments are made, and such adjustments shall be binding upon the bidder.

The bidder is directed to Subsections 106.12 - Recycling of Waste Glass and 106.13 - Ordering of Certain Material.

INSTRUCTIONS TO COMPUTE THE AMOUNT FOR COMPARISON OF BIDS FOR FOREIGN STEEL

Each bidder shall indicate its intention to furnish foreign steel on this project by initialing after the AMOUNT for each of the items the bidder intends to use such foreign steel including lump sum items. A bidder not indicating such usage certifies that the bidder will furnish and use only domestic steel on this project. Also, the bidder shall add an additional 25% to the SUM OF ALL ITEMS if the bid submitted is based on furnishing foreign steel in excess of the minimal use specified in Subsection 106.11 - Domestic Materials.