

VERIZON NOTES:

- . CONTRACTOR SHALL RELOCATE EXISTING VERIZON UNDERGROUND INFRASTRUCTURES, INCLUDING BUT NOT LIMITED INSTALLATION OF 2-4" PVC CONDUITS, NEW 3'x5' HANDHOLES, REPLACING EXISTING 2'x4' PULLBOXES WITH 3'x5' HANDHOLE, TRENCH EXCAVATION AND RESTORATION, PRIOR TO START OF CONSTRUCTION OF THE LAHAINA ROAD OVERPASS.
- . ALTERNATE ROUTES "A" AND "B" ARE ROUTE ACCEPTABLE TO VERIZON, CONTRACTOR SHALL COORDINATE DESIGN AND CONSTRUCTION OF SELECTED ROUTE WITH VERIZON.
- . ALTERNATE ROUTE "A" WILL REQUIRE A 15-FOOT WIDE EASEMENT; CONTRACTOR SHALL BE RESPONSIBLE FOR SECURE EASEMENT IN FAVOR OF VERIZON.
- . PLAN REPRODUCED FROM MECO "PRELIMINARY DISTRIBUTION OF KELAWEA MAUKA II".

