

1 **SECTION 313 – PERMEABLE SEPARATOR**

2
3 Make the following amendments to said Sections:

4
5 **(I)** Amend **Section 313.03 Construction** from lines 13 to 14 to read as follows:

6
7 **“(A) Site Preparation.**

8
9 **(1)** The exposed pavement subgrade materials should be
10 proofrolled with a large vibratory drum roller (minimum 10 tons
11 static weight) for a minimum of eight passes. The vibratory drum
12 roller should be operated at a speed of about 300 feet per minute.

13
14 **(2) Site Preparation Over Existing Waterline and Sewerline.**
15 The contractor shall exercise care and utilize appropriate
16 compaction equipment in the vicinity of the waterline and sewerline
17 to achieve the required minimum compaction and to avoid
18 damaging the utilities.

19
20 The contractor does have the option to use a large vibratory
21 drum roller if a CCTV inspection is conducted before and after the
22 vibratory compaction work in order to confirm the existing sewerline
23 was not damaged. If there are any damages due to the vibratory
24 compaction work, the contractor shall repair the damages to the
25 sewerline at their own cost.

26
27 **(II)** Amend **Section 313.03 Construction** from lines 50 to 60 to read as follows:

28
29 **“(F) Damage Repair.** Geotextile will be considered damaged if it is torn
30 or punctured, if overlaps or sewn joints are disturbed, or if there is
31 evidence of subgrade pumping, intrusion, or roadbed distortion. Repair
32 damaged geotextile by replacing it with a patch of the same type of
33 geotextile. Overlap existing geotextile a minimum of 3 feet from edge of
34 damaged area, or repair damaged sheets by sewing.”

35
36 **(III)** Amend **Section 313.04 Measurement** from lines 62 to 63 to read as follows:

37
38 **“313.04 Measurement.** The Engineer will measure permeable separator per
39 square yard in accordance with the contract documents.”

(IV) Amend **Section 313.05 Payment** from lines 65 to 68 to read as follows:

“313.05 Payment. The Engineer will pay for the accepted pay item listed below at the contract price per pay unit, as shown in the proposal schedule. Payment will be full compensation for the work prescribed in this section and the contract documents.

Pay Item	Pay Unit
Permeable Separator	Square Yard”

END OF SECTION 313