1 2	SECTION 613 – CENTERLINE AND REFERENCE SURVEY MONUMENTS
3	Make the following amendments to said Section:
5 6 7	(I) Amend Subsection 613.03(A) – Initial Installation from lines 22 to 26 to read:
8 9 10 11 12 13 14	"(A) Initial Installation. Cut holes, in completed medians and shoulders, to required depth or to solid rock, whichever is less Fill hole with concrete. Burr or feather plug for anchorage in concrete. Place the 4 #4 x 20-inch bars as shown on the plans when curing the concrete. Install brass plug in required position after concrete has sufficiently set. After curing concrete at least 7 days, restore edge of pavement surrounding monument to original condition."
17 18 19	(II) Amend lines 48 through 60 of Subsection 613.04 - Measuremen to read as follows:
20 21 22 23	"(C) Adjusting Centerline and Reference Survey Monument The Engineer will measure for adjustments of centerline and reference survey monuments per each.
24 25 26 27	(D) Survey Work. The Engineer will not measure survey work to verify the centerline and reference survey monuments fo payment."
28 29 30	(III) Amend lines 71 through 88 of Subsection 613.05 - Payment to read as follows:
31 32 33 34	"(C) Adjusting Centerline and Reference Survey Monument The Engineer will pay for the accepted adjustments of centerline and reference survey monuments per each.
35 36 37 38 39	(D) Survey Work. The Engineer will not pay for survey work separately and will consider the cost for survey work as included in the contract prices for various pay items under this section. The cost is for the work prescribed in this section and the contract documents."
11 12 13	The Engineer will pay for each of the following pay items wher included in the proposal schedule:
14 15	Pay Item Pay Uni

47	Centerline and Reference Survey Monuments	Each
48 49	Reconstructing Centerline and Reference Survey Monuments	Each
50		
51	Adjusting Centerline and Reference Survey Monuments	Each"
52 53		
54	END OF SECTION 613	