

SECTION 629 - PAVEMENT MARKINGS

Make the following amendments to said Section:

(I) Amend **Subsection 629.03(B) – Temporary Pavement Markings** by revising the third paragraph from line 62 to 63 to read:

“Maintain and replace temporary pavement markings, flexible delineators, and barricades.”

(II) Amend **Table 629.03 – 1 – Temporary Pavement Markings** to read as follows:

“TABLE 629.03-1 TEMPORARY PAVEMENT MARKINGS	
TYPE	PAVEMENT MARKINGS
Passing Permitted - Both Sides	Single 4-inch yellow stripe 5 feet in length spaced 20 feet on center with Type D markers spaced 40 feet on center and located on center of 5-foot length of stripe.
Passing Prohibited - Both Sides	Double solid 4-inch yellow stripes with Type D markers placed 20 feet on center on one of 4-inch yellow stripes selected by the Engineer.
Passing Permitted - One Side Only	Single continuous 4-inch yellow stripe with Type D markers placed on stripe 20 feet on center on no-passing side and single 4-inch yellow stripes 5 feet in length spaced 20 feet on center on passing side.
Lane Lines - Lane Changing Permitted	Single 4-inch yellow or white stripe 5 feet in length spaced 20 feet on center with Type C or Type D markers spaced 40 feet on center.
Lane Lines - Lane Changing Prohibited	Double solid 4-inch white stripes with Type C markers placed 20 feet on center on one of the 4-inch white stripes selected by the Engineer.
Crosswalk	Two 12-inch white transverse lines spaced 8 feet on center or as ordered by the Engineer.
Stop Line	Single 12-inch white transverse line.
Note: Paint may be used for temporary markings in areas where final paving is not complete.”	

(III) Amend **Section 629.04 Measurement** from lines 292 to 294 to read as follows:

“629.04 Measurement. Pavement striping will be paid per linear foot. Crosswalk Markings will be paid per lane. Pavement arrow, pavement word, pavement symbol, and pavement markers will be paid per each.”

(IV) Amend Section 629.05 Payment from lines 296 to 330 to read as follows:

“629.05 Payment. The Engineer will pay for the accepted pay items listed below at the contract price per pay unit, as shown in the proposal schedule. Payment will be full compensation for the work prescribed in this section and the contract documents.

The Engineer will pay for each of the following pay items when included in the proposal schedule:

Pay Item	Pay Unit
4-Inch Yellow Pavement Striping (Thermoplastic Extrusion)	Linear Foot
4-Inch White Pavement Striping (Thermoplastic Extrusion)	Linear Foot
4-Inch Yellow Dashed Pavement Striping (Thermoplastic Extrusion)	Linear Foot
4-Inch White Dashed Pavement Striping (Thermoplastic Extrusion)	Linear Foot
6-Inch White Pavement Striping (Thermoplastic Extrusion)	Linear Foot
8-Inch White Pavement Striping (Thermoplastic Extrusion)	Linear Foot
12-Inch Yellow Pavement Striping (Thermoplastic Extrusion)	Linear Foot
12-Inch White Pavement Striping (Thermoplastic Extrusion)	Linear Foot
Crosswalk Marking (Thermoplastic Extrusion)	Lane
Pavement Arrow (Thermoplastic Extrusion)	Each
Pavement Word (Thermoplastic Extrusion)	Each
Pavement Symbol Bike (Thermoplastic Extrusion)	Each
Pavement Symbol Shared Lane Marking (Thermoplastic Extrusion)	Each
Type “C” Pavement Markers	Each
Type “D” Pavement Markers	Each

65		
66	Type "F" Pavement Markers	Each
67		
68	Type "H" Pavement Markers	Each"
69		
70	END OF SECTION 629	
71		