

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	HWY-M-04-99M	1999	35	36

RAISED PAVEMENT MARKERS AND STRIPING SUMMARY

STATION TO STATION	PAVEMENT STRIPING					DISTANCE (L.F.)	PAVEMENT MARKERS (EA.)					STOP BAR	PAVEMENT		CROSS WALK	COMMENTS
	4" YELLOW (L.F.)		4" WHITE	8" WHITE	12" YELLOW		TYPE "A"	TYPE "C"	TYPE "D"	TYPE "H"	TYPE "J"		WHITE 12" (L.F.)	ARROW		
	DOUBLE	SINGLE	L.F.	L.F.	L.F											
HALEAKALA HIGHWAY - WORK AREA 1 M.P. 0.00 - M.P. 5.60																
37+15± - 42+00	480	150	1360	700	450*	485	40	100	10	25		24	6		3	Intersection Transverse Median Channelizing Island Two Lanes (Inbound) One Lane (Outbound) Transverse Median One Lane (Inbound) Two Lanes (Outbound)
42+00 - 48+00	600		1200			600	64	48	31							
48+00 - 54+00	1200		1680		125	600		32		60						
54+00 - 72+20.36	1820		3640			1820	186	140	92							
(72+20.36 = 0+00 EQ. STA.)																
0+00 - 206+70	20670		41340			20670	2071	1553	1035			550				One Lane (Inbound) Two Lanes (Outbound)
206+70 - 221+00	2900		4000		300	1430	150	130		110		50	6	3		Intersection Transverse Median Channelizing Island Accel. & Decel. Lanes
221+00 - 252+00	3100		6200			3100	315	235	156							One Lane (Inbound) Two Lanes (Outbound)
252+00 - 262+55	1055	650	2110	1030	730*	1055		85	55	30		35	3			Haleakala Bypass Old Haleakala Hwy. Intersection - Off Ramp
SUBTOTAL	31825	800	61530	1730	1605	29760	2826	2323	1379	225		659	15	3	3	
HANA HIGHWAY - WORK AREA 2 M.P. 6.58 - M.P. 8.82																
253+81 - 257+00	319		638			319		17	17							No Passing
257+00 - 262+30	800	120	750	200	100	530		20		40		80	8	1	6	Intersection Hana Hwy. Baldwin Ave. Transv. Median
262+30 - 273+50	1120		2240			1120		57	57							No Passing
273+50 - 283+65	1340		2270	550	100	1015	45	105	30	40			7		7	Transverse Median Left & Right Turn Decel. Lane
283+65 - 467+75	18410		36820			18410		922	922			150			2	No Passing
(467+75 = 112+00 EQ. STA.)																
112+00 - 118+76.04	676		1352			676		35	35							No Passing
SUBTOTAL	22665	120	44070	750	200	22070	45	1156	1061	80		230	15	1	15	Transverse Median
MOKULELE HIGHWAY - WORK AREA 3 M.P. 0.67 - M.P. 6.50																
3+00 - 4+00	200		200		50	200		6		12						
4+00 - 22+00	1800		3600			1800		91	91							No Passing
22+00 - 57+44.82			7090			3545		178	90		360					Passing Both Sides
(57+44.82 = 57+36.98 EQ. STA.)																
57+36.98 - 64+00			1326			663		34	18		72					Passing Both Sides
64+00 - 68+01.86		402	804			402		21	11	11	44					Oneway Passing
(68+01.86 = 5+34.63 EQ. STA.)																
SUBTOTAL	2000	402	13020		50	6610		330	210	23	476					

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
	DRAWN BY	Dec. 1998
	TRACED BY	
	NOTED BY	
NOTE BOOK	QUANTITIES BY	
	CHECKED BY	

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

RAISED PAVEMENT MARKERS
STRIPING SUMMARY

HALEAKALA HIGHWAY,
HANA HIGHWAY AND MOKULELE HIGHWAY
PAVEMENT MARKING AND STRIPING
Project No. HWY-M-04-99M

Date: January, 1999

SHEET No. 1 OF 2 SHEETS

[illegible]

ORIGINAL PLAN _____ SURVEY PLOTTED BY _____ DATE Dec. 1928
DRAWN BY 46 _____
TRACED BY _____
NOTE BOOK _____ DESIGNED BY CR _____
login: jay _____
QUANTITIES BY _____
CHECKED BY _____
8 mmms24gn

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

RAISED PAVEMENT MARKERS
\$ STRIPING SUMMARY
HALEAKALA HIGHWAY,
HANA HIGHWAY AND MOKULELE HIGHWAY
PAVEMENT MARKING AND STRIPING
Project No. HWY-M-04-99M

Date: January, 1999