

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	NH-036-1(17)	2008	3	13

GENERAL NOTES

1. The scope of work for this project consists of application of slurry seal over existing asphalt concrete pavement, installing pavement markings and striping.
2. The Contractor's attention is directed to the following Sections of the Special Provisions : Subsection 104.09 - Maintenance of Traffic; Subsection 107.06 - Contractor duty regarding Public Convenience 104.11 - Utilities and Services; and Section 645 - Traffic Control.
3. At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.
4. The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.
5. Existing drainage system will be functional at all times during construction. The Contractor is to furnish materials, equipment, labor, tools and incidentals necessary to maintain flow. This work shall be considered incidental to various contract items.
6. No material or equipment shall be stockpiled or otherwise stored within highway right-of-way except at locations designated in writing and approved by the Engineer.
7. After the project is completed, the Contractor shall restore grades and groundcover within the project limits to a condition equal or better than existing condition prior to construction.
8. All excess materials not needed for this project shall become the property of the Contractor. If disposed of, it shall be in accordance with the Environmental Protection Agency's policies and guidelines. This work shall be considered incidental to various contract items and will not be paid for separately.
9. The Contractor shall remove and dispose of all existing raised pavement markers and traffic tapes prior to applying of slurry seal. This work shall be considered incidental to slurry seal and will not be paid for separately.
10. Removal of existing pavement markers and eradicating of existing pavement striping shall be incidental to slurry seal, Type III.
11. The Contractor shall notify the Engineer in writing, two (2) weeks prior to starting paving operations.

LEGEND

- ep Existing Edge of Pavement  
es Existing Edge of Shoulder  
- M - Existing Metal Guardrail  
gdi Existing Grated Drop Inlet

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
	DRAWN BY	
	DESIGNED BY	
	CHECKED BY	
NOTE BOOK	NOTED BY	
	DESIGNED BY	
	CHECKED BY	
	CHECKED BY	

STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION
<b>GENERAL NOTES AND LEGEND</b>
HANA HIGHWAY PAVEMENT PREVENTIVE MAINTENANCE Kaahumanu Avenue to Dairy Road Federal-Aid Project No. NH-036-1(17)
Date: August, 2008
SHEET No. 1 OF 1 SHEETS