

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	36BC-02-17M	2017	3	42

GENERAL NOTES

- The project includes cold planing existing pavement, reconstructing weakened pavement areas, overlaying 2 inch Hot Mix Asphalt Pavement, installing pavement markings, installing guardrail Type 3 Strong Post W-Beam and end terminals, installing milled rumble strip, applying longitudinal joint stabilizer, adjusting centerline and reference monuments, and cleaning storm drains within the project limits.
- The Contractor's attention is directed to the following Sections of the Special Provisions: Subsection 107.06 Contractor Duty Regarding Public Convenience, Subsection 104.11 Utilities and Services, Subsection 104.09 Maintenance of Traffic, and Section 645 - Work Zone Traffic Control.
- At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.
- The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.
- Existing drainage system will be functional at all times during construction. The Contractor is to furnish materials, equipment, labor, tools and incidentals necessary to maintain flow. This work shall be considered incidental to various contract items.
- No material or equipment shall be stockpiled or otherwise stored within highway right-of-way except at locations designated in writing and approved by the Engineer.
- After the project is completed, the Contractor shall restore grades and groundcover within the project limits to a condition equal or better than existing condition prior to construction.
- All excess materials not needed for this project shall become the property of the Contractor. If disposed of, it shall be in accordance with the Environmental Protection Agency's policies and guidelines. This work shall be considered incidental to various contract items and will not be paid for separately.
- The Contractor shall remove and dispose of all existing raised pavement markers and traffic tapes prior to Cold Planing. This work shall be considered incidental to Cold Planing and will not be paid for separately.
- The Contractor shall notify the Engineer in writing, two (2) weeks prior to starting paving operations.
- The Contractor shall contact Hawaii One Call Center for existence and location of underground utilities. Please call 811 or 1-800-551-8344.
- Dressing of shoulder, sidewalk shall consist of cleaning, grubbing, grading, reshaping and compacting the unpaved shoulder with suitable materials as shown on the plans and/or as directed by the Engineer. This works shall be incidental to various contract items.

REQUIREMENTS OF STATE HISTORIC PRESERVATION DIVISION

- Should historic sites such as walls, platforms, pavements and mounds, or remains such as artifacts, burials, concentration of charcoal or shells are encountered during construction work, work shall cease in the immediate vicinity of the find and the find shall be protected from further damage. The Contractor shall immediately contact the State Historic Preservation Division (243-5169), which will assess the significance of the find and recommend an appropriate mitigation measure, if necessary.

Section 7 of the Endangered Species Act:

- To avoid impacts to listed seabirds, no night work will be allowed.
- To avoid impacts to the Hawaiian hoary bat, trees and shrubs taller than 15 feet will not be trimmed or cleared between June 1 and September 15.
- No utilities will be moved or realigned.
- No highway lighting will be installed or replaced.
- All work will occur on existing roadways or within the paved portions of the right-of-way.

Section 106 of the National Historic Preservation Act:

- If cultural materials are discovered during construction, all earth-moving activity within and around the immediate discovery area will be diverted until a qualified archaeologist can ases the nature and significance of the find.
- If human remains are discovered, Hawaii Administrative Rule Title 13, Chapter 300 states that further disturbances and activities shall cease in any area or nearby area suspected of overlie remains, and SHPD and the Maui Police Department will be contacted. The human remains will be treated in conformance with HAR 13-300 Subchapter 4, "Procedures for Proper Treatment of Burial Sites and Human Skeletal Remains."

LEGEND

- Resurfacing Limits
- Reconstruction Areas
- Existing CS Pipe
- ep

Existing Edge of Pavement
- es

Existing Edge of Shoulder
- H -

Existing Metal Guardrail
- gdi

Existing Grated Drop Inlet
- ° pp

Existing Power Pole
- ° tp

Existing Telephone Pole
- mon.

Existing Monument
- MON.

Adjusted Monument
- RM-3

RM-3
- 1

Existing Traffic Sign Wtih 1 Post
- 2

Existing Traffic Sign Wtih 2 Posts
- Existing Highway Lighting Standard
- WMH

Adjusted Water MH Frame/Cover
- WV

Adjusted Water Valve Box
- fh

Existing Fire Hydrant
- sp

Existing Standpipe
- SMH

Adjusted Sewer MH Frame/Cover
- gdi

Existing Grated Drop Inlet

SURVEY PLOTTED BY	DATE
DRAWN BY	
TRACED BY	
NOTED BY	
QUANTITIES BY	
CHECKED BY	

ORIGINAL PLAN
NOTE BOOK
FILED
STAMPED

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

GENERAL NOTES AND LEGEND

HANA HIGHWAY RESURFACING
Hookipa Park to Kaupakalua Road
Project No. 36BC-02-17M

Date: December, 2016

SHEET No. 1 OF 1 SHEETS