
FED. ROAD DIST. NO. STATE PROJ. NO. FISCAL YEAR NO. SHEET NO. SHEETS


HAWAII HAW. 37B-02-94 1995 7 8




NOTES:


- 1. Center sensor loops in lanes.
- 2. Collector cables shall be twisted 2 turns per foot.
- 3. Number of loops and locations vary. See project plans.
- 4. Number and locations of collector sawcuts may be varied in the field to suit.





TYPICAL SENSOR LOOP SAWCUT DETAIL






NOTES ON CONSTRUCTION AT END OF SAWCUT

- 1. Seal roadway end of conduit after installation of conductors.
- 2. Install bulkhead across conduit trench.
- 3. Place hot tar in sawcut.
- 4. Backfill over conduit with new A.C.
- 5. Reconstruct curb and gutter as required.

DETAIL OF SENSOR LOOP INSTALLATION

AT EDGE OF ROADWAY



TYPICAL SENSOR LOOP WIRING DIAGRAM

TYPES OF CABLES

TYPE 1 Signal Loop Cable: Stranded No. 14, 26 conductors

TYPE 2 Detector Lead-In Cable and Pedestrian
Push Button Circuit Cable: Stranded,
No. 14, 2 Conductors

TYPE 3 Interconnect Cable: Solid No. 20, 12 Pairs

TYPE 4 Loop Sensor Cable: Solid No. 12, Single Conductor to IMSA SPEC 51-5

TYPE 5 Cable from Signal Loop to Signal Head: Stranded, No. 14, Single Conductor

TYPE 6 Service Cable: Solid, No. 6, 3 Conductors

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

LOOP DETECTOR DETAILS

HALEAKALA HIGHWAY (PUKALANI BY-PASS)

TRAFFIC SIGNALS AT MAKAWAO AVENUE

PROJECT NO. 37B-02-94

Not to Scale

Date: June, 1994

SHEET No. 1 OF 1 SHEETS

