

**STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION**

**ADDENDUM NO. 4
for
KULA HIGHWAY GUARDRAIL AND SHOULDER IMPROVEMENTS
OMAOPIO ROAD TO SUN YAT SEN PARK**

PROJECT NO. STP-037-1(027)

DISTRICT OF MAKAWAO

ISLAND OF MAUI

2019

A. NOTICE TO BIDDERS

1. Prospective bidders are hereby notified that receiving of sealed bids scheduled for October 3, 2019 will be postponed until **2:00 P.M. October 10, 2019**. The attached NOTICE TO BIDDERS dated 9/24/2019 shall be incorporated and made a part of the NOTICE TO BIDDERS.

B. PROPOSAL

1. Delete PROPOSAL SCHEDULE pages P-8 to P-9 dated r/9/16/2019 and replace them with the attached PROPOSAL SCHEDULE pages P-8 to P-9 dated r9/24/2019.


C. PLANS

1. Delete Plan Sheets ADD.14, ADD.18, ADD. 19, ADD. 21, ADD 23, ADD.25, ADD 27, ADD 32, and ADD 35 and replace them with the attached Plan Sheets ADD. 14, ADD.18, ADD. 19, ADD.21, ADD. 23, ADD.25, ADD.27, ADD. 32 and ADD.35 dated 9/23/2019.

D. RFI AND RESPONSES

1. See Attached RFI and Responses


Please acknowledge receipt of this Addendum No. 4 by recording the date of its receipt in the space provided on page P-4 of the Proposal.



JADE T. BUTAY
Director of Transportation

NOTICE TO BIDDERS
(Chapter 103D, HRS)

The receiving of SEALED BIDS for KULA HIGHWAY GUARDRAIL AND SHOULDER IMPROVEMENTS, OMAOPIO ROAD TO SUN YAT SEN PARK, FEDERAL-AID PROJECT NO. STP-037-1(027), scheduled for 2:00 P.M., October 3, 2019, at the Contracts Office, Department of Transportation, 869 Punchbowl Street, Honolulu, Hawaii 96813, or at the Office of the District Engineer-Maui, 650 Palapala Drive, Kahului, Hawaii 96732, is HEREBY POSTPONED until **2:00 P.M., October 10, 2019**, at which time and place they will be publicly opened and read.



JADE T. BUTAY
Director of Transportation

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
209.1000	Installation, Maintenance, Monitoring, and Removal of BMP	L.S.	L.S.	L.S.	\$ _____
209.2000	Additional Water Pollution, Dust, and Erosion Control	F.A.	F.A.	F.A.	\$ <u>5,000.00</u>
401.0200	Hot Mix Asphalt (HMA) Pavement, Mix No. V at Guardrail Front, Under, Behind and Beyond Terminals	714	Ton	\$ _____	\$ _____
606.3000	Terminal Section Soft Stop System	8	EA	\$ _____	\$ _____
606.4000	Reset Guardrail Post	5,038	L.F.	\$ _____	\$ _____
631.3000	Contruction Sign With Post	5	EA	\$ _____	\$ _____
632.1000	Reflector Marker (RM-3) Yellow With Steel Post	292	EA	\$ _____	\$ _____
632.2000	Reflector Marker (RM-3) Yellow With Flexible Post	7	EA	\$ _____	\$ _____
632.3000	Reflector Marker (RM-4) Yellow With Steel Post	8	EA	\$ _____	\$ _____
632.4000	Reflector Marker (RM-5) Mounted on Rail	1,068	EA	\$ _____	\$ _____
632.5000	Type II Object Marker With Flexible Post	32	EA	\$ _____	\$ _____
643.1000	Maintenance of Existing Landscape Areas	F.A.	F.A.	F.A.	\$ <u>50,000.00</u>
645.0200	Traffic Control	L.S.	L.S.	L.S.	\$ _____
645.0210	Additional Police Officers, Additional Traffic Control Devices, And Advertisement	F.A.	F.A.	F.A.	\$ <u>25,000.00</u>
648.0100	Field-Posted Drawing	L.S.	L.S.	L.S.	\$ _____
696.0000	Field Office trailer (Not to Exceed \$32,000.00)	L.S.	L.S.	L.S.	\$ _____

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
696.2000	Maintenance of Trailer	F.A.	F.A.	F.A.	\$ 15,000.00
699.1000	Mobilization (Not to exceed 6% of the Sum of all items excluding bid price of this item).	L.S.	L.S.	L.S.	\$
Sum of All Items					\$
<p>NOTE: Bidders must complete all unit prices and amounts. Failure to do so may be grounds for rejection of bid.</p> <p>The lowest responsible bidder will be determined by comparison of Sum of All Items.</p>					

**STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION**

**REQUEST FOR INFORMATION
DOT RESPONSES**

For

**KULA HIGHWAY GUARDRAIL AND SHOULDER IMPROVEMENTS
OMAOPIO ROAD TO SUN YAT SEN PARK**

PROJECT NO. STP-037-1(027)

DISTRICT OF MAKAWAO

ISLAND OF MAUI

2019

RFI 1.1 – Can State Mix V be used for the paving under the guardrail?.

RFI 1.1 Response: See Addendum No.3.

RFI 1.2 – For plan sheet 8 & 9 please clarify the location for guardrail with offset block and guardrail without block.

RFI 1.2 Response: The 31" MGS without the blockout could be used in certain specific situations where additional roadway space is desired or required.

RFI 1.3 – For plan sheet 11 "Trailing End Anchorage System" there are no call outs in the plan & no pay item.

RFI 1.3 Response: Not required.

RFI 1.4 – For plan sheet 12 "MSG Transition to Strong Post Guardrail" there are no call outs in the plan & no pay item.

RFI 1.4 Response: Not required.

RFI 1.5 – For plan sheet 13 "Thrie Beam Guardrail" there are no call outs in the plan and no pay item.

RFI 1.5 Response: Not required..

RFI 1.6 -For Pay Item 606.4000 – Reset Guardrail Post- does the post need to be fully removed then reinstalled? Or adjusted to new height?

RFI 1.6 Response: Yes, guardrail post shall be fully removed, reset and adjusted to the new height.

RFI 1.7 – For Pay Item 606.4000 Reset guardrail Post – is there a provision for post damaged posts.

RFI 1.7 Response: Yes, there is a provision in the Hawaii Standard Specifications for Road and Bridge Construction 2005.

RFI 1.8 – On Sheet 14 there is a call out for RM-3 on flexible, but there is no pay item.

RFI 1.8 Response: See Addendum 4

RFI 1.9 – On Sheet 18 there two call outs for RM-5 within the same STA location STA 6+15LT to STA12+00LT and STA 6+00LT to STA10+00LT.

RFI 1.9 Response: See Addendum 4

RFI 1.10 – There are call outs for RM-5 installation but there is no GR legend on the plans sheet 19 STA 14+55 to STA 15+85 RT.

RFI 1.10 Response: See Addendum 4.

RFI 1.11 – On Sheet 21 there is a call out for Soft Stop at STA 62+00 LT to STA 65+87.5 LT please clarify approach or trailing end.

RFI 1.11 Response: Approach terminal.

RFI 1.12 - There are call outs for RM-5 installation but there is no GR legend on the plans sheet 21 STA 73+20 to STA 75+00LT.

RFI 1.12 Response: See Addendum No.4.

RFI 1.13 - There are call outs for RM-5 installation but there is no GR legend on the plans sheet 27 STA47+20 to STA 49+60LT.

RFI 1.13 Response: See Addendum No.4.

RFI 1.14 - There are call outs for RM-5 installation but there is no GR legend on the plans sheet 27 STA 47+20 to STA 49+20LT.

RFI 1.14 Response: See Addendum No.4.

RFI 1.15 – On Sheet 34 there is no call outs for RM-3 on steel post behind guardrail.

RFI 1.15 Response: No call out on plan sheet 34.

RFI 1.16 – There is a pay item 631.3000 Construction Sign with Post, there is no call on plans, please clarify and type, size and location.

RFI 1.16 Response: See Addendum No. 4

RFI 1.17 – For the call for the pay item 606.4000 Reset Guardrail post-there are two different types of call outs LF and EA. On sheet 23 at Sta 114+35 to Sta 124+00 Lt call out is 80 Ea on other locations call out is in LF

RFI 1.17 Response: See Addendum No.4

RFI 1.18 – For the call outs for the pay item 606.4000 Reset Guardrail Post - please clarify on why the LF call out does not always match the LF of the guardrail run minus the end treatment?

RFI 1.18 Response: The length of reset guardrail as shown in the plan only be reset not the entire length of guardrail run from Station to Station.

END OF RFI RESPONSES