


FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	STP-0310(4)	2007	3	24

GENERAL NOTES

1. The Project begins on North Kihei Road at Sta. ~~0+00~~ **10+63** of Project No. STP-0310(4) in the vicinity of Honoapiilani Highway and proceeds towards Wailea ending in the vicinity of South Kihei Road. The scope of work for this project consists of applying a slurry seal to the existing pavement, replacing of signage and installation of pavement markings.
2. The Contractor's attention is directed to Sub-Section 104.09 Maintenance of Traffic, 107.06 Contractor Duty Regarding Public Convenience 104.11 Utilities and Services Section 645 Traffic Control of the Standard Specification and the Special Provisions.
3. The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.
4. The Contractor shall notify the Engineer in writing, two (2) weeks prior to starting operations.
5. All construction signs shall be left in place until all construction items have been completed. Contractor shall obtain prior approval from the Engineer to remove construction signs.
6. Smooth riding connections shall be constructed at the beginning and end of the project and at all connecting approaches, side roads and driveways shown on the plans and/or as directed by the Engineer.
7. At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.
8. The Contractor shall provide for vehicular and pedestrian access to and from all existing sideroads, driveways and walkways at all times.
9. The Contractor shall remove and dispose of all existing raised pavement markers prior to the overlaying of ~~Asphalt Concrete~~ **Slurry Seal**. This work shall be considered incidental to ~~Asphalt Concrete Pavement, Mix No. IV~~ **Slurry Seal, Type III** and will not be paid for separately.

LEGEND

- ~~XXXXXX~~ ~~Reconstruction Areas~~
~~(See Schedule Sht. No. 16)~~
- ~~XXXXXX~~ ~~Cold Planing Areas~~
-  ~~Resurfacing~~ Slurry Limits
- ep Existing Edge of Pavement
- es Existing Edge of Shoulder
- III- RM-4

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTE BOOK	DRAWN BY	Aug. 07
	TRACED BY	
	DESIGNED BY	
	QUANTITIES BY	
	CHECKED BY	

LEGEND FOR	
AS-BUILT POSTINGS	
XXXXXX	Squiggly line for as-built deletion
00.00	Double line for as-built deletion
Roadway	Text for as-built posting

STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION
GENERAL NOTES AND LEGEND
NORTH KIHAI ROAD PAVEMENT PREVENTIVE MAINTENANCE
Honoapiilani Highway to Piilani Highway
Federal-Aid Project No. STP-0310(4)
Date: August, 2007
SHEET No. 1 OF 1 SHEETS