

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	360A-01-82 360A-01-83M	1982	3	36

PAVEMENT WIDTH SCHEDULE

APPROX. LIMITS STA. TO STA.	PAVEMENT WIDTH	APPROX. LIMITS STA. TO STA.	PAVEMENT WIDTH
79+00 - 80+25	21.0'	437+25 - 438+75	17.0'
80+25 - 81+75	19.0'	438+75 - 439+75	15.0'
81+75 - 95+25	16.0'	439+75 - 453+25	16.0'
95+25 - 96+75	18.0'	453+25 - 454+75	14.0'
96+75 - 114+75	16.0'	454+75 - 460+25	16.0'
114+75 - 117+25	17.0'	460+25 - 461+25	17.0'
117+25 - 119+25	18.0'	461+25 - 518+00**	16.0'
119+25 - 124+75	16.0'	525+75 - 526+75	18.0'
124+75 - 125+75	17.0'	526+75 - 540+25	16.0'
125+75 - 126+75	18.0'	540+25 - 541+25	17.0'
126+75 - 129+25	20.0'	541+25 - 542+75	15.0'
129+25 - 141+25	16.0'	542+75 - 547+75	16.0'
141+25 - 142+75	18.0'	547+75 - 548+75	13.0'
142+75 - 179+25	16.0'	548+75 - 567+25	16.0'
179+25 - 181+25	18.0'	567+25 - 570+25	18.0'
181+25 - 183+75	16.0'	570+25 - 571+75	17.0'
183+75 - 185+75	18.0'	571+75 - 573+25	18.0'
185+75 - 201+25	16.0'	573+25 - 575+25	16.0'
201+25 - 205+25	17.0'	575+25 - 576+75	19.0'
205+25 - 210+75	18.0'	576+75 - 578+25	15.0'
210+75 - 212+75	16.0'	578+25 - 582+75	18.0'
212+75 - 214+25	18.0'	582+75 - 585+25	17.0'
214+25 - 239+25	16.0'	585+25 - 588+25	10.0'
239+25 - 241+25	17.0'	588+25 - 590+25	18.0'
241+25 - 290+25	16.0'		
290+25 - 291+75	18.0'	*Eq Sta. 590+00 = Sta. 0+90	
291+75 - 297+25	16.0'	1+15 - 44+25	18.0'
297+25 - 299+25	17.0'	44+25 - 100+75	20.0'
299+25 - 301+75	18.0'	100+75 - 106+25	18.0'
301+75 - 303+25	16.0'	106+25 - 114+00	26.0'
303+25 - 305+25	18.0'	**STA. 518+00 = END OF LEVELING COURSE	
305+25 - 329+75	16.0'	STA. 423+50 = END OF SURFACE COURSE	
329+75 - 331+25	18.0'		
331+25 - 432+75	16.0'	*PROJ. NOS. 360A-01-82 & 360A-01-83M Sta. 590+00± = COUNTY JOB NO. 68-15 Sta. 0+90±	
432+75 - 433+75	17.0'		
433+75 - 437+25	16.0'		

CRM WALL SCHEDULE

APPROX. LIMITS STA. TO STA.	APPROX. CRM VOL.	APPROX. SHOTCRETE AREA
186+50± - 192+00± RT.	54 57 C.Y.	287 185 S.Y.
341+25± - 341+60± LT.	7 6 C.Y.	10 15 S.Y.
453+50± - 454+50± LT.	46 10 C.Y.	43 35 S.Y.
541+50± - 543+00± LT.	15 17 C.Y.	25 50 S.Y.
181+00 - 183+00 LT.	11 C.Y.	79 S.Y.
TOTAL	90 C.Y.	285 S.Y.
305+00 - 305+15 LT.	2 C.Y.	
375+40 - 375+58 LT.	3 C.Y.	
454+40 - 455+08 LT.	36 C.Y.	
TOTAL	135 C.Y.	504 S.Y.

PAVEMENT MARKINGS SUMMARY

DESCRIPTION	QUANTITY
PAVEMENT STRIPING - 4" DOUBLE YELLOW	41,419 62,816 L.F.
TYPE "D" PAVEMENT MARKERS	1,950 3,125 Ea.
PAVEMENT STRIPING - 8" WHITE E.P. C.C.O. #3	18,702 L.F.

TRAFFIC SIGNS AND REFLECTOR MARKERS SUMMARY

TYPE	DESCRIPTION	QUANTITY	
		W/ POST	W/O POST
R2-1 (15)	SPEED LIMIT SIGN	10	
W1-5R	WINDING ROAD SIGN	8	
W1-5L	WINDING ROAD SIGN	5	
W1-8R	CHEVRON ALIGNMENT SIGN	58	
W1-8L	CHEVRON ALIGNMENT SIGN	60	
W5-1	ROAD NARROWS SIGN	8	
W5-2a	NARROW BRIDGE SIGN	6	
W13-1 (10)	ADVISORY SPEED PLATE		12
W17-1R	HAIR PIN TURN SIGN	2	
W17-1L	HAIR PIN TURN SIGN	2	
RM-1	REFLECTOR MARKER WITH RESILIENT DELINEATOR POST	857 1,885	
RM-3	REFLECTOR MARKER WITH RESILIENT DELINEATOR POST	143 190	
W1-3R	REVERSE TURN SIGN	2	
W3-2a	YIELD AHEAD (FIELD DIRECTIVE No. 1A)	4	
R1-2	YIELD (FIELD DIRECTIVE No. 1A)	4	
R5P-1	TO ONCOMING TRAFFIC (FIELD DIRECTIVE No. 1A)		4

NOTES:

- For CRM Wall Details, see Plan Sht. No. 2.
- For Traffic Sign Locations, see Plan Sht. Nos. 4 to 13.
- For Typical Reflector Markers Spacings, see Plan Sht. No. 4.
- For Typical Pavement Markers and Striping Details, see Plan Sht. No. 4.

7/20/82 Quantities revised to reflect increase in Scope of Work in accordance with Subsection 103.01 Consideration of Proposals of the Special Provisions.

DATE REVISION

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
LAND TRANSPORTATION FACILITIES DIVISION
PAVEMENT WIDTH, CRM, SIGNS
RM'S & PAVEMENT MARKINGS
SCHEDULES AND SUMMARIES
HANA HIGHWAY
IMPROVEMENTS & RESURFACING
Proj. Nos. 360A-01-82 & 360A-01-83M

Date: June, 1982

SHEET No. 1 OF 1 SHEETS