

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	360B-01-06M	2006	27	28

RAISED PAVEMENT MARKERS AND STRIPING SUMMARY										
STATION TO STATION	PAVEMENT STRIPING					DISTANCE (L.F.)	PAVEMENT MARKERS (EA)		YIELD PAVEMENT MARKING	COMMENTS
	4" YELLOW (L.F.)		4" WHITE	8" WHITE	12" YELLOW		TYPE "C"	TYPE "D"		
	DOUBLE	SINGLE	L.F.	L.F.	L.F.				LANE	
1089+50 - 1089+75	25			50		25	2	2		No passing both sides
1089+75 - 1090+70				190		95	8		1	Kapaula Bridge
1090+70 - 1098+20	750			1500		750	38	38		No passing both sides
1098+20 - 1115+15	1695		3390			1695	85	85		No passing both sides
1115+15 - 1122+65	750			1500		750	38	38		
1122+65 - 1123+85				240		120	8		1	Hanawai Bridge
1123+85 - 1131+60	775			1550		755	40	40		No passing both sides
1131+60 - 1132+95				270		135	8		2	E. Hanawai Bridge
1132+95 - 1175+00	4205		2410	3000		4205	211	211		No passing both sides
1175+00 - 1175+85				170		85	6		1	Makapiipi Bridge
1175+85 - 1186+40	1055			2110		1055	53	53		No passing both sides
1186+40 - 1187+45				210		105	8		1	Kuhiwa Bridge
1187+45 - 1198+55	1110			2220		1110	56	56		No passing both sides
1198+55 - 1199+30				150		75	6		1	Kupukoi Bridge
1199+30 - 1226+45	2715		2640	2790		2715	121	121		No passing both sides
1226+45 - 1227+10				130		65	6		1	Kahalaowaka Bridge
1227+10 - 1234+60	750			1500		750	38	38		No passing both sides
1234+60 - 1254+25	1965		2430	1500		1965	99	99		No passing both sides
1254+25 - 1255+00				150		75	6		1	Pupape Bridge
1255+00 - 1260+90	590			1180		590	30	30		
1260+90 - 1261+95				210		105	6		1	Kawaihapapa Bridge
1261+95 - 1269+90	795			1590		795	40	40		No passing both sides
1269+90 - 1270+60				140		70	6		1	Kehaki Bridge
1270+60 - 1278+85	825			1650		825	42	42		
1278+85 - 1279+60				150		75	6		1	West Waioni Bridge
1279+60 - 1281+40	180			360		180	10	10		
1281+40 - 1282+20				160		80	6		1	Waioni Bridge
1282+20 - 1289+70	750			1500		750	38	38		
1289+70 - 1322+15	3245		4990	1500		3245	163	163	2	No passing both sides
1322+15 - 1323+15				260		100	6		1	Lanikele Bridge
1323+15 - 1330+60	730			1460		730	37	37		
1330+60 - 1331+40				160		80	6		1	Heleleikeoho Bridge
1331+40 - 1334+10	270			540		270	14	14		No passing both sides
1334+10 - 1335+05				190		95	6		1	Ulaino Bridge
1335+05 - 1351+20	1615			3230		1615	82	82		No passing both sides
1351+20 - 1351+10				180		90	5		1	Mokulehua Bridge
1351+10 - 1359+60	750			1500		750	38	38		
1359+60 - 1385+00	2540		5080			2540	127	127		No passing both sides
TOTAL	28085		20940	35130			1505	1402	19	
SAY	28100		21000	35200			1550	1450		

ORIGINAL PLAN	SURVEY PLOTTED BY _____ DATE _____
NOTE BOOK	DRAWN BY <u>JO</u> _____
<u>med Jay</u>	TRACED BY _____
<u>thamsmidgrn</u>	DESIGNED BY <u>Gr</u> _____
<u>Gr</u>	QUANTITIES BY _____
	CHECKED BY _____

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

RAISED PAVEMENT MARKERS
AND STRIPING SUMMARY

HANA HIGHWAY RESURFACING
Kapaula Bridge to Olowai Bridge
Project No. 360B-01-06M

Date: October, 2005