

TRUE NORTH
Scale: 1 in. = 5 ft.

LEGEND

- Approx. C/L of Road
- Approx. R/W
- Limits of Cold Planing and New Pavement (Not in Contract)
- Re-Stripe 8" Solid White Line (Not in Contract)
- New GRP Apron
- Hydroseed and Erosion Mat
- Structural Improvements (See Struct Dwgs)

LEGEND FOR AS-BUILT POSTINGS

- Squiggly line for as-built deletion
- Double line for as-built deletion
- Text for as-built posting

Notes:

- Limits and quantities provided on this plan are approximate and for construction estimating purposes only.
- Erosion mat and GRP limits are shown in plan view. Contractor shall account for slope irregularities when performing work and installing construction materials.
- Contractor shall protect all utility structures to remain. Any damages to existing utilities shall be repaired by the Contractor at no additional cost.
- Object Markers shall be as specified in the FHWA MUTCD.
- See structural drawings for bridge repair plan and details.
- State DOT R/W is shown schematically based off available record maps within the project area. Record R/W map with metes and bounds were not available for reference and a boundary survey was not performed for this project.

Site Plan

EMERGENCY REPAIRS AT PIINAU BRIDGE
HANA HIGHWAY, NEAR MILEPOST 17.0
PROJECT NO. ER-20(006), UNIT 1
Scale: As Noted Date: September 2018

Scale: 1"=5'

Scale: 1" = 5' Feet

SHEET No. 4 OF 16 SHEETS

 Δ