

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	378A-01-92M	1992	23	42

G U A R D R A I L S C H E D U L E			
STATION TO STATION	OFF- SET	606.3100 GUARDRAIL, TYPE 3	606.3110 RESET GUARDRAIL POST
UNIT USED		L.F.	EACH
343+00 - 344+40	LT.	160	
382+00 - 384+75	RT.	37.5	41
394+73 - 396+95	LT.	87.5	29
407+75 - 409+35	LT.	100	17
447+60 - 450+30	LT.	75	36
508+00 - 514+00	RT.	600	
514+00 - 520+00	RT.		89
521+35 - 536+50	LT.	1,515	
545+80 - 547+70	RT.	37.5	44
547+70 - 552+00	RT.	430	
557+10 - 559+00	RT.	37.5	30
561+90 - 570+50	LT.	860	
574+85 - 579+05	LT.	37.5	65
581+30 - 585+30	RT.	400	
592+05 - 596+20	RT.	37.5	65
598+50 - 611+00	LT.	1,250	
614+40 - 618+45	LT.	37.5	62
622+00 - 630+00	RT.	800	
633+10 - 637+95	RT.	37.5	75
642+35 - 646+25	LT.	37.5	60
649+00 - 655+70	RT.	670	
659+00 - 661+50	LT.	250	
679+00 - 688+35	LT.	935	
712+00 - 719+35	LT.	515	48
726+20 - 727+90	LT.	37.5	25
744+60 - 745+45	LT.	75	7
744+75 - 745+35	RT.		2
745+70 - 746+55	RT.		12
745+70 - 746+75	LT.	37.5	12
747+50 - 748+70	LT.	37.5	16
747+55 - 749+70	RT.	37.5	31
756+65 - 763+00	LT.	530	22
766+70 - 768+70	LT.	75	26
788+25 - 789+60	LT.	37.5	16
788+65 - 790+05	RT.	37.5	19
790+55 - 793+00	LT.	37.5	39
790+60 - 791+90	RT.	37.5	17
796+20 - 800+10	LT.	75	61
805+15 - 805+90	RT.	75	5
808+50 - 810+80	LT.	75	30
821+55 - 822+50	RT.	75	8
823+80 - 824+80	LT.	75	9
837+15 - 837+95	RT.	75	5
839+40 - 844+70	LT.	75	79
850+00 - 857+25	LT.	212.5	94
866+15 - 872+45	LT.	400	55
T O T A L		11,065	1,251

ORIGINAL PLAN	DESIGNED BY	DATE
NOTE BOOK	TRACED BY	
	QUANTITIES BY	
	CHECKED BY	

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION
GUARDRAIL SCHEDULE
HALEAKALA CRATER ROAD
RESURFACING
Haleakala National Park Boundary
Towards Kekaulike Avenue
Project No. 378A-01-92M
Date: May, 1992
SHEET No. 1 OF 1 SHEETS