

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	378A-01-92M	1992	37	42

INSTALLATION OF REFLECTOR MARKERS AND SUMMARY									
LOCATION	QUANTITY								
	RM2 W/FLEXIBLE DELINEATOR POST TYPE B		RM2 W/ STEEL POST		RM3 BI-DIRECTIONAL		RM3 W/ STEEL POST		RM4 w/ STEEL POST
	YELLOW	WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	WHITE	
Sta. 871+65± Rt. & Lt. to Sta. 871+75± Rt. & Lt. @ 10' o.c.	4								
Sta. 872+00± Rt. to Sta. 872+80± Rt. @ 80' o.c.		2							
Sta. 872+40± Lt.							1		
Sta. 874+10± Lt. to Sta. 875+70± Lt. @ 30' o.c.		7							
Sta. 337+00± RT. & Lt. to Sta. 877+50± RT. & Lt. 2/					120				
TOTALS	540	636	0	347	120	0	95	0	8

2/ Install RM3 Reflector Marker (Bi-Directional) on New Traffic Sign Post (Except Signs Installed Behind Guardrails), Facing the Traffic.

ROUTE MARKER SUMMARY				
SIGN ASSEMBLY	LOCATION	SIGN NO. AND MESSAGE	TYPE A ASSEMBLY	
			W/POST	W/O POST
SM-1	Sta. 338+50 Rt.	M1-6(378) EAST 378	1	
SM-2	Sta. 342+25 Lt.	M1-6(377) JCT 377	1	
SM-3	Sta. 614+50 Rt.	M1-6(378) EAST 378	1	
SM-4	Sta. 614+50 Lt.	M1-6(378) WEST 378	1	
SM-5	Sta. 778+00 Rt.	M1-6(378) EAST 378	1	
SM-6	Sta. 778+00 Lt.	M1-6(378) WEST 378	1	
TOTAL			6	0

CONSTRUCTION SIGN SUMMARY				
SIGN NO.	LOCATION	MESSAGE	W/POSTS	W/O POST
CW20-1d	Sta. 332+50± Rt.	ROAD CONSTRUCTION AHEAD	1	
CG20-2	Sta. 332+50± Lt.	END CONSTRUCTION	1	
CG20-2	Kekaulike Hwy. Sta. 5+00± Rt.	END CONSTRUCTION	1	
CW20-1d	Kekaulike Hwy. Sta. 5+00± Lt.	ROAD CONSTRUCTION AHEAD	1	
CG20-2	Sta. 882+47± Rt.	END CONSTRUCTION	1	
CW20-1d	Sta. 882+47± Lt.	ROAD CONSTRUCTION AHEAD	1	
TOTAL			6	0

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
	DRAWN BY	
	TRACED BY	
	NOTED BY	
NOTE BOOK	QUANTITIES BY	
	CHECKED BY	
No.		

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

REFLEC. & ROUTE MARKERS
CONST. SIGN SUMMARIES

HALEAKALA CRATER ROAD
RESURFACING
PROJECT NO. 378A-01-92M

Date: May, 1992

SHEET No. 114 OF 18 SHEETS