

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

ADDENDUM NO. 1

FOR

HALEAKALA CRATER ROAD BICYCLE PULLOUTS
FEDERAL-AID PROJECT NO. STP-0378(2)
DISTRICT OF MAKAWAO
ISLAND OF MAUI

FY 2011

Amend the bid documents as follows:

A. PROPOSAL SCHEDULE

1. Replace page P-8 dated 08/30/11 with the attached page P-8 dated 12/20/11.

B. PRE-BID MEETING

1. Attached are the December 20, 2011 Pre-Bid Meeting Summary, Agenda, and Attendance sheet.

Please acknowledge receipt of this Addendum No. 1 by recording the date of its receipt in the space provided on page P-4 of the Proposal.



GLENN M. OKIMOTO, Ph.D.
Director of Transportation

PROPOSAL SCHEDULE					
ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
209.1000	Installation, Maintenance, Monitoring and Removal of BMP	L.S.	L.S.	L.S.	\$
209.2000	Additional Water Pollution, Dust, and Erosion Control	F.A.	F.A.	F.A.	\$ 10,000.00
203.1000	Roadway Excavation	185	C.Y.	\$	\$
212.0010	Archaeological Monitoring	F.A.	F.A.	F.A.	\$ 10,000.00
312.0100	Hot Mix Glassphalt Base Course	230	Tons	\$	\$
401.0400	HMA Pavement, Mix No. IV	160	Tons	\$	\$
629.1010	4 - Inch White Guide Lines (Thermoplastic Extrusion)	1,040	L.F.	\$	\$
645.2000	Traffic Control	L.S.	L.S.	L.S.	\$
645.2100	Additional Police Officers Additional Traffic Control Devices, And Advertisement	F.A.	F.A.	F.A.	\$ 10,000.00
648.1000	Field-Posted Drawings	L.S.	L.S.	L.S.	\$
699.1000	Mobilization (Not to exceed 10% of the sum of all items Excluding the bid price of this Item, and force account items)	L.S.	L.S.	L.S.	\$
SUM OF ALL ITEMS					\$
NOTE: Bidders must complete all unit prices. Failure to do so may be grounds for rejection of bid.					

**PRE-BID CONFERENCE
FOR
HALEAKALA CRATER ROAD BICYCLE PULLOUT AREAS
Federa Aid Project No. STP-0378(2)**

**December 20, 2011@ 9:00am
DOT HIGHWAYS DIVISION
MAUI DISTRICT CONFERENCE ROOM**

Conference Summary

Conference began at 9:00am. The purpose was to brief prospective bidders on the project scope, allow questions and requests for clarification.

- I. Ms. Charlene Shibuya (DOT Design Project Manager / Construction Engineer) opened the meeting to the lone attendee. Sign-in sheet attached.
- II. Pre-Bid Conference Agenda was handed out. The Project Title, Project No., & brief scope of work as detailed in the meeting agenda, was described.
- III. Ms. Shibuya continued on to remind the prospective bidder of project specific requirements as outlined in the Agenda:

- Subsection 105.16(A) – Subcontract Requirements
- Subsection 108.08 – Liquidated Damages
- Subsection 108.09 – Rental Fees for Unauthorized Lane Closure
- Section 212 – Archaeological Monitoring
- Federal aid requirements
- Proposal Schedule page 8 errors
- Standard Specification Subsection 107.07 Overtime and Night Work

- IV. The meeting was opened to questions and requests for clarifications.

Arisumi Brothers, Inc.

1. Can you close lanes?

Response: Yes. You may do lane closures during off-peak hours from 8:30am to 3:00pm as noted in the bid documents.

2. Is there staging area space around the pullouts.

Response: Yes. The selected spots are wide shoulder areas that the downhill bicycle tour vans already stop and rest at.

**AGENDA
HIGHWAYS DIVISION
PRE-BID CONFERENCE FOR PROJECT
December 20, 2011 @ 9:00am**

**PROJECT TITLE: Haleakala Crater Road Bicycle Pullout Areas
Federal Aid Project No.STP-0378(2)**

Introduction (by STATE)

SCOPE OF WORK:

The project involves constructing paved shoulder pullouts at four (4) spot locations along Haleakala Crater Road (Route 378). The locations of the pullouts are at approximate Mile Posts 3.00, 4.00, 4.37, & 7.00. The scope of work consists of some sawcutting & removal of pavement, excavating, placing base & fill material, asphalt paving, shoulder dressing, and installing pavement markings.

The Contractor's attention is directed to the requirements of:

Special Provisions

Subsection 105.16 (A) Subcontract Requirements. Contractor shall perform with his/her own organization work amounting to not less than 30% of the total contract cost, except "Specialty Items" as listed in Special Provision pages 105-2a and 105-3a.

Subsection 108.08 – Liquidated Damages for failure to complete work on time is \$1,200 per working day.

Subsection 108.09 – Rental Fees for Unauthorized Lane Closure or Occupancy is \$500 for every fifteen minute increment per lane not to exceed \$5,500 per day.

Section 212 – Archaeological Monitoring; Contractor shall obtain the services of a qualified archaeological firm to create an archaeological monitoring plan that will address incorporating any historic properties which might be encountered during construction activities into the Programmatic Agreement (PA) survey planned for the Advance Technology Solar Telescope Project at the Haleakala Crater summit. Refer to August 22, 2011 State Historic Preservation Division letter inserted before the Proposal pages.

This is a federally aided project and all requirements as noted in the Special Provisions apply to the general contractor and subcontractors. Form FHWA-1273 (Rev.3-94) and Supplement to the Federal Form FHWA-1273 must be physically incorporated in all of the subcontractor agreements.

Proposal Schedule

Page 8 of the Proposal Schedule has errors in the approximate quantities for Items 312.0100 Hot Mix Glassphalt Base Course and 401.0400 HMA Pavement, Mix No.IV. Corrected quantities of 230 Tons and 160 Tons respectively, will be reflected on a new Proposal page to be distributed by Addendum No. 1.

Standard Specifications

Subsection 107.04 Overtime and Night Work. The contract Standard Specifications state that *"Overtime and nighttime work are permissible when approved by the Engineer in writing..."* However, due to concerns expressed by the US Fish and Wildlife Service regarding nighttime lighting disorienting seabirds, no nighttime work will be permitted.

Discussion

- 1) Contractor's questions on scope of work and/or requirements outlined above.
- 2) Contractor's Request for Information/Clarification

ADJOURNMENT

Participant Sign In:

[illegible]