

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
	DRAWN BY	
	TRACED BY	
	NOTED BY	
NOTE BOOK	QUANTITIES BY	
	CHECKED BY	
No.		

PAVEMENT STRIPING SUMMARY									
Station to Station	4" White E.P. Left (L.F.)	4" White E.P. Right (L.F.)	4" Single Yellow (L.F.)	4" Double Yellow (L.F.)	3" White (L.F.)	12" White (L.F.)	12" Yellow (L.F.)	Paint Arrow (Paint)	Paint Word (Paint)
3+82.47 - 4+42	70	70							
4+42 - 10+20	1484	1484							
10+20 - 20+73	285	158							
20+73 - 34+61	1388	1388							
34+61 - 35+87	120	158							
35+87 - 39+32	345	345							
39+32 - 40+23	91	158							
40+23 - 44+27	404	404							
4+00 - 17+00				1300					
17+00 - 23+00				1100	500	150	130	8 Ea.	4 Ea.
23+00 - 25+20			220						
31+00 - 40+00				1200	200	50	200	4 Ea.	2 Ea.
40+00 - 44+27				427					
TOTAL	4202	4174	220	4027	700	200	330	12	6

MONUMENTS		
Station	Type	Qty.
6+81.75	Brass Pin in Concrete	1
8+81.75	" " " "	1
11+47.34	" " " "	1
13+47.60	" " " "	1
35+22.18	City & County Survey Mon.	1
35+73.39	Brass Pin in Concrete	1
TOTAL		5

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	3400A-01-88M	1988	4	7

UTILITY, VALVES & MANHOLE			
Station	Item	Location	Qty.
11+03	WMH	95 15.4'R	1
19+98	WV	19.7'L	1
19+99	WV	10.1'R	1
20+02	WV	12.7'R	1
20+02	WV	10.3'R	1
20+10	WV	10.2'R	1
20+14	WV	12.7'R	1
35+16	WV	15.1'R	1
35+20	WV	21.2'R	1
35+22	WV	14.7'R	1
35+27	SDMH	32.2'R	1
37+01	WMH	15.1'R	1
39+27	WV	13.2'R	1
39+32	WV	12.8'R	1
39+89	WV	15.6'R	1
39+92	WV	19.8'R	1
39+97	WV	15.9'R	1
TOTAL			17

PAVEMENT MARKER SUMMARY				
Station to Station	Type CL (Each)	Type DL (Each)	Type HL (Each)	Type J (Each)
4+00 - 17+00		66		
17+00 - 23+00	40	22	36	
23+00 - 25+20		6	6	24
25+20 - 31+00		15		60
31+00 - 40+00	18	8	60	
40+00 - 44+27		22		
TOTAL	58	139	102	84

STATE OF HAWAII	
DEPARTMENT OF TRANSPORTATION	
HIGHWAYS DIVISION	
SUMMARIES - PAV'T. MARKERS & STRIP'G., MON., VALVES & MANHOLES	
WAIHEHU BEACH RD. RESURFACING KAHEKILI HIGHWAY TO KEALII DRIVE	
PROJ. No. 3400A-01-88M	
NO SCALE	DATE: MAR. 1988
SHEET No. 1 OF 1 SHEETS	