

GENERAL NOTES

1. The Improvements consist of constructing concrete and bituminous sidewalks, curbs, and wheelchair ramps, paving shoulders with asphalt concrete, reconstructing existing drop inlets, installing signs and pavement markers, and striping.
2. The existence and location of underground utilities and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of the work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.
3. The exact limits of concrete and bituminous sidewalks shall be determined in the field by the Engineer.
4. Dressing of slopes and sidewalks shall consist of clearing, grubbing, grading and reshaping sidewalk edges and border area swales as shown on the plans and/or as directed by the Engineer. This work will not be paid for separately, but shall be considered incidental to various contract items.
5. Contractor shall provide for access to and from all existing driveways and streets at all times.
6. Contractor shall provide safe and all-weather temporary pedestrian footpath between Kaahumanu Avenue to Wakea Avenue while sidewalks are being constructed and cured. This work will be incidental to various contract items.
7. All sawcutting work shall be considered incidental to Roadway Excavation.
8. Relocation of existing power poles will be done by others.

UTILITY NOTES

WATER CONSTRUCTION NOTES

1. Unless otherwise specified, all materials and construction of water system facilities and appurtenances shall be in accordance with the STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, dated 1985, as amended, of the Hawaii Highways Division, Department of Transportation and the County of Maui, Department of Water Supply's "Water System Standards", Volume I, dated 1985, and the "Approved Material List and Standard Details for Water System Construction", Volume 2, dated 1985 and all subsequent amendments and additions.
2. The Contractor shall notify the Dept. of Water Supply in writing one week prior to commencing work.
3. Any adjustments to the existing water system required during construction to meet requirements of D.W.S. Standards, whether shown on the plans or not, shall be done by the Contractor at no cost to the D.W.S.

MAUI ELECTRIC CO., LTD. NOTES

1. The location of MECO's overhead and underground facilities shown on the plans are from existing records with varying degrees of accuracy and are not guaranteed as shown. The Contractor shall exercise extreme caution whenever construction crosses or is in close proximity of underground lines and shall maintain adequate clearance when operating equipment within or under any overhead lines.
2. The Contractor shall comply with the State of Hawaii's Occupational Safety and Health Law (DOSH).
3. For verification of underground lines or for assistance in supporting and protecting these lines, the Contractor shall call MECO a minimum of 72 hours in advance.
4. The Contractor shall be liable for any damages to MECO facilities and shall immediately report such damages to MECO.

HAWAIIAN TELEPHONE CO. (HTCO) NOTES

1. *The location of existing Hawaiian Telephone Company underground facilities are approximate only. The Contractor shall verify their location and depth of the facilities. Any damages to the underground facilities as a result of his operations shall be repaired by the Contractor.*
2. *The Contractor shall notify Hawaiian Telephone Company 72 hours prior to the start of excavation for field location of Hawaiian Telephone Company underground facilities.*

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	MG-3500(2)	1989	6	16

ORIGINAL PLAN	SURVEY PLOTTED BY _____ DATE _____
NOTE BOOK	

No. _____	

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

GENERAL AND UTILITY NOTES

PUUNENE AVENUE SIDEWALKS
Kaahumanu Ave. tow. Kulhelani Hwy.
FED. AID PROJ. NO. MG-3500(2)

Date: Aug., 1988

SHEET No. / OF / SHEETS