

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	HES-STP-3500(3)	1994	3	7

GENERAL NOTES

- The scope of work for this project consists of constructing left turn lanes and paved shoulders; widening the existing roadway; adjusting the existing sidewalk; and installing signs and pavement markings.*
- The Contractor's attention is directed to Subsection 107.13 - Public Convenience and Safety; Section 645 - Traffic Control and Subsection 104.04 Maintenance of Traffic.*
- At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.*
- The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of the work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.*
- The Contractor shall notify the State in writing, two (2) weeks prior to starting paving operations.*
- Dressing of shoulder shall consist of clearing, grubbing, grading, reshaping and compacting the unpaved shoulders with suitable excavated material as shown on the plans and/or as directed by the Engineer. This work shall be considered incidental to the various contract items.*
- Existing drainage system will be functional at all times during construction. Contractor is to furnish materials, equipment, labor, tools and incidentals necessary to accomplish maintenance of flow, the cost of which shall be considered incidental to the various contract items.*
- Contractor shall provide for access to and from all existing driveways and streets at all times.*
- All saw cutting of existing pavement shall not be measured or paid for separately, but shall be considered incidental to various contract items.*
- Payment for relocation of trees, mail boxes, structures and obstructions, etc. will not be paid for separately but shall be considered incidental to various items of work.*
- The State intends to have all construction completed in a safe and timely manner. Therefore, the Contractor shall coordinate his work with Contractor(s) for another project, Puunene Avenue Intersection Improvements at Kamehameha Avenue, Project No. HES-STP-3500(4).*
- Smooth riding connections shall be constructed at areas where the new pavement meets the existing pavement, connecting approaches, side streets and driveways as shown on the plans and/or as directed by the Engineer.*

LEGEND

- e— Existing Electrical Line
- s— Existing Sewer Line
- w—8"— Existing Water Line
- °pp Existing Power Pole
- °wv Existing Water Valve
- ✧fh Existing Fire Hydrant
- °smh Existing Sewer Manhole
- cdl Existing Concrete Drop Inlet

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTE BOOK	DRAWN BY	7/22/93
Signs, Plans	DESIGNED BY	
	CHECKED BY	

STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION		
GENERAL NOTES & LEGEND		
PUUNENE AVENUE IMPROVEMENTS		
Wakea Ave. Towards Ai'ai St.		
Fed. Aid Project No. HES-STP-3500(3)		
Date: August, 1993		
SHEET No. 1 OF 1 SHEETS		