

**STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION**

ADDENDUM NO. 4

FOR

**Kahului Airport Access Road, Phase I
PROJECT NO. Federal- Aid NH-0380(10)
DISTRICT OF Wailuku
ISLAND OF MAUI**

FY 2013

The following amendments shall be made to the bid documents:

A. SPECIFICATIONS

1. Replace Table of Contents dated r03/25/13 with the attached Table of Contents dated r04/15/13.
2. Replace Section 617, PLANTING SOIL dated 09/14/12, with the attached Section 617, PLANTING SOIL, Pages 617-1a-2a dated 04/15/13.
3. Add Section 630, TRAFFIC CONTROL GUIDE SIGNS, Page 630-1a dated 04/15/13.

B. PROPOSAL

1. Replace Pages P-8 through P-21 dated r04/08/13 with the attached Pages P-8 to P-21 dated r04/15/13.

C. PLANS

1. Replace Plan Sheet Nos. 70, 71, 72, 73, 74, 75, 76, 77, 79, 80, 107, 108, 110, 111, 115, 142, 143, 144, 145, 146, 147, 148, 150, 153, 156, 157, 158, 159, 160, and 161 with the attached Plan Sheet Nos. ADD. 70, ADD. 71, ADD. 72, ADD. 73, ADD. 74, ADD. 75, ADD. 76, ADD. 77, ADD. 79, ADD. 80, ADD. 107, ADD. 108, ADD. 110, ADD. 111, ADD. 115, ADD. 142, ADD. 143, ADD. 144, ADD. 145, ADD. 146, ADD. 147, ADD. 148, ADD. 150, ADD. 153, ADD. 156, ADD. 157, ADD. 158, ADD. 159, ADD. 160, and ADD. 161.

Addendum No. 4
4/15/13

Please acknowledge receipt of this Addendum No. 4 by recording the date of its receipt in the space provided on Page P-4 of the Proposal.


GLENN M. OKIMOTO, Ph.D
Director of Transportation

Addendum No. 4
4/15/13

TABLE OF CONTENTS

Notice To Bidders

Instructions for Contractor's Licensing

Notice of Requirement for Affirmative Action to Ensure
Equal Employment Opportunity (Executive Order 11246)

Disadvantaged Business Enterprise (DBE) Requirements

Required Federal-Aid Contract Provisions

Special Provisions Title Page

Special Provisions:

DIVISION 100 - GENERAL PROVISIONS		
Section	Description	Pages
102	Bidding Requirements and Conditions	102-1a – 102-8a
103	Award And Execution of Contract	103-1a – 103-5a
104	Scope of Work	104-1a – 104-2a
105	Control of Work	105-1a – 105-3a
106	Material Restrictions and Requirements	106-1a
107	Legal Relations and Responsibility To Public	107-1a
108	Prosecution And Progress	108-1a – 108-2a
109	Measurement and Payment	109-1a

DIVISION 200 - EARTHWORK		
Section	Description	Pages
203	Excavation And Embankment	203-1a
209	Temporary Water Pollution, Dust, and Erosion Control	209-1a
212	Archaeological Monitoring	212-1a – 212-5a

DIVISION 300 - BASES		
Section	Description	Pages
301	Hot Mix Asphalt Base Course	301-1a – 301-2a
304	Aggregate Base Course	304-1a

DIVISION 400 - PAVEMENTS		
Section	Description	Pages
401	Hot Mix Asphalt Pavement	401-1a – 401-4a
411	Portland Cement Concrete Pavement	411-1a
415	Cold Planing of Existing Pavement	415-1a

DIVISION 600 - INCIDENTAL CONSTRUCTION		
Section	Description	Pages
603	Culverts and Storm Drains	603-1a
606	Guardrail	606-1a
613	Centerline and Reference Survey Monuments	613-1a
616	Irrigation System	616-1a
617	Planting Soil	617-1a – 617-2a
619	Planting	619-1a – 619-5a
622	Roadway and Sign Lighting System	622-1a – 622-2a
623	Traffic Signal System	623-1a – 623-6a
624	Water System	624-1a
629	Pavement Markings	629-1a
630	Traffic Control Guide Signs	630-1a
631	Traffic Control Regulatory, Warning, and Miscellaneous Signs	631-1a
634	Portland Cement Concrete Sidewalks	634-1a
642	Landscape Maintenance	642-1a
650	Curb Ramps	650-1a
697	Project Web Page	697-1a – 697-2a
698	Training	698-1a – 698-3a
699	Mobilization	699-1a

DIVISION 700 – MATERIALS		
Section	Description	Pages
712	Miscellaneous	
	Frames, Grates, Covers and Ladder Rungs	712.07-1a
717	Cullet And Cullet-Made Materials	717-1a – 717-2a
721	Triaxial Geogrid	721-1a – 721-4a
750	Traffic Control Sign and Marker Materials	750-1a
755	Pavement Marking Materials	755-1a
760	Roadway and Sign Lighting Systems Materials	760-1a – 760-6a
770	Traffic Signal Materials	770-1a – 770-10a

Requirement of Chapter 104, HRS
Wages and Hours of Employees on Public Works Law

Federal Wage Rates

Proposal Title Page

Proposal	P-1 – P-7
Proposal Schedule	P-8 - P- 22
Supplement to Proposal Schedule	P-23 - P- 26

Confirmation by DBE

Surety Bid Bond

Sample Forms

Contract

Performance Bond (Surety)

Performance Bond

Labor and Material Payment Bond (Surety)

Labor and Material Payment Bond

Disclosure of Lobbying Activities
Standard Form - LLL and LLL-A

Statement of Compliance
Form WH-348

DBE Participation Report & Prompt Payment Certification

Chapter 104, HRS Compliance Certificate

Certification of Compliance for Final Payment

END OF TABLE OF CONTENTS

SECTION 617 - PLANTING SOIL

Make the following amendments to said Sections:

(I) Amend **Section 617.02 Materials**, from line 8 to line 63 to read as follows:

"(A) Selected Material. Existing topsoil obtained from within the Contract Zone Limits shall be considered by the Engineer as selected material for planting soil. Existing topsoil approved by the Engineer shall be removed, stockpiled, and used. Stockpile in area designated by the Engineer. If there is insufficient topsoil to meet the design intent of the Drawings, imported topsoil shall be used. Material unsuitable for planting soil shall be disposed of in accordance with Section 203 - Excavation and Embankment.

(B) Imported Planting Soil. Imported planting soil shall be topsoil obtained from sources outside the Contract Zone Limits that has been accepted by the Engineer.

(C) Qualities of Planting Soil. Planting soil texture and physical properties shall be conducive to proper plant growth. Topsoil shall contain sufficient quantities of available nitrogen, phosphorus, potassium, calcium and magnesium to support normal plant growth, or be amendable in accordance with the soil analysis recommendations. Planting soil shall be free of deleterious substances, weeds, rocks, gravel and debris.

(1) Physical Properties. Soils with high proportions of silt and clay, or high proportions of material falling under the "gravel" classification, shall be rejected. Topsoil shall not be screened subsoil. Material locally identified as "red" soil shall be rejected. Unacceptable soil classifications are: clay (C), sandy clay (SC), silty clay (SiC), silt (Si), sand (S), and loamy sand (LS).

(a) Sand. Less than 70%.

(b) Silt. Less than 70%.

(c) Clay: Less than 30%.

(2) Chemistry. Imported planting soil shall comply, or be amendable to comply, with the following:

46 (a) Salinity. Saturation Extract Conductivity (EC) less
47 than 3.0 mmhos/cm.

48 (b) Sodium. Sodium Absorption Rate (SAR) less than
49 1.0 part per million.
50

51 (c) Reaction. Imported planting soil shall have pH of
52 saturated paste of 5.5 to 7.0.
53

54
55 **(D) Testing.** Representative samples of existing soil obtained from
56 within the Contract Zone Limits, or imported planting soil, shall be
57 submitted to University of Hawaii Agricultural Extension Service, or a
58 laboratory acceptable to the Engineer, for analysis and
59 recommendations for amendments and fertilizer to bring the planting soil
60 to acceptable levels. Test results and amendment and fertilization
61 schedule shall be presented to the Engineer for review and acceptance
62 before stockpiling existing topsoil, or obtaining, excavating, or
63 transporting imported planting soil. Tests shall include and not be limited
64 to:

65
66 **(1) Physical Properties.**

67 (a) Particle size distribution: Proportions of sand, silt
68 and clay and resulting soil classification.
69

70
71 **(2) Chemistry.**

72 (a) Nutrient levels. Available phosphorus (P),
73 potassium (K), calcium (Ca), Nitrogen (N) and magnesium
74 (Mg) with recommendations for appropriate fertilizers and
75 liming material.
76

77 (b) Soil salinity.
78

79 (c) Soil pH.
80

1 **SECTION 630 – TRAFFIC CONTROL GUIDE SIGNS**

2
3 Make the following amendments to said Sections:

4
5
6 **(I) Amend Section 630.04 Measurement** from lines 204 to 221 to read as
7 follows:

8
9 **"630.04 Measurement.**

10
11 **(A)** Traffic Control Guide Signs will be paid on a lump sum basis.
12 Measurement for payment will not apply.

13
14 **(II) Amend Section 630.05 Payment,** from lines 223 to 303 to read as
15 follows:

16
17 **"630.05 Payment.** The Engineer will pay for the traffic control guide signs on a
18 contract lump sum basis. Payment will be full compensation for the work
19 prescribed in this section and the contract documents.

20
21 The Engineer will pay for the following pay item when included in the
22 proposal schedule:

23
24 **Pay Item** **Pay Unit**
25
26 Traffic Control Guide Signs Lump sum

27
28 The Engineer will not pay separately for sign panel, posts, arms, footings,
29 relocation of existing sign, breakaway steel post and foundation, excavation for
30 footing, concrete in footings, reinforcing steel, and other items of work to
31 complete the installation of traffic control guide signs as shown on the plans and
32 will consider the cost for those items as included in the unit price for traffic control
33 guide signs."

34
35 **END OF SECTION 630**

PROPOSAL SCHEDULE					
ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
201.0100	Clearing and Grubbing	L.S.	L.S.	L.S.	\$ _____
203.0100	Roadway Excavation	67,050	C.Y.	\$ _____	\$ _____
203.0200	Selected Material for Planting Soil	L.S.	L.S.	L.S.	\$ _____
205.0100	Structural Excavation for Retaining Walls and End Posts	L.S.	L.S.	L.S.	\$ _____
205.0200	Structural Backfill for Retaining Walls	L.S.	L.S.	L.S.	\$ _____
205.0300	Filter Material	L.S.	L.S.	L.S.	\$ _____
206.0100	Excavation for Drainage Systems	L.S.	L.S.	L.S.	\$ _____
206.0200	Excavation for Detention Basins	L.S.	L.S.	L.S.	\$ _____
209.0100	Installation, Maintenance, Monitoring, and Removal of BMP	L.S.	L.S.	L.S.	\$ _____
209.0200	Additional Water Pollution, Dust, and Erosion Control	F.A.	F.A.	F.A.	\$ <u>25,000</u>
212.0100	Archaeological Monitoring	F.A.	F.A.	F.A.	\$ <u>150,000</u>
301.0100	Hot Mix Asphalt Base Course	L.S.	L.S.	L.S.	\$ _____
304.0100	Aggregate Base Course	L.S.	L.S.	L.S.	\$ _____
305.0100	Aggregate Subbase	L.S.	L.S.	L.S.	\$ _____

NH-0380(10)

r04/15/13

P-8

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
401.0100	HMA Pavement, Mix No. IV	L.S.	L.S.	L.S.	\$ _____
411.0100	Concrete Pavement	L.S.	L.S.	L.S.	\$ _____
415.0100	Cold Planing	L.S.	L.S.	L.S.	\$ _____
503.0100	Concrete for Retaining Walls	L.S.	L.S.	L.S.	\$ _____
503.0200	Concrete in Retaining Wall Foundation	L.S.	L.S.	L.S.	\$ _____
503.0300	Concrete Railing	L.S.	L.S.	L.S.	\$ _____
503.0400	Concrete End Post Railing	L.S.	L.S.	L.S.	\$ _____
503.0500	Concrete Inlet/Outlet Structure for 24-Inch Drain	L.S.	L.S.	L.S.	\$ _____
503.0600	Concrete Inlet/Outlet Structure for 36-Inch Drain	L.S.	L.S.	L.S.	\$ _____
503.0700	Concrete Inlet/Outlet Structure for 48-Inch Drain	L.S.	L.S.	L.S.	\$ _____
503.0800	Concrete Inlet/Outlet Structure for 66-Inch Drain	L.S.	L.S.	L.S.	\$ _____
507.0100	Pedestrian Railing	L.S.	L.S.	L.S.	\$ _____
602.0100	Reinforcing Steel for Retaining Walls	L.S.	L.S.	L.S.	\$ _____
602.0200	Reinforcing Steel for Retaining Wall Footings	L.S.	L.S.	L.S.	\$ _____

NH-0380(10)

r04/15/13

P-9

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
603.0100	24-Inch Reinforced Concrete Pipe, Class III or 24-Inch High Density Polyethylene Pipe, Type S	L.S.	L.S.	L.S.	\$ _____
603.0200	36-Inch Reinforced Concrete Pipe, Class III or 36-Inch High Density Polyethylene Pipe, Type S	L.S.	L.S.	L.S.	\$ _____
603.0300	48-Inch Reinforced Concrete Pipe, Class III or 48-Inch High Density Polyethylene Pipe, Type S	L.S.	L.S.	L.S.	\$ _____
603.0400	54-Inch Reinforced Concrete Pipe, Class III or 54-Inch High Density Polyethylene Pipe, Type S	L.S.	L.S.	L.S.	\$ _____
603.0500	66-Inch Reinforced Concrete Pipe, Class III	L.S.	L.S.	L.S.	\$ _____
604.0100	Type C Storm Drain Manhole, 4.00 feet to 4.99 feet	3	Each	\$ _____	\$ _____
604.0200	Type C Storm Drain Manhole, 5.00 feet to 5.99 feet	3	Each	\$ _____	\$ _____
604.0300	Type C Storm Drain Manhole, 7.00 feet to 7.99 feet	3	Each	\$ _____	\$ _____
604.0400	Type C Storm Drain Manhole, 10.00 feet to 10.99 feet	1	Each	\$ _____	\$ _____
604.0500	Type C Storm Drain Manhole, 13.00 feet to 13.99 feet	1	Each	\$ _____	\$ _____
604.0600	Type 61614P Inlet, 3.00 feet to 3.99 feet	1	Each	\$ _____	\$ _____
604.0700	Type 61614P Inlet, 4.00 feet to 4.99 feet	1	Each	\$ _____	\$ _____
604.0800	Type 61614P Inlet, 5.00 feet to 5.99 feet	4	Each	\$ _____	\$ _____
604.0900	Type 61614P Inlet, 6.00 feet to 6.99 feet	18	Each	\$ _____	\$ _____

NH-0380(10)

r04/15/13

P-10

PROPOSAL SCHEDULE					
ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
604.1000	Type 61614P Inlet, 7.00 feet to 7.99 feet	10	Each	\$ _____	\$ _____
604.1100	Type 61614P Inlet, 8.00 feet to 8.99 feet	6	Each	\$ _____	\$ _____
604.1200	Type 61614P Inlet, 9.00 feet to 9.99 feet	7	Each	\$ _____	\$ _____
604.1300	Type 61614P Inlet, 10.00 feet to 10.99 feet	1	Each	\$ _____	\$ _____
604.1400	Type 61614P Inlet, 11.00 feet to 11.99 feet	1	Each	\$ _____	\$ _____
604.1500	Type 61616P Inlet, 9.00 feet to 9.99 feet	4	Each	\$ _____	\$ _____
604.1600	Type 61616P Inlet, 10.00 feet to 10.99 feet	2	Each	\$ _____	\$ _____
604.1700	Type 61616P Inlet, 11.00 feet to 11.99 feet	3	Each	\$ _____	\$ _____
604.1800	Type 61616P Inlet, 12.00 feet to 12.99 feet	1	Each	\$ _____	\$ _____
604.1900	Type 61616P Inlet, 13.00 feet to 13.99 feet	2	Each	\$ _____	\$ _____
604.2000	Type C1 Catch Basin, 6.00 feet to 6.99 feet	1	Each	\$ _____	\$ _____
604.2100	Adjusting Drain Manhole Cast Iron Frame and Cover	1	Each	\$ _____	\$ _____
605.0100	6-Inch Underdrain	L.S.	L.S.	L.S.	\$ _____
605.0200	Cleanout	L.S.	L.S.	L.S.	\$ _____

NH-0380(10)
 r04/15/13
 P-11

PROPOSAL SCHEDULE					
ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
605.0300	Underdrain Outlet Connection to Grated Drop Inlet	L.S.	L.S.	L.S.	\$ _____
605.0400	Underdrain Outlet Connection to Catch Basin	L.S.	L.S.	L.S.	\$ _____
605.0500	Underdrain Outlet to Daylight with GRP Outlet	L.S.	L.S.	L.S.	\$ _____
606.0100	Guardrail, Type 3-Single with Steel Post	L.S.	L.S.	L.S.	\$ _____
606.0200	Guardrail, Type 3-Modified Thrie Beam with Steel Post	L.S.	L.S.	L.S.	\$ _____
606.0300	Portable Concrete Barrier	L.S.	L.S.	L.S.	\$ _____
606.0400	Terminal Section, Type FLEAT-350 / ET Plus TL-3	L.S.	L.S.	L.S.	\$ _____
606.0500	Terminal Section, Type A End Post	L.S.	L.S.	L.S.	\$ _____
607.0100	6-Foot Chain Link Fence With Top Rail and Concrete Footings	L.S.	L.S.	L.S.	\$ _____
607.0200	Chain Link Gate, 6-Foot High and 14 Feet Wide	L.S.	L.S.	L.S.	\$ _____
612.0100	Grouted Rubble Paving for Underdrain Outlet to Daylight	L.S.	L.S.	L.S.	\$ _____
613.0100	Centerline and Reference Survey Monument	L.S.	L.S.	L.S.	\$ _____
616.0100	Temporary Irrigation	L.S.	L.S.	L.S.	\$ _____
619.0100	Cinder amendment, 2" depth for Ilima planting beds	L.S.	L.S.	L.S.	\$ _____

NH-0380(10)
 r04/15/13
 P-12

PROPOSAL SCHEDULE					
ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
619.0200	Soil preparation with organic amendments (ground cover and shrubs areas only.)	L.S.	L.S.	L.S.	\$ _____
619.0300	Kou tree, 45 gal.	L.S.	L.S.	L.S.	\$ _____
619.0400	Hala tree, field specimen	L.S.	L.S.	L.S.	\$ _____
619.0500	Monkeypod tree, field specimen	L.S.	L.S.	L.S.	\$ _____
619.0600	Milo tree, 45 gal.	L.S.	L.S.	L.S.	\$ _____
619.0700	Beach Naupaka, 1 gal.	L.S.	L.S.	L.S.	\$ _____
619.0800	Ilima papa, 4" pot at 12" o.c.	L.S.	L.S.	L.S.	\$ _____
619.0900	Pohinahina, 4" pot at 18" o.c.	L.S.	L.S.	L.S.	\$ _____
619.1000	Landscape edging (1x4 recycled plastic)	L.S.	L.S.	L.S.	\$ _____
619.1100	Organic Cover Mulch	L.S.	L.S.	L.S.	\$ _____
622.0100	LED Street Light Concrete Footing	L.S.	L.S.	L.S.	\$ _____
622.0200	LED Street Light and Pole	L.S.	L.S.	L.S.	\$ _____
622.0300	Handhole 2' x 4'	L.S.	L.S.	L.S.	\$ _____
622.0400	Concrete Encased Ductline for Street Lights	L.S.	L.S.	L.S.	\$ _____

PROPOSAL SCHEDULE					
ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
622.0500	Concrete Encased Ductline for Service	L.S.	L.S.	L.S.	\$ _____
622.0600	Wiring for Street Lights	L.S.	L.S.	L.S.	\$ _____
622.0700	Concrete Pad for MECO Transformer	L.S.	L.S.	L.S.	\$ _____
622.0800	Electrical Distribution Equipment	L.S.	L.S.	L.S.	\$ _____
622.0900	MECO Service Charge	F.A.	F.A.	F.A.	\$ <u>50,000</u>
622.1000	Hawaiian Telcom Service Charge	F.A.	F.A.	F.A.	\$ <u>50,000</u>
623.2000	Furnish And Install Controller Assembly (Model 170 Traffic Signal Controller Unit, Type 332A Cabinet And Auxiliary Equipment)	2	Each	\$ _____	\$ _____
623.2012	Type I Traffic Signal Standard, H=10 Ft	13	Each	\$ _____	\$ _____
623.2021	Type II Traffic Signal Standard With 41-Foot Mast Arm	1	Each	\$ _____	\$ _____
623.2022	Type II Traffic Signal Standard With 47-Foot Mast Arm	1	Each	\$ _____	\$ _____
623.2023	Type II Traffic Signal Standard With 53-Foot Mast Arm	1	Each	\$ _____	\$ _____
623.2024	Type II Traffic Signal Standard With 55-Foot Mast Arm	1	Each	\$ _____	\$ _____
623.2025	Type II Traffic Signal Standard With 56-Foot Mast Arm	1	Each	\$ _____	\$ _____

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
623.2026	Type II Traffic Signal Standard With 60-Foot Mast Arm	3	Each	\$ _____	\$ _____
623.2040	Foundation For Type I Signal Standard	13	Each	\$ _____	\$ _____
623.2050	Foundation For Type II Signal Standard	8	Each	\$ _____	\$ _____
623.2070	Foundation For Controller Cabinet	2	Each	\$ _____	\$ _____
623.3001	Traffic Signal Assembly, (1-Way, 12-Inch, 1-3 Section Vertical With Type TP-1W Mounting)	5	Each	\$ _____	\$ _____
623.3002	Traffic Signal Assembly, (2-Way, 12-Inch, 2-3 Section Vertical Type TP-2W Mounting)	5	Each	\$ _____	\$ _____
623.3003	Traffic Signal Assembly, (3-Way, 12-Inch, 3-3 Section Vertical With Type TP-3W Mounting)	3	Each	\$ _____	\$ _____
623.3004	Traffic Signal Assembly, (1-Way, 12-Inch, 1-3 Section Vertical With Type B-1W Mounting)	1	Each	\$ _____	\$ _____
623.3005	Traffic Signal Assembly with Backplate, (1-Way, 12-Inch, 1-3 Section Vertical With Type MA-1W(1) Mounting)	17	Each	\$ _____	\$ _____
623.3006	Traffic Signal Assembly with Backplate, (1-Way, 12-Inch, 1-3 Section Vertical, Programmable Visibility Head With Type MA-1W(1) Mounting)	13	Each	\$ _____	\$ _____
623.3007	Traffic Signal Assembly with Backplate, (1-Way, 12-Inch, 1-4 Section Vertical, Programmable Visibility Head With Type MA-1W(1) Mounting)	2	Each	\$ _____	\$ _____
623.3080	EVP Optical Receiver With Mast Arm Mounting	8	Each	\$ _____	\$ _____

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
623.4021	Pedestrian Signal Assembly, (1-Way, 12-Inch, One Vertical With Type B-1W Mounting)	2	Each	\$ _____	\$ _____
623.4022	Pedestrian Signal Assembly, (1-Way, 12-Inch, One Vertical With Type C-1W Mounting)	12	Each	\$ _____	\$ _____
623.4040	Pedestrian Push Button With Instruction Sign	14	Each	\$ _____	\$ _____
623.5000	Traffic Signal Ductline, One 2-Inch Conduit, Sch 40 PVC, Concrete Encased	1650	Lin Ft	\$ _____	\$ _____
623.5001	Traffic Signal Ductline, Two 2-Inch Conduit, Sch 40 PVC, Concrete Encased	6800	Lin Ft	\$ _____	\$ _____
623.5002	Traffic Signal Ductline, Four 2-Inch Conduit, Sch 40 PVC, Concrete Encased	350	Lin Ft	\$ _____	\$ _____
623.5003	Traffic Signal Ductline, Five 2-Inch Conduit, Sch 40 PVC, Concrete Encased	650	Lin Ft	\$ _____	\$ _____
623.5004	Traffic Signal Ductline, Six 2-inch Conduit, Sch 40 PVC, Concrete Encased	350	Lin Ft	\$ _____	\$ _____
623.5005	Traffic Signal Ductline, Seven 2-inch Conduit, Sch 40 PVC, Concrete Encased	175	Lin Ft	\$ _____	\$ _____
623.5006	Traffic Signal Ductline, Two 3-inch Conduit and Four 2-inch Conduit, Sch 40 PVC, concrete encased	10	Lin Ft	\$ _____	\$ _____
623.5007	Traffic Signal Ductline, Four 3-inch Conduit and Three 2-inch Conduit, Sch 40 PVC, concrete encased	10	Lin Ft	\$ _____	\$ _____
623.6000	Type A Pullbox	9	Each	\$ _____	\$ _____

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
623.6010	Type B Pullbox	45	Each	\$ _____	\$ _____
623.6020	Type C Pullbox	2	Each	\$ _____	\$ _____
623.7002	No. 14, 2-Conductor Loop Detector Lead-In Cable	9600	Lin Ft	\$ _____	\$ _____
623.7026	No. 14, 26-Conductor Traffic Control Cable	3400	Lin Ft	\$ _____	\$ _____
623.7028	No. 19, 24-Conductor (12-Pair) Traffic Control Interconnect Cable	7100	Lin Ft	\$ _____	\$ _____
623.7029	No. 6, 3-Conductor Power Cable	100	Lin Ft	\$ _____	\$ _____
623.7040	EVP Cable	2000	Lin Ft	\$ _____	\$ _____
623.7042	Loop Detector Sensing Unit (6 Ft X 6 Ft) One Loops	15	Each	\$ _____	\$ _____
623.7043	Loop Detector Sensing Unit (6 Ft X 6 Ft) Two Loops	10	Each	\$ _____	\$ _____
623.7044	Loop Detector Sensing Unit (6 Ft X 6 Ft) Four Loops	5	Each	\$ _____	\$ _____
623.7045	Loop Detector Sensing Unit (6 Ft X 6 Ft) Six Loops	17	Each	\$ _____	\$ _____
624.0100	Water Systems	L.S.	L.S.	L.S.	\$ _____
626.0100	Adjusting Water Valve Box Frame and Cover	L.S.	L.S.	L.S.	\$ _____
626.0200	Adjusting Sewer Manhole Frame and Cover	L.S.	L.S.	L.S.	\$ _____

PROPOSAL SCHEDULE					
ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
626.0300	Adjusting Water Manhole Frame and Cover	L.S.	L.S.	L.S.	\$ _____
626.0400	Adjusting Sewer Cleanout Frame and Cover	L.S.	L.S.	L.S.	\$ _____
629.0100	4-Inch Pavement Striping (Tape-Type I or Thermoplastic Extrusion)	L.S.	L.S.	L.S.	\$ _____
629.0200	4-Inch Pavement Striping (Tape-Type II or Thermoplastic Extrusion)	L.S.	L.S.	L.S.	\$ _____
629.0300	4-Inch Pavement Striping (Tape-Type III or Thermoplastic Extrusion)	L.S.	L.S.	L.S.	\$ _____
629.0400	8-Inch Pavement Striping (Tape-Type I or Thermoplastic Extrusion)	L.S.	L.S.	L.S.	\$ _____
629.0500	8-Inch Pavement Striping (Tape-Type II or Thermoplastic Extrusion)	L.S.	L.S.	L.S.	\$ _____
629.0600	12-Inch Pavement Striping (Tape-Type II or Thermoplastic Extrusion)	L.S.	L.S.	L.S.	\$ _____
629.0700	12-Inch Pavement Striping (Tape-Type III or Thermoplastic Extrusion)	L.S.	L.S.	L.S.	\$ _____
629.0800	Crosswalk Marking (Tape, Type III or Thermoplastic Extrusion)	L.S.	L.S.	L.S.	\$ _____
629.0900	Pavement Arrows (Tape-Type III, or Thermoplastic Extrusion)	L.S.	L.S.	L.S.	\$ _____
629.1000	Pavement Words (Tape-Type III, or Thermoplastic Extrusion)	L.S.	L.S.	L.S.	\$ _____
629.1100	Type A Pavement Markers	L.S.	L.S.	L.S.	\$ _____

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
629.1200	Type C Pavement Markers	L.S.	L.S.	L.S.	\$ _____
629.1300	Type D Pavement Markers	L.S.	L.S.	L.S.	\$ _____
629.1400	Type H Pavement Markers	L.S.	L.S.	L.S.	\$ _____
630.0100	Destination and Guide Signs	L.S.	L.S.	L.S.	\$ _____
631.0100	Regulatory Signs (10 SQ FT or Less)	L.S.	L.S.	L.S.	\$ _____
631.0200	Regulatory Signs (Greater than 10 SQ FT)	L.S.	L.S.	L.S.	\$ _____
634.0100	Portland Cement Concrete Sidewalk	L.S.	L.S.	L.S.	\$ _____
638.0100	Gutter, Type 61614	L.S.	L.S.	L.S.	\$ _____
638.0200	Gutter, Type 61616	L.S.	L.S.	L.S.	\$ _____
638.0300	Curb, Type 2D	L.S.	L.S.	L.S.	\$ _____
638.0400	Curb and Gutter, Type 2DG	L.S.	L.S.	L.S.	\$ _____
641.0100	Hydro Mulch Seeding (Common Bermuda Grass)	L.S.	L.S.	L.S.	\$ _____
642.0100	Maintenance - Planting period	3	Month	\$ _____	\$ _____
642.0200	Maintenance - Establishment period	9	Month	\$ _____	\$ _____

PROPOSAL SCHEDULE					
ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
645.0100	Traffic Control	L.S.	L.S.	L.S.	\$ _____
645.0200	Additional Police Officers and/or Additional Traffic Control Devices and Advertisement	F.A.	F.A.	F.A.	\$ <u>100,000</u>
648.0100	Field-Posted Drawings	L.S.	L.S.	L.S.	\$ _____
650.0100	Curb Ramp, Type 1	L.S.	L.S.	L.S.	\$ _____
650.0200	Curb Ramp, Type 2A	L.S.	L.S.	L.S.	\$ _____
650.0300	Curb Ramp, Type 2B	L.S.	L.S.	L.S.	\$ _____
650.0400	Curb Ramp, Type 2C	L.S.	L.S.	L.S.	\$ _____
696.0100	Field Office Trailer (Not to Exceed \$32,000)	L.S.	L.S.	L.S.	\$ _____
696.0200	Maintenance of Trailer	F.A.	F.A.	F.A.	\$ <u>25,000</u>
698.0100	Training	F.A.	F.A.	F.A.	\$ <u>25,000</u>
699.1000	Mobilization (Not to Exceed 6 Percent of the Sum of All Items Excluding the Bid Price of this Item)	L.S.	L.S.	L.S.	\$ _____

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX. QUANTITY	UNIT	UNIT PRICE	AMOUNT
	a. Sum of All Items				\$ _____
	b. Either Furnish Foreign Steel Not to Exceed Minimal Amount (Fill in '0') or Furnish Foreign Steel in Excess of Minimal Amount (Fill in 25% x a)				\$ _____
	c. Amount for Comparison of Bids (a + b)				\$ _____
All bidders must fill in b and complete c NOTE: Bidders must complete all unit prices and amounts. Failure to do so may be grounds for rejection of bid.					