


FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	HWY-0-01-95M	1995	3	6

GENERAL NOTES

- The scope of work for this project consists of cold planing, resurfacing, replacing a chain link fence and constructing drainage structures.
- The Contractor is reminded of the requirements of Subsection 108.01 - Subletting of Contract, which requires him to perform work amounting to not less than 50 percent of the total contract cost less deductible items. Non-compliance with this Subsection may be grounds for rejection of bid.
- The Contractor's attention is directed to the following Sections of the Special Provisions : Subsection 107.13 - Public Convenience and Safety; Subsection 107.21 - Contractor's Responsibility For Utility Property And Services.
- At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.
- The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.
- The exact locations and limits or areas to be cold planed shall be determined in the field by the Engineer.
- The Contractor shall notify the Engineer in writing, two (2) weeks prior to starting paving operations.
- The Contractor shall remove and dispose of all existing raised pavement markers prior to the overlaying of Asphalt Concrete. This work shall be considered incidental to Asphalt Concrete Pavement, Mix No. IV and will not be paid for separately.
- All holes and depressions shall be filled and compacted with Asphalt Concrete Pavement, Mix No. V prior to resurfacing. This work will be paid for under Asphalt Concrete Pavement, Mix No. V.
- Smooth riding connections shall be constructed at all limits of resurfacing as shown on the plans and/or as directed by the Engineer.
- Existing drainage system will be functional at all times during construction. The Contractor is to furnish materials, equipment, labor, tools and incidentals necessary to maintain flow. This work shall be considered incidental to various contract items.
- The contractor shall provide for access to and from all parking lots at all times.
- All saw cutting work shall be considered incidental to Cold Planing and will not be paid for separately.
- Grading and Compacting existing ground prior to paving shall be considered incidental to Asphalt Concrete Pavement, Mix No. IV and will not be paid for separately.
- All excess A.C. Aggregate Base and Subbase material not used for this project shall be delivered to the Pearl City Viaduct near 2nd Street. This work shall include but not limited to loading, hauling and end-dumping at the designated site. The Contractor shall contact the Engineer for specific instructions. All of the aforementioned work shall be considered incidental to the various contract items and will not be paid for separately.
- Removal and disposal of existing flagpole shall be considered incidental to Item No. 670.1000 "Flagpole" and will not be paid for separately.
- Removal and disposal of existing chain link fence shall be considered incidental to Item No. 607.0080 "8-Feet Chain Link Fence with Top Rail and Concrete Footings" and will not be paid for separately.

LEGEND

- Reconstruction Areas
- Leveling Areas
- Cold Planing Areas
- Resurfacing Limits
- Existing Electrical Line
- New Electrical Line
- Existing Joint Pole
- Existing Power Pole
- Existing Electric Manhole
- Adjusted Elec. MH Frame/Cover
- New Electric Manhole
- Existing Telephone Line
- New Telephone Line
- Existing Telephone Pole
- Existing Telephone Manhole
- Adjusted Tele. MH Frame/Cover
- New Telephone Manhole
- Existing Signal Corps Line
- New Signal Corps Line
- Existing TV Cable
- New TV Cable
- Existing 12" Water Line
- New 12" Water Line
- Existing Water Manhole
- Adjusted Water MH Frame/Cover
- New Water Manhole
- Existing Water Air Valve
- Adjusted Water Air Valve
- New Water Air Valve
- Existing Water Valve Box
- Adjusted Water Valve Box
- New Water Valve Box
- Existing Water Meter
- Adjusted Water Meter
- New Water Meter
- Existing Fire Hydrant
- New Fire Hydrant
- Existing Sewer Line
- New 12" Sewer Line
- Existing Sewer Manhole
- Adjusted Sewer MH Frame/Cover
- New Sewer Manhole
- Existing 6" Gas Line
- New 6" Gas Line
- Existing Gas Valve Box
- Adjusted Gas Valve Box
- New Gas Valve Box
- Existing Gas Manhole
- Adjusted Gas MH Frame/Cover
- New Gas Manhole
- Existing Monument
- Adjusted Monument
- New Monument
- Existing 24" Drain Line
- New 24" RCP Drain Line
- Existing Storm Drain Manhole
- Adjusted Storm Drain MH Frame/Cover
- New Storm Drain Manhole
- Existing Grated Drop Inlet
- Existing Catch Basin
- Existing Traffic Sign
- Existing Highway Lighting Standard
- Existing Light Pole



TYPICAL PAVEMENT SECTION

Scale: 3/4"=1'-0"

SURVEY PLOTTED BY	DATE
DRAWN BY G. Athanasio	10-95
DESIGNED BY C. Chang	
CHECKED BY	
ORIGINAL PLAN	
NOTE BOOK	
DATE	
BY	

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION
**GENERAL NOTES, LEGEND
AND TYPICAL SECTION**
OAHU DISTRICT BASEYARD
RESURFACING
Project No. HWY-0-01-95M
Scale: As Shown Date: April, 1995
SHEET No. 1 OF 1 SHEETS