

## ARTICLE XI – MOBILIZATION AND DEMOBILIZATION

11.1 GENERAL – The work consists of furnishing at the job site, plant, equipment, materials, labor and appliances and performing all work in connection with mobilization and demobilization for the job in accordance with this Article of the Specifications.

### 11.2 DESCRIPTION

- A. Mobilization shall include setting up, ready for use, all plant, equipment and necessary materials at the job site.
- B. Providing temporary barricades as required for Harbor operations during construction.
- C. Moving the barricades back to their original position upon completion of work.
- D. Demobilization shall include the removal of all the Contractor's plant and equipment and surplus material from the job site. The cleanup of the job site, satisfactory to the Harbors Division Construction Engineer, shall also be included in this article.

11.3 PAYMENT – Payment for Mobilization and Demobilization will not be measured and paid for separately but shall be considered incidental to the applicable items in Article X of these Specifications.