

**STATE OF HAWAII  
DEPARTMENT OF TRANSPORTATION  
HIGHWAYS DIVISION**

**ADDENDUM NO. 1  
for  
PAVEMENT REPAIR AT VARIOUS LOCATIONS  
PROJECT NO. HWY-OM-2014-37**

The following amendment shall be made to the Bid Documents:


**A. SPECIFICATIONS**

Replace Pages 629-1a through 629-2a dated 11/10/10 with the attached Pages 629-1a through 629-2a dated 9/25/14.

**B. PRE-BID CONFERENCE NOTES**

Pre-bid conference notes and attendance sheet are attached for your information.

Please acknowledge receipt of this Addendum No. 1 by recording the date of its receipt in the space provided on page P-4 of the Proposal.

  
\_\_\_\_\_  
**FORD N. FUCHIGAMI**  
Interim Director of Transportation

## SECTION 629 - PAVEMENT MARKINGS

Make the following amendments to said Section:

(I) Amend **Subsection 629.03(B) – Temporary Pavement Markings** by revising the third paragraph from line 62 to 63 to read:

“Maintain and replace temporary pavement markings, flexible delineators, and barricades for three months after installation.”

(III) Amend **Table 629.03 – 1 – Temporary Pavement Markings** to read as follows:

“TABLE 629.03-1 TEMPORARY PAVEMENT MARKINGS	
TYPE	PAVEMENT MARKINGS
Passing Permitted - Both Sides	Single 4-inch yellow stripe 5 feet in length spaced 20 feet on center with Type D markers spaced 40 feet on center and located on center of 5-foot length of stripe.
Passing Prohibited - Both Sides	Double solid 4-inch yellow stripes with Type D markers placed 20 feet on center on one of 4-inch yellow stripes selected by the Engineer.
Passing Permitted - One Side Only	Single continuous 4-inch yellow stripe with Type D markers placed on stripe 20 feet on center on no-passing side and single 4-inch yellow stripes 5 feet in length spaced 20 feet on center on passing side.
Lane Lines - Lane Changing Permitted	Single 4-inch yellow or white stripe 5 feet in length spaced 20 feet on center with Type C or Type D markers spaced 40 feet on center.
Lane Lines - Lane Changing Prohibited	Double solid 4-inch white stripes with Type C markers placed 20 feet on center on one of the 4-inch white stripes selected by the Engineer.
Crosswalk	Two 12-inch white transverse lines spaced 8 feet on center or as ordered by the Engineer.
Stop Line	Single 12-inch white transverse line.
<b>Note:</b> Paint may be used for temporary markings in areas where final paving is not complete.”	

(IV) Amend **Subsection 629.04 – Measurement** by revising the lines 292 to 294 to read as follows:

18                   **"629.04      Measurement.**     The Engineer will not measure for  
19                   furnishing and installing pavement striping, pavement markers, detour  
20                   pavement striping, curb markings, temporary pavement markings,  
21                   flexible delineator posts with reflector markers, Type I Barricades,  
22                   temporary signs, crosswalk marking, pavement arrows, pavement  
23                   words, pavement symbols and removing pavement markings for  
24                   payment.

25  
26   **(V)   Amend Subsection 629.05 – Payment** by revising lines 296 to 330 to  
27   read as follows:

28  
29                   **"629.05      Payment.**     The Engineer will not pay for the  
30                   accepted pavement marking items separately.     The Engineer will  
31                   consider the cost for pavement marking in the contract price of the various  
32                   contract items in Section 401 – Hot Mix Asphalt Pavement.     The cost  
33                   includes full compensation for maintaining, replacing, and eventually  
34                   removing the temporary pavement markings, flexible delineators and  
35                   barricades; and furnishing labor, materials, equipment, tools, and  
36                   incidentals necessary to complete the work.

37  
38                   The Engineer will not pay for the accepted removal of existing  
39                   pavement markings separately.     The Engineer will consider the cost for  
40                   the removal of existing pavement markings as included in the contract  
41                   price of the various items in Section 401 – Hot Mix Asphalt Pavement.  
42                   The cost includes full compensation for removing the existing pavement  
43                   markings, and furnishing labor, materials, equipment, tools, and  
44                   incidentals necessary to complete the work."

45  
46  
47  
48                   **END OF SECTION 629**

STATE OF HAWAII  
DEPARTMENT OF TRANSPORTATION  
HIGHWAYS DIVISION  
DESIGN BRANCH  
HIGHWAY DESIGN SECTION  
601 KAMOKILA BOULEVARD, ROOM 609  
KAPOLEI, HAWAII 96707

**PRE-BID CONFERENCE NOTES**

SEPTEMBER 16, 2014

**PROJECT:** PAVEMENT REPAIR AT VARIOUS LOCATIONS  
ISLAND OF OAHU  
**PROJECT NUMBER:** HWY-OM-2014-37

The pre-bid conference began at 9:02 AM and was opened by stating the project title and that the conference would answer any questions related to the project.

1. Question: Can maintenance of the temporary striping be limited to a specific duration with a force account for anything longer than that?

Response: The duration for maintenance of the temporary pavement markings, flexible delineators and barricades will be three months. Revised Special Provisions Section 629 in the addendum addresses this issue.

2. Question: Who provides the striping plans for the contractor?

Response: HDOT provides these plans.

3. Question: Is there a minimum square yardage for work orders, such as 100 square yards?

Response: There is no minimum area for any of the work orders.

The pre-bid conference concluded at 9:17 AM.

**PAVEMENT REPAIR AT VARIOUS LOCATIONS**  
**PROJECT NO. HWY-OM-2014-37**  
**PRE-BID MEETING**  
**SEPTEMBER 16, 2014**  
**9:00 AM**

NO.	NAME	COMPANY	PHONE NO.
1	Kevin Yamabayashi	Grace Pacific	842-3233
2	Sev Aggarwal	Road Builders Corp	833-5400
3			
4			
5			
6			
7			
8			
9			
10			
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			