

1 **SECTION 613 – CENTERLINE AND REFERENCE SURVEY MONUMENTS**

2
3 Make the following amendments to said Section:

4
5 **(I)** Amend **Subsection 613.03(A) – Initial Installation** from lines 22 to 26 to
6 read:

7
8 **“(A) Initial Installation.** Cut holes, in completed medians and
9 shoulders, to required depth or to solid rock, whichever is less. Fill hole
10 with concrete. Burr or feather plug for anchorage in concrete. Place
11 the 4 #4 x 20-inch bars as shown on the plans when curing the concrete.
12 Install brass plug in required position after concrete has sufficiently set.
13 After curing concrete at least 7 days, restore edge of pavement
14 surrounding monument to original condition.”

15
16 **(II)** Amend **613.04 – Measurement** by revising lines 48 to 56 to read as
17 follows:

18
19 **“613.04 Measurement.**

20
21 **(A)** New centerline and reference survey monuments and
22 reconstructing centerline and reference survey monuments will be paid on
23 a lump sum basis. Measurement for payment will not apply.

24
25 The Engineer will measure adjusting centerline and reference
26 survey monuments per each in accordance with the contract documents.

27
28 **(B)** The Engineer will measure new centerline and reference survey
29 monuments, reconstructing centerline and reference survey monuments,
30 and adjusting centerline and reference survey monuments per each in
31 accordance with the contract documents.”

32
33 **(III)** Amend **613.05 – Payment** by revising lines 62 to 79 to read as follows:

34
35 **“613.05 Payment.**

36
37 **(A)** The Engineer will pay for the accepted new centerline and
38 reference survey monuments and reconstructing centerline and reference
39 survey monuments on a contract lump sum basis. The Engineer will pay
40 for the accepted adjusting centerline and reference survey monument at
41 the contract unit price per each. Payment will be full compensation for
42 work prescribed in this section and the contract documents.

46 **(B)** The Engineer will pay for the accepted new centerline and
47 reference survey monuments, reconstructing centerline and reference
48 survey monuments, and adjusting centerline and reference survey
49 monuments at the contract unit price per each. Payment will be full
50 compensation for work prescribed in this section and the contract
51 documents.

52

53 The Engineer will pay for each of the following pay items when included in
54 the proposal schedule:

55

56 **Pay Item** **Pay Unit**

57

58 **(A)** Reconstructing Centerline and Reference
59 Survey Monuments Force Account

60

61
62 **(B)** Centerline and Reference Survey Monuments Each

63

64 Reconstructing Centerline and Reference Survey Monuments Each"

65

66

67

68

69

END OF SECTION 613