

GENERAL NOTES

FED. ROAD DIST. NO.	STATE	FED. AD PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	HWY-0-03-09M	2009	3	11

1. The scope of work for this project consists of installing landscape planting and asphalt median curbing.

2. The Contractor is reminded of the requirements of Subsection 108.01 - Subletting of Contract, which requires him to perform work to not less than 30 percent of the total contract cost less deductible items. Non-compliance with this Subsection may be grounds for rejection of bid.

3. The Contractor's attention is directed to the following Sections: Subsection 104.11 - Utilities and Services; Subsection 107.06 - Contractor Duty Regarding Public Convenience; and Section 645 - Work Zone Traffic Control.

4. At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.

5. The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data, but the accuracy is not guaranteed. The encountering of other obstacles during the course of work is possible. The Contractor shall tone for the exact locations and depths of all underground facilities, either shown on or omitted from the plans, in areas where work, such as the placement of sign posts, traffic signal conduits, etc. may affect these properties. Toning shall be considered incidental to the various contract items and will not be paid for seperately. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.

6. The Contractor shall notify, the Oahu Transit Services, Lowell Tom (848-4578) two (2) weeks prior to construction, informing them of location, scope of work, and closure of Name of Highway and/or traffic lanes and dates of closure. (For Oahu projects only. For other islands, check with your local bus company.)

7. The Contractor shall notify the Engineer in writing, two (2) weeks prior to starting construction operations.

8. The Contractor shall obtain a Community Noise permit from the State Department of Health, Noise and Radiation Branch, 591 Ala Moana Blvd., Room 136, Honolulu, HI 96813-2498; Telephone No. 586-4700. This shall be considered inidental to the various contract items and will not be paid for seperately.

9. The Contractor shall indemnify and be solely responsible for the protection of adjacent properties, utilities and existing structures from damages due to construction. Repairing any damage shall be at the Contractor's own expense, to the satisfaction of the Engineer.

10. Existing drainage system will be functional at all times during construction. The Contractor shall furnish materials, equipment, labor, tools and incidentals necessary to maintfain flow. This work shall be considered incidental to any culvert work or the various contract items and will not be paid for seperately.

11. The Contractor shall clean and remove any accumulation of aggregates along the roadside within 10 feet of the edge of pavement. This work shall be considered incidental to bulk of work or the various contract items and will not be paid for seperately.

12. All saw cutting work shall be considered incidental to Roadway Excavation or Asphalt Concrete or Various Contract Items or their respective bid items.

13. The Contractor shall provide and maintain for access to and from all existing driveways , sidewalks and ADA access routes, and side streets and cross streets at all times.

14. No material and/or equipment shall be stockpiled or otherwise stored within the highway right-of-way except at locations de- signed in writing and approved by the Engineer. If use of location is approved by the engineer, the Contractor shall obtain a permit to use the property within the highway right-of-way from the Oahu District Office at telephone no. 831-6712.

LEGEND

- Existing Electrical Line

Existing Joint Pole

Existing Power Pole

Existing Electric Manhole

Existing Telephone Line

Existing Telephone Pole

Existing Telephone Manhole

Existing Signal Corps Line

Existing TV Cable

Existing 12" Water Line

Existing Water Manhole

Existing Water Air Valve

Existing Water Valve Box

Existing Water Meter

Existing Fire Hydrant

Existing Sewer Line

Existing Sewer Manhole

Existing 6" Gas Line

Existing Gas Valve Box

Existing Gas Manhole

Existing Monument

Existing 24" Drain Line

Existing Storm Drain Manhole

Existing Grated Drop Inlet

Existing Catch Basin

Existing Traffic Sign

Existing Highway Lighting Standard

Existing Highway Lighting Pullbox

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

GENERAL NOTES AND LEGEND

Kailua Rd., Castle Hospital to Kawaiunui Bridge
Kalaniana'ole Hwy., Kailua Rd. to Ulupuni St.
Median Erosion Control
Project No. HWY-0-03-09M

Date: April, 2009

SHEET No. 1 OF 1 SHEETS