

STATE OF HAWAII  
DEPARTMENT OF TRANSPORTATION  
HIGHWAYS DIVISION

ADDENDUM NO. 1  
for  
SLOPE MAINTENANCE FOR EROSION CONTROL  
AT VARIOUS SITES ON OAHU, PHASE 4  
PROJECT NO. HWY-O-04-10M  
DISTRICT OF EWA  
ISLAND OF OAHU  
FY 2010

The following amendments shall be made to the Bid Documents:

**A. SPECIFICATIONS**

1. Amend **Section 667.03 (J) (2) – Placement** by revising lines 253 to 256 to read as follows:

“The open areas around existing structures and obstructions within the ACBM system shall be a minimum of 2 inches and a maximum of 8 inches. To achieve the allowable gap width, the precast concrete blocks may be sawcut in the field. The blocks shall be cut linearly such that each partial block keys into at least two (2) adjacent blocks. Further, the partial blocks shall be physically interlocked with at least three (3) surrounding blocks to resist lateral movement and uplift. The gross area of each partial block in direct contact with the protected subgrade shall be no less than 0.5 square feet. The remaining open areas shall be filled with uncompacted 3B Fine aggregate material and made flush with the top of the ACBMs as shown on the contract documents.”


**B. PLANS**

1. Replace Plan Sheet No. 11 with the attached Plan Sheet No. ADD. 11.

**C. PRE-BID MEETING MINUTES**

1. Attached are the June 8, 2010 Pre-bid Meeting Minutes and Attendance Sheet for your information.

Please acknowledge receipt of this Addendum No. 1 by recording the date of its receipt in the space provided on page P-4 of the Proposal.

  
BRENNON T. MORIOKA, Ph.D., P.E.  
Director of Transportation

**STATE OF HAWAII  
DEPARTMENT OF TRANSPORTATION  
HIGHWAYS DIVISION**

**June 8, 2010  
PRE-BID MEETING MINUTES  
FOR**

**SLOPE MAINTENANCE FOR EROSION CONTROL  
AT VARIOUS SITES ON OAHU, PHASE 4  
PROJECT NO. HWY-O-04-10M  
DISTRICT OF EWA  
ISLAND OF OAHU  
FY 2010**

The pre-bid meeting for the project Slope Maintenance For Erosion Control At Various Sites On Oahu, Phase 4 was called to order by Mr. Herbert Chu on June 8, 2010 at 9:00 a.m. The pre-bid meeting was held at the Department of Transportation, Highways Division, Oahu District Conference Room, 727 Kakoi Street, Honolulu, Hawaii 96813:

Mr. Chu stated that the meeting was not mandatory and was held to answer questions by prospective bidders. There was no question asked since no bidder attended the meeting.

Meeting was adjourned at approximately 9:10 a.m.

# STATEWIDE STORM WATER MANAGEMENT PROGRAM SIGN-IN SHEET



Meeting: Project No. HWY-O-04-10M Pre-Bid Conference  
 Date: June 8, 2010 Time: 9:00 A.M.  
 Location: DOT-Highways, Kakoi Conference Room

	NAME	ORGANIZATION/TITLE
1	KYSON MORIKUNI	ENVIRO SERVICES / DOT CONSULTANT
2	HERBERT CHU	HWY-L&T
3	BIG SH	HWY "
4	JASON LAU	LIMTACO CONSULTING GRP.
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		