

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15
- 16
- 17
- 18
- 19
- 20
- 21
- 22
- 23
- 24
- 25
- 26
- 27
- 28
- 29
- 30
- 31
- 32
- 33
- 34
- 35
- 36
- 37
- 38
- 39
- 40
- 41
- 42
- 43
- 44
- 45

(I) Amend 624.04 - Measurement by replacing lines 587 to 588 to read:

Water meter relocation at Kalanianaʻole Highway will be paid on a lump sum basis. Measurement for payment will not apply.”

“624.05 Payment. The Engineer will pay for accepted water lateral relocation at Vineyard Boulevard on a contract lump sum basis. The price includes full compensation for saw cutting, excavating and backfilling; including asphalt concrete pavement, hot mix asphalt base course, concrete sidewalk, aggregate base course, and aggregate subbase course for trench repair; and furnishing equipment, tools, labor, materials, and other incidentals necessary to complete the work. Payment will be full compensation for the work prescribed in this section and contract documents.

The Engineer will pay for accepted water meter relocation at Kalanianaʻole Highway on a contract lump sum basis. The price includes full compensation for saw cutting, excavating and backfilling; including asphalt concrete pavement, hot mix asphalt base course, aggregate base course, and aggregate subbase course for trench repair; restoration of existing irrigation system; and furnishing equipment, tools, labor, materials, and other incidentals necessary to complete the work. Payment will be full compensation for the work prescribed in this section and contract documents.

The Engineer will pay for following pay items when included in proposal schedule:

Pay Item	Pay Unit
Water Lateral Relocation at Vineyard Boulevard	Lump Sum
Water Meter Relocation at Kalanianaʻole Hwy	Lump Sum”

END OF SECTION 624