

1 **SECTION 641 – HYDRO-MULCH SEEDING**
2

3 Make the following amendments to said Section:
4

5 **(I)** Amend **Subsection 641.02(B) – Fertilizer** by revising the section from line
6 33 to 36 to read:

7
8 **“(B) Fertilizer.** Proper fertilizer shall be used in hydro-mulch mix,
9 depending on condition of soil. Apply at rates and in amounts consistent
10 with manufacturer’s specifications. Contractor shall provide a Soil Analysis
11 Report, if requested by Engineer, and shall use report to determine quantity
12 and ratio of fertilizer for sustained growth of grass. Submit
13 recommendations from a licensed Landscape Architect when deviating
14 from the application rates and amounts above.”
15

16
17 **(II)** Amend **Subsection 641.03(A) – Seeding** by revising the first paragraph
18 from line 100 to 103 to read:

19
20 **“(A) Seeding.** Apply seeded mulch within the timeframe in Subsection
21 209.03(B), if temporary stabilization will not be utilized, after completion of
22 slopes or portion of slope when exposed face attains height of 15 feet.
23 Notify Engineer not less than 24 hours ahead of hydro-mulch seeding
24 operation. Do not hydro-mulch until the Engineer inspects and accepts
25 areas for planting.”
26

27 **END OF SECTION 641**
28
29
30
31
32