



- WATER NOTES**
1. THE WATER LINE LAYOUT WHEN STAKED OUT IN THE FIELD AS INDICATED ON THE PLAN SHALL BE ADJUSTED ACCORDING TO THE MOST FINISHED PROFILES PROVIDING THE NECESSARY COVER AND OTHER REQUIREMENTS.
 2. THE CONTRACTOR SHALL NOTIFY THE BOARD OF WATER SUPPLY IN WRITING ONE WEEK PRIOR TO COMMENCING WORK ON THE MAIN.
 3. MATERIALS & CONSTRUCTION OF WATER MAINS & APPURTENANCES SHALL BE IN ACCORDANCE WITH THE STANDARDS OF THE B.W.S.
 4. CONNECTION TO EX'G. WATER MAINS AND THE CHORINATION OF THE NEW MAINS SHALL BE DONE BY THE B.W.S. AND PAID FOR BY THE CONTRACTOR.
 5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DAMAGES TO EX'G. WATER MAINS & APPURTENANCES.
 6. THE CONTRACTOR SHALL EXPOSE THE EX'G. MAIN PRIOR TO EXCAVATION OF MAIN TRENCHES TO VERIFY THEIR LOCATIONS & DEPTHS.
 7. APPROVAL OF THESE PLANS BY THE B.W.S. IS FOR THE WATER SYSTEM ONLY.
 8. * INDICATES MATERIALS FURNISHED BY THE CONTRACTOR AND INSTALLED BY THE B.W.S.
 9. THE ENGINEER WILL FURNISH THE CONTRACTOR WITH THE DETAILS & DIMENSION OF ALL NEAR REACTION BLOCKS AS SOON AS POSSIBLE AFTER THE GROUND CONDITIONS HAVE BEEN VERIFIED BY EXCAVATING THE TRENCH AT THE REQ'D. LOCATION.

EX'G. CONDITIONS, SITE PLAN, SECTION & UTILITIES.

BRIDGE DETAILS
 KAPIOLANI CHANNEL K-1
 WAIANAE IRI WATERSHED
 WAIANAE, OAHU, HAWAII

DEPARTMENT OF PUBLIC WORKS
 CITY AND COUNTY OF HONOLULU
 DIVISION OF ENGINEERING
 AND

U. S. DEPARTMENT OF AGRICULTURE
 SOIL CONSERVATION SERVICE

Designed by: [Signature]
 Date: [Date]
 Drawn by: [Signature]
 Traced by: [Signature]
 Checked by: [Signature]
 Approved by: [Signature]
 TITLE: CIVIL ENGINEER
 BOARD OF WATER SUPPLY

Approved by: [Signature]
 TITLE: CIVIL ENGINEER
 BOARD OF WATER SUPPLY

Sheet No. 7
 Drawing No. 7-3-0-1-200
 Form SCS-313 (November)