



CONCRETE WASHOUT PIT DETAIL

Not to Scale

1. *The dimensions and location of the washout pit shall be determined by the contractor and submitted to the Department of Health, Clean Water Branch (DOH-CWB) in the Site-Specific BMP Plan.*
2. *The dimensions of the concrete washout pit shall be sized to hold wash water for the number of concrete trucks required, based on 20 gallons of wash water per truck, plus additional capacity for a 3-inch rainfall storm event, without overflowing.*
3. *If the washout pit is sized for a one-day pour, the collected water and materials shall be removed from the pit and disposed of properly prior to the start of the next pour, or another properly sized pit shall be used for each subsequent concrete pour and truck washout.*
4. *Water shall be allowed to evaporate or disposed of properly, and all hardened materials shall be disposed of in an appropriate manner.*

FIGURE 13A

STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION	
<u>CONCRETE WASH OUT PIT DETAIL</u>	
<u>CASTLE HILLS ACCESS ROAD DRAINAGE IMPROVEMENTS</u>	
T.M.K. 4-5-24: 02, 03, 04 and 05 T.M.K. 4-5-108: 68, 69, 70, 71, 72, 73 and 74	
SCALE: AS SHOWN	DATE: MARCH 2009