

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	61A-01-92	1992	3	13

GENERAL NOTES

1. The scope of work for this project consists of constructing a 6-foot wide concrete sidewalk, wheelchair ramps and curbing, adjusting manholes, water meters and pullboxes and installing signs and pavement markings.
2. The Contractor is reminded of the requirements of Subsection 108.01 - Subletting of Contract, to perform with its own organization, work amounting to not less than 50 percent of the total contract cost less deductible amounts allowed. Non compliance with this Subsection shall be grounds for rejection of bid.
3. The existence and location of underground utilities, appurtenances and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of the work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.
4. The exact limits of constructing the specified items are approximate. The exact locations shall be determined in the field by the Engineer.
5. The Contractor's attention is directed to Subsection 107.13-Public Convenience and Safety, Section 645-Traffic Control and Subsection 107.21-Contractor's Responsibility for Utility Property and Service of the Special Provisions.
6. Dressed sidewalk shall consist of cleaning, grubbing, grading, reshaping and compacting the unpaved edge of sidewalk with suitable excavated material as shown on the plans and/or as directed by the Engineer. This work shall be considered incidental to the various contract items.
7. Removal of existing asphalt or concrete sidewalk shall be considered incidental to Item No. 608.0200, Plain Concrete Sidewalk.
8. The Contractor shall provide safe access for pedestrians at all times during construction.
9. Existing Drainage system will be functional at all times during construction. Contractor is to furnish materials, equipment, labor tools and incidentals necessary to accomplish maintenance of flow, the cost of which shall be considered incidental to the various contract items.
10. Contractor shall provide for access to and from all existing driveways and streets at all times.
11. At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.
12. Smooth connections shall be constructed to existing driveways, concrete sidewalks, catch basins and wheelchair ramps as shown on the plans and/or directed by the Engineer.
13. The Contractor shall notify the Oahu Transit Services, Inc. Customer and Public Relations Office at 848-4576, seven (7) days prior to starting construction.

14. HECO and HECO pullboxes shall be adjusted to new finished grade in accordance with HECO and HECO Standard Details.

LEGEND:

- htpb Existing Hawaiian Telephone Pullbox to be Adjusted
- htpb Existing Hawaiian Telephone Pullbox
- hepb Existing Hawaiian Electric Pullbox to be Adjusted
- hepb Existing Hawaiian Electric Pullbox
- tmh Existing Telephone Manhole
- sdmh Existing Storm Drain Manhole to be Adjusted
- sdmh Existing Storm Drain Manhole
- smh Existing Sewer Manhole
- cb Existing Catch Basin
- wmh Existing Water Manhole
- wm Existing Water Meter to be Adjusted
- wm Existing Water Meter
- wv Existing Water Valve
- gv Existing Gas Valve
- fh Existing Fire Hydrant
- hlpb Existing Highway Light Pullbox to be Adjusted
- hlpb Existing Highway Light Pullbox
- hl Existing Highway Light
- tsp Existing Traffic Signal Pole
- tspb Existing Traffic Signal Pullbox to be Adjusted
- tspb Existing Traffic Signal Pullbox
- tscb Existing Traffic Signal Control Box
- mon. Existing Monument to be Adjusted
- mon. Existing Monument
- tree Existing Tree
- s-8" Existing Sewer Line
- sd-6" Existing Storm Drain
- d-24" Existing Drain Line
- w-8" Existing Water Line
- g-16" Existing Gas Line
- t Existing Telephone Cable
- Existing Concrete Sidewalk
- Existing Road Loop Detectors
- Existing Guardrail
- Existing Right of Way

STATE OF HAWAII  
DEPARTMENT OF TRANSPORTATION  
HIGHWAYS DIVISION

GENERAL NOTES AND  
LEGEND

PALI HIGHWAY SIDEWALKS  
WYLLIE STREET TO AHI PLACE  
PROJECT NO. 61A-01-92

Scale: As Shown Date: Mar., 1992

SHEET No. 1 OF 1 SHEETS