

GENERAL NOTES

1. The scope of work for this project consists of constructing a 6-foot wide concrete sidewalk; wheelchair ramps and curbing; adjusting manholes, water meters and pullboxes; and relocating signs, a crosswalk and a highway light.
2. The Contractor is reminded of the requirements of Subsection 108.01 - Subletting of Contract, which requires him to perform work amounting to not less than 50 percent of the total contract cost less deductible items. Non-compliance with this Subsection may be grounds for rejection of bid.
3. The Contractor's attention is directed to the following Sections of the Special Provisions : Subsection 107.13 - Public Convenience and Safety; Subsection 107.21 - Contractor's Responsibility For Utility Property And Services; and Section 645 -Traffic Control.
4. At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.
5. The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.
6. The Contractor shall notify in writing, the Oahu Transit Services, Inc. Roads Supervision Office, 811 Middle St., Hon., HI 96819 (ph. #848-4571) seven (7) days prior to any paving operations.
7. Smooth connections shall be constructed to existing driveways, concrete sidewalks, catch basins and wheelchair ramps as shown on the plans and/or directed by the Engineer.
8. Dressed sidewalk shall consist of cleaning, grubbing, grading, reshaping and compacting the unpaved edge of sidewalk with suitable excavated material as shown on the plans and/or as directed by the Engineer. This work shall be considered incidental to the various contract items.
9. Existing drainage system will be functional at all times during construction. The Contractor is to furnish materials, equipment, labor, tools and incidentals necessary to maintain flow. This work shall be considered incidental to various contract items.
10. The Contractor shall provide safe access for pedestrians at all times during construction.
11. The contractor shall provide for access to and from all existing side streets at all times.
12. Removal of existing asphalt or concrete sidewalk shall be considered incidental to Item No. 608.0200, Plain Concrete Sidewalk.
13. HTCO and HECO pullboxes shall be adjusted to new finished grade in accordance with HTCO and HECO Standard Details.

| FED. ROAD DIST. NO. | STATE | FED. AID PROJ. NO. | FISCAL YEAR | SHEET NO. | TOTAL SHEETS |
|---------------------|-------|--------------------|-------------|-----------|--------------|
| HAWAII              | HAW.  | STP-061-1(31)      | 1995        | 3         | 11           |

LEGEND

|        |  |             |                                     |
|--------|--|-------------|-------------------------------------|
| —e—    | Existing Electrical Line                       | —Δ—12—      | Existing Sewer Line                 |
| °jp    | Existing Joint Pole                            | °Δmh        | Existing Sewer Manhole              |
| °pp    | Existing Power Pole                            | °SMH        | Adjusted Sewer MH Frame/Cover       |
| °emh   | Existing Electric Manhole                      | —g—6—       | Existing 6" Gas Line                |
| °EMH   | Adjusted Elec. MH Frame/Cover                  | °gv         | Existing Gas Valve Box              |
| —t—    | Existing Telephone Line                        | °GV         | Adjusted Gas Valve Box              |
| °tp    | Existing Telephone Pole                        | °gmh        | Existing Gas Manhole                |
| °tmh   | Existing Telephone Manhole                     | °GMH        | Adjusted Gas MH Frame/Cover         |
| °HTMH  | Adjusted Tele. MH Frame/Cover                  | °mon.       | Existing Monument                   |
| —Δc—   | Existing Signal Corps Line                     | °MON.       | Adjusted Monument                   |
| —tv—   | Existing TV Cable                              | ---d--24--- | Existing 24" Drain Line             |
| —w—12— | Existing 12" Water Line                        | °Δdmh       | Existing Storm Drain Manhole        |
| °wmh   | Existing Water Manhole                         | °SDMH       | Adjusted Storm Drain MH Frame/Cover |
| °WMH   | Adjusted Water MH Frame/Cover                  | □gdi        | Existing Grated Drop Inlet          |
| °av    | Existing Water Air Valve                       | ch          | Existing Catch Basin                |
| °AV    | Adjusted Water Air Valve                       | ⊙           | Existing Traffic Sign               |
| °wv    | Existing Water Valve Box                       | ⊙           | Existing Highway Lighting Standard  |
| °WV    | Adjusted Water Valve Box                       | ●           | Existing Highway Lighting Standard  |
| °wm    | Existing Water Meter                           | °ppb        | Existing Pedestrian Push Button     |
| °WM    | Adjusted Water Meter                           |             |                                     |
| °fh    | Existing Fire Hydrant                          |             |                                     |
| □Lapb  | Existing Highway Lighting Pullbox              |             |                                     |
| □LSPB  | Adjusted Highway Lighting Pullbox              |             |                                     |
| □HEHH  | Adjusted Electric Handhole                     |             |                                     |
| □hepb  | Existing Electric Pullbox                      |             |                                     |
| □HEPB  | Adjusted Electric Pullbox                      |             |                                     |
| □HECPB | Adjusted Electric Pullbox with Concrete Cover  |             |                                     |
| □htpb  | Existing Telephone Pullbox                     |             |                                     |
| □HTPB  | Adjusted Telephone Pullbox                     |             |                                     |
| □HTCPB | Adjusted Telephone Pullbox with Concrete Cover |             |                                     |
| □tapb  | Existing Traffic Signal Pullbox                |             |                                     |
| □TSPB  | Adjusted Traffic Signal Pullbox                |             |                                     |

|               |                   |         |
|---------------|-------------------|---------|
| ORIGINAL PLAN | SURVEY PLOTTED BY | DATE    |
| NOTED         | DRAWN BY          | 1/26/95 |
| DESIGNED BY   | TRACED BY         |         |
| CHECKED BY    | DESIGNED BY       |         |
| CHECKED BY    | CHECKED BY        |         |

STATE OF HAWAII  
DEPARTMENT OF TRANSPORTATION  
HIGHWAYS DIVISION

GENERAL NOTES AND LEGEND

PALI HIGHWAY SIDEWALKS  
Philippine Consulate to Puhiwa Rd.  
# Ahi Pl. to Country Club Rd.  
Fed. Aid Proj. No. STP-061-1(31)

Scale: As Shown      Date: Sept., 1994

SHEET No. 1 OF 1 SHEETS