

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	61A-01-97M	1997	13	84

PALI HIGHWAY PAVEMENT RESURFACING SCHEDULE								
	LIMITS (@ STA.)		COLD PLANING DEPTH (IN.)	EXCAVATION DEPTH (IN.)	NEW A.C. BASE THICKNESS (IN.)	NEW A.C. PAV'T MIX NO. IV THICKNESS (IN.)	NEW UNTREATED PERMEABLE BASE COURSE THICKNESS (IN.)	NEW P.C.C. PAVEMENT THICKNESS (IN.)
INBOUND ALL LANES	BEGIN PROJECT 121+15± RT.	HOMELANI ST. 13+25± LT.	2½			2½		
OUTBOUND AUXILIARY, LEFT & CENTER LANES			5			2½		
OUTBOUND RIGHT LANE				10	5	2½		
INBOUND ALL LANES AND SHOULDERS (EXCEPT OUTSIDE SHOULDER STA. 95+00 to 43+30)	13+25± LT.	96+00± LT.				1½		
OUTSIDE SHOULDER	95+00± LT.	43+30± LT.		9½	8½	2½		
OUTBOUND ALL LANES AND SHOULDERS EXCEPT RIGHT LANE STA. 27+45± to 89+80±	13+25± LT.	96+00± LT.	1½ LT. LANE 17+00-51+00			1½		
OUTBOUND RIGHT LANE	27+45± RT.	28+30± RT.		10	8½	2½		
	28+30± RT.	80+80± 81+00± RT.		15½			6	11
	80+80± 81+00± RT.	88+40± 88+80± RT.		VAR. 15½ to 20½			VAR. 6 to 11½	11
	88+40± 88+80± RT.	89+40± 89+80± RT.		10½	9½ 10	2½ 2		

PALI LOOKOUT ROAD PAVEMENT RESURFACING SCHEDULE				
	LIMITS (@ STA.)		EXCAVATION (IN.)	A.C. BASE (IN.) A.C. PAVEMENT MIX NO. IV (IN.)
ALL LANES	83+83±	6+04±		3
	6+04±	63+30±	5½ (FOR WIDENING AREAS)	5½ (FOR WIDENING AREAS) 3

LEGEND FOR
AS-BUILT POSTINGS

~~~~~

100-00

Roadway

Squiggly line for  
as-built deletion

Double line for  
as-built deletion

Text for as-built  
posting

STATE OF HAWAII  
DEPARTMENT OF TRANSPORTATION  
HIGHWAYS DIVISION

RESURFACING SCHEDULES

PALI HIGHWAY RESURFACING  
Country Club Road to Tunnel Entrance  
Including Both Roads to Lookout  
Project No. 61A-01-97M

Scale: As Shown      Date: May 1997

SHEET No. 1 OF 1 SHEETS

SURVEY PLOTTED BY: DATE: 5-13-97

DESIGNED BY: H. S. S. S.

NOTED BY: J. S. S. S.

CHECKED BY: J. S. S. S.

"AS-BUILT"