


DAVID Y. IGE
GOVERNOR OF HAWAII



STATE OF HAWAII
DEPARTMENT OF HEALTH
P. O. BOX 3378
HONOLULU, HI 96801-3378

DIR 0739
DIRECTOR'S OFFICE
DEPT. OF TRANSPORTATION
VIRGINIA PRESSLER, M.D.
DIRECTOR OF HEALTH

2015 JUN 17 A 5:24
In reply, please refer to:
File:

June 4, 2015

TO: Community Noise Permit Applicant

FROM : James E. Toma
Noise Section Supervisor
Indoor and Radiological Health Branch

SUBJECT: Community Noise Permit #O 15-093 Approval

Please be advised that your Community Noise Permit is hereby granted.


If additional time is necessary for the project, the applicant shall submit a request for extension, along with an updated work schedule, prior to the **expiration date**. Extensions to Community Noise Permits are subject to annual fees.

Extensions or modifications of a permit shall be submitted in writing to the following address:

Department of Health
Indoor and Radiological Health Branch
591 Ala Moana Boulevard
Honolulu, Hawaii 96813-4921

Should you have any questions, please call me at 586-4700.

Thank you for your cooperation.



State of Hawaii

Department of Health

Application for Community Noise Permit

Permit is required by Title 11, Administration Rules, Department of Health, Chapter 46, Community Noise Control.

Part I. Applicant Information

Name of Company			Authorized Individual
State of Hawaii, Department of Transportation			Ford N. Fuchigami
Mailing Address			Title
869 Punchbowl Street			Director
City	State	Zipcode	Phone
Honolulu	HI	96813	808-587-2150

Part II. Community Noise Permit Fee Schedule (Annual)

<input type="checkbox"/>	Activities involving demolition, construction, extension, additions, or renovation of a single family dwelling	\$25
<input checked="" type="checkbox"/>	All other construction activities	\$50
<input type="checkbox"/>	Operation of stationary noise sources	\$50
<input type="checkbox"/>	Equipment related to agricultural activities	\$50
<input type="checkbox"/>	Equipment related to industrial activities	\$50

Part III. Description of Activity

The resurfacing of Pali Highway from Waakanaka Street to Kamehameha Highway and Pali Highway lighting replacement from Vineyard Boulevard to Kamehameha Highway, replacement of guardrails and crash cushions, construction of concrete median barriers, installing of new guardrails, curb ramp, signs and pavement markings.

Part IV. Location of Activity

Pali Highway from Vineyard Boulevard to Kamehameha Highway. See Attachment 1- Location Map

Part V. Equipment to be Utilized

Backhoe, Excavator, Hoe Ram, Loader, Compressor, Truck, Water Truck, Walk Behind Saw, Concrete Truck, Premelter, Thermoplastic Machine, Paver, Cold Planer, Shuttlebuggy, Steel Drum Roller w/vibration, Saw, K/P Broom, Liquid Distributor Truck, Power Generator, Jackhammer, Grader, Crane, Liquid Tack Coat Distribution Truck, Drilling Machine, and Post Driving Machine.

Part VI. Estimated Duration of Construction Activity


* Attach activity schedule for construction activities or attenuation of stationary sources.

From	February 1, 2016	To	January 31, 2018
------	------------------	----	------------------

Certification of Individual Authorized to Act for Applicant

I certify that I have knowledge of the facts herein set forth and that the same are true and correct to the best of my knowledge and belief. Acceptance of this permit constitutes an acknowledgement and agreement that the permittee will comply with all rules, regulations and orders of the department and the conditions precedent to the granting of this permit.

DAVID Y. IGE
GOVERNOR



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
869 PUNCHBOWL STREET
HONOLULU, HAWAII 96813-5097

FORD N. FUCHIGAMI
DIRECTOR

Deputy Director
JADE T. BUTAY
ROSS M. HIGASHI
EDWIN H. SNIFFEN
DARRELL T. YOUNG

IN REPLY REFER TO:

HWY-DS 2.8302

March 23, 2015

TO: THE HONORABLE VIRGINIA G. PRESSLER, M.D., M.B.A, FACS
DIRECTOR OF HEALTH

ATTN: JAMES TOMA
NOISE SECTION SUPERVISOR
INDOOR AND RADIOLOGICAL HEALTH BRANCH

FROM: FORD N. FUCHIGAMI
DIRECTOR OF TRANSPORTATION

SUBJECT: COMMUNITY NOISE PERMIT AND APPLICATION FOR
PALI HIGHWAY RESURFACING
WAOKANAKA STREET TO KAMEHAMEHA HIGHWAY
AND PALI HIGHWAY LIGHTING REPLACEMENT, VINEYARD BOULEVARD
TO KAMEHAMEHA HIGHWAY
FEDERAL-AID PROJECT NO. NH-061-1(035)

In response to your telephone comments provided to Chris Dasch of Wesley Segawa's office on March 10, 2015, regarding the Community Noise Permit application for Pali Highway Resurfacing, Vineyard Boulevard to Kamehameha Highway, the State of Hawaii Department of Transportation (HDOT) provides the following response.

Comment 1: How many hoe rams will the Contractor use?

HDOT Response: If the Contractor decides to utilize a hoe ram during construction, then one hoe ram will be used.

Comment 2: What is the schedule for the hoe ram use?

HDOT Response: It is anticipated that this project will go out to bid in August 2015, and a Contractor would be chosen shortly after that. It is anticipated the Contractor would use the hoe ram between June 2016 and August 2016. However, once the Contractor has been chosen, we will notify the Department of Health of any changes to the hoe ram schedule or the overall job schedule.

Comment 3: What is the overall schedule of the project?

HDOT Response: Construction of this project is estimated to begin in February 2016 and to end in January 2018. Please see the attached estimated construction schedule.

We appreciate your consideration of this application. If you have any questions regarding this application or the project in general please contact Ms. Mung Fa Chung at (808) 692-7545 or mungfa.chung@hawaii.gov. If submitting a written reply, please reference HWY-DS 2.8302 as shown above.

PERMIT No. 0 15-093

STATE OF HAWAII
DEPARTMENT OF HEALTH
INDOOR AND RADIOLOGICAL HEALTH BRANCH

COMMUNITY NOISE PERMIT FOR CONSTRUCTION ACTIVITIES

PURSUANT TO THE PROVISIONS OF CHAPTER 342F, HAWAII REVISED STATUTES, AND CHAPTER 11-46, HAWAII ADMINISTRATIVE RULES,
THIS PERMIT IS HEREBY GRANTED TO:

**STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION**

COMPANY OR INDIVIDUAL

FORD N. FUCHIGAMI - DIRECTOR

NAME OF AUTHORIZED INDIVIDUAL

AT PALI HIGHWAY FROM VINEYARD BOULEVARD TO KAMEHAMEHA HIGHWAY

(LOCATION OF ACTIVITY)

DURING THE HOURS OF 7:00 A.M. TO 6:00 P.M., MONDAY THROUGH FRIDAY AND 9:00 A.M. TO 6:00 P.M., SATURDAY
(EXCEPT SUNDAYS AND HOLIDAYS)

FEBRUARY 1, 2016

DATE ISSUED

JANUARY 30, 2018

EXPIRATION DATE

THIS PERMIT IS GRANTED UPON THE EXPRESSED PROVISION THAT THE HOLDER WILL COMPLY WITH ALL RULES, REGULATIONS AND
ORDERS OF THE DEPARTMENT AND THE CONDITIONS PRECEDENT TO THE GRANTING OF THIS PERMIT.

DIRECTOR OF HEALTH

By

James E. Toma
James E. Toma

NOISE SECTION SUPERVISOR

TITLE

SPECIAL RESTRICTIONS AND CONDITIONS: The use of the hoeram, walk behind saw, & jackhammer shall be limited to 9:00a.m.
to 5:30 p.m., Monday through Friday. The contractor shall notify the affected properties prior to hoeram
activities.

*SEE GENERAL RESTRICTIONS AND CONDITIONS ON BACK

THIS PERMIT IS GRANTED IN ACCORDANCE WITH THE FOLLOWING RESTRICTIONS AND CONDITIONS:

1. NO PERMIT SHALL ALLOW ANY CONSTRUCTION ACTIVITIES WHICH EMIT NOISE IN EXCESS OF THE MAXIMUM PERMISSIBLE SOUND LEVELS FOR THE HOURS BEFORE 7:00 A.M. AND AFTER 6:00 P.M. OF THE SAME DAY, MONDAY THROUGH FRIDAY.
2. NO PERMIT SHALL ALLOW ANY CONSTRUCTION ACTIVITIES WHICH EMIT NOISE IN EXCESS OF THE MAXIMUM PERMISSIBLE SOUND LEVELS FOR THE HOURS BEFORE 9:00 A.M. AND AFTER 6:00 P.M. ON SATURDAY.
3. NO PERMIT SHALL ALLOW ANY CONSTRUCTION ACTIVITIES WHICH EMIT NOISE IN EXCESS OF THE MAXIMUM PERMISSIBLE SOUND LEVELS ON SUNDAYS AND ON HOLIDAYS.
4. NO PERSON SHALL OPERATE NOR SHALL ITS OWNER PERMIT THE OPERATION OF AN ON-SITE VEHICLE, CONSTRUCTION EQUIPMENT, OR DEVICE, WITH A MOTOR OR EXHAUST SYSTEM OR BOTH, WITHOUT A MUFFLER. THIS SUBPARAGRAPH SHALL NOT APPLY TO PILE HAMMERS AND PNEUMATIC HAND TOOLS WEIGHING LESS THAN FIFTEEN POUNDS.
5. NO PERSON SHALL OPERATE NOR SHALL ITS OWNER PERMIT THE OPERATION OF AN ON-SITE VEHICLE, CONSTRUCTION EQUIPMENT, TOOL OR DEVICE ON ANY PREMISES OR A CONSTRUCTION SITE, WITH A MOTOR OR EXHAUST SYSTEM OR BOTH, WHICH HAS BEEN ALTERED, MODIFIED, OR REPAIRED; PROVIDED THIS SUBPARAGRAPH SHALL NOT APPLY IF THE OPERATOR OR OWNER CAN SHOW THAT THE ALTERED, MODIFIED OR REPAIRED COMPONENT IS EQUALLY OR MORE EFFECTIVE THAN THE ORIGINAL COMPONENT IN REDUCING NOISE.
6. SHOULD COMPLAINTS OCCUR AS A RESULT OF THE CONSTRUCTION ACTIVITY, THE HOLDER OF THIS PERMIT SHALL IMPLEMENT ABATEMENT PROCEDURES TO REDUCE NOISE EMISSIONS FROM THE ACTIVITY.
7. SHOULD NOISE EMISSIONS INTERFERE WITH ACTIVITIES WITHIN SCHOOL CLASSROOMS, LIBRARIES OR MULTIPURPOSE FACILITIES; OR DISTURBS PATIENTS IN HOSPITALS OR REST HOMES, THE HOLDER OF THIS PERMIT SHALL COORDINATE WITH FACILITY ADMINISTRATION TOWARD MINIMIZING POTENTIAL ADVERSE NOISE IMPACTS.
8. EACH PERMIT IS NONTRANSFERABLE EITHER FROM ONE LOCATION TO ANOTHER, FROM ONE ACTIVITY TO ANOTHER, OR FROM ONE PERSON TO ANOTHER WITHOUT THE WRITTEN APPROVAL OF THE DIRECTOR.
9. ANY MODIFICATION TO THE PERMIT SHALL BE SUBMITTED IN WRITING.
10. THIS PERMIT SHALL BE POSTED AT THE LOCATION OF THE ACTIVITY AT ALL TIMES.
11. THIS PERMIT DOES NOT RELEASE THE PERMITTEE FROM ANY LIABILITY FOR ANY LOSS DUE TO DAMAGE TO PERSONS OR PROPERTIES CAUSED BY, RESULTING FROM, OR ARISING OUT OF ANY NOISE ABATEMENT PROCEDURES.
12. THIS PERMIT IN NO MANNER IMPLIES OR SUGGESTS THAT THE DEPARTMENT OF HEALTH, OR ITS OFFICERS, AGENTS OR EMPLOYEES ASSUMES ANY LIABILITY, DIRECTLY OR INDIRECTLY, FOR ANY LOSS DUE TO DAMAGE TO PERSONS OR PROPERTIES CAUSED BY OR RESULTING FROM OR ARISING OUT OF ANY NOISE ABATEMENT PROCEDURES.
13. THE DIRECTOR IS AUTHORIZED TO ENTER AND INSPECT THE LOCATION OF ACTIVITY FOR ASCERTAINING COMPLIANCE OR NONCOMPLIANCE WITH ANY RULES, REGULATIONS OR STANDARDS PROMULGATED BY THE DEPARTMENT, TO MAKE REASONABLE NOISE TESTS IN CONNECTION THEREWITH, AND TO RECOMMEND REQUIREMENTS OF ANY NOISE ATTENUATION MEASURES.
14. THE DIRECTOR SHALL BE NOTIFIED, IN WRITING, OF THE PERMANENT TERMINATION OF THE ACTIVITY FOR WHICH THE PERMIT HAS BEEN GRANTED. IF SUCH NOTICE IS NOT RECEIVED BY THE EXPIRATION DATE SPECIFIED IN THE PERMIT, THE PERMIT SHALL AUTOMATICALLY TERMINATE AND THE PERMITTEE SHALL BE DIVESTED OF ALL RIGHTS THEREIN.
15. THIS PERMIT MAY BE SUSPENDED OR REVOKED FOR CAUSE.

DAVID Y. IGE
GOVERNOR OF HAWAII



STATE OF HAWAII
DEPARTMENT OF HEALTH
P. O. BOX 3378
HONOLULU, HI 96801-3378

VIRGINIA PRESSLER, M.D.
DIRECTOR OF HEALTH

COPY
In reply, please refer to:
File

FEB 2 2016

February 2, 2016

Ford N. Fuchigami
Director
State Department of Transportation
869 Punchbowl Street
Honolulu, Hawaii 96813

Dear Mr. Fuchigami:

This is in reference to your request for an extension of the **Community Noise Permit No. O 15-093; Resurfacing of Pali Highway between Waokanaka Street and Kamehameha Highway.**

The Community Noise Permit expiration date has been amended to March 31, 2019.

Should the duration of the project continue beyond the expiration date, the applicant shall submit a request for extension **prior to March 31, 2019.**


If there are any questions, please contact Mr. Stanley Yu of our office (808) 586-4700 or at stanley.yu@doh.hawaii.gov.

Sincerely,

A handwritten signature in dark ink, appearing to read "James E. Toma".

James E. Toma
Noise Section Supervisor
Indoor and Radiological Health Branch

DAVID Y. IGE
GOVERNOR OF HAWAII



DIR 0835

VIRGINIA PRESSLER, M.D.
DIRECTOR OF HEALTH

STATE OF HAWAII
DEPARTMENT OF HEALTH
P. O. BOX 3378
HONOLULU, HI 96801-3378

In reply, please refer to:
File:

July 1, 2015

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Ford N. Fuchigami
Director of Transportation
State of Hawaii
Department of Transportation
869 Punchbowl Street, Room 513
Honolulu, Hawaii 96813

DIRECTOR'S OFFICE
DEPT. OF
TRANSPORTATION
2015 JUL -6 P 1:51

Dear Mr. Fuchigami:

Enclosed is the VARIANCE (Docket No. 15-NR-VN-15) for Community Noise Control which was granted on June 30, 2015. The Decision and Order specifies the conditions and restrictions that are applicable to your project.

Non-compliance with the conditions and restrictions of the Decision and Order may bring about additional restrictions or possible suspension of the variance. Should you have any questions relative to the variance, please do not hesitate to contact me at (808) 586-4700 or at james.toma@doh.hawaii.gov.

Sincerely,

A handwritten signature in black ink, appearing to read "James E. Toma".

James E. Toma
Noise Section Supervisor
Indoor and Radiological Health Branch

STATE OF HAWAII
DEPARTMENT OF HEALTH

In the Matter of the Application)	
For Variance for:)	
)	
STATE DEPARTMENT OF)	Docket No. 15-NR-VN-15
TRANSPORTATION)	V-859
Noise – Pali Highway Resurfacing and)	
Lighting Replacement from Waokanaka)	
Street to Kamehameha Highway.)	
_____)	

DECISION AND ORDER

Pursuant to Chapter 342F, Hawaii Revised Statutes (H.R.S.), and Chapter 11-46, Hawaii Administrative Rules (H.A.R.), Community Noise Control; and based upon the application and review by the Indoor and Radiological Health Branch, the variance request from the provisions of Section 11-46-6(a), H.A.R., is hereby GRANTED with the following restrictions and conditions:

1. The variance shall be granted to conduct the following construction activities along Pali Highway from Waokanaka Street, Honolulu to Kamehameha Highway, Kaneohe:
 - a. Conduct cold planing, resurfacing, and reconstruction of weakened pavement areas.
 - b. Installation of new highway lighting, curb ramps, bridge rails, and new guard rails.
 - c. Replacement of guardrails in-kind and end treatments.
 - d. Construction of concrete median barriers.
 - e. Installation of signs and pavement markings.
2. The variance shall be granted from February 1, 2016 to January 31, 2018.
3. The variance shall be granted for the following days/times:

Sunday	midnight to midnight
Monday to Friday	midnight to 5:00 a.m., 7:00 p.m. to midnight
Saturday	midnight to 8:00 a.m., 8:00 p.m. to midnight

4. The variance shall be granted with the following restriction:
 1. The use of the hoe ram, the walk behind saw, and handheld jackhammers shall be prohibited after 10:00 p.m. within 500 feet of residences.
 2. The use of excavators, backhoes, loaders, vibratory rollers, and cold planers shall be prohibited after midnight within 500 feet of residences.
5. The applicant shall notify the Indoor and Radiological Health Branch as to the date and time of any variance hour activity as soon as the dates are confirmed and also when the project is completed.
6. Residents shall be given sufficient notice regarding the project. The notification for the planned nighttime activity shall also contain the name and telephone number of the job-site inspector. In addition, a copy of any notifications, as well as progress reports, shall also be sent to the Indoor and Radiological Health Branch.
7. The applicant shall make every effort to minimize noise emanating from the project.
8. The use of reverse signal alarms shall be prohibited from 8:00 p.m. to 7:00 a.m. Alternative methods such as utilizing a ground guide for signaling shall be employed.
9. Traffic noise from heavy vehicles travelling to and from the project site shall be minimized near residences.
10. The applicant shall have a job-site inspector to whom immediate complaints can be forwarded for prompt response, and who shall have the general responsibility of monitoring quiet work procedures.
11. If the noise level is such that numerous complaints are received by the Department, the applicant shall cease operations upon receipt of an order and complete the project during hours on weekdays as directed.
12. Pursuant to Section 342F-5(d)(3), H.R.S., the applicant shall be required to perform noise sampling during the variance hours and report the results of such sampling to the Indoor and Radiological Health Branch.

13. Should the duration of the project continue beyond the expiration date, the applicant shall submit a request for extension along with an updated work schedule prior to January 31, 2018.

DATED: Honolulu, Hawaii, JUN 30 2015.



LYNN M. NAKASONE

Environmental Health Program Administrator
Environmental Health Services Division

DAVID Y. IGE
GOVERNOR OF HAWAII



STATE OF HAWAII
DEPARTMENT OF HEALTH
P. O. BOX 3378
HONOLULU, HI 96801-3378

VIRGINIA PRESSLER, M.D.
DIRECTOR OF HEALTH

COPY

In reply, please refer to
File:

FEB 9 2016

February 5, 2016

Ford N. Fuchigami
Director of Transportation
State Department of Transportation
869 Punchbowl Street, Room 513
Honolulu, Hawaii 96813

Dear Mr. Fuchigami:

This is in reference to your request for an extension of the **Community Noise Variance (Docket No. 15-NR-VN-15); Resurfacing and Lighting Replacement on Pali Highway**.

The Community Noise Variance expiration date has been amended to March 31, 2019.

Should the duration of the project continue beyond the expiration date, the applicant shall submit a request for extension **prior to March 31, 2019**.

If there are any questions, please contact Mr. James Toma, Noise Section Supervisor at (808) 586-4700 or james.toma@doh.hawaii.gov.

Sincerely,

A handwritten signature in cursive script, appearing to read "Lynn M. Nakasone".

Lynn M. Nakasone
Environmental Health Program Administrator
Environmental Health Services Division

PRE-BID MEETING MINUTES

Pali Highway Resurfacing Waakanaka Street to Kamehameha Highway and Pali Highway Lighting Replacement Vineyard Boulevard to Kamehameha Highway Federal-Aid Project No. NH-061-1(035)

District of Honolulu and Koolaupoko, Island of Oahu

Date/Time: May 5, 2017; 9:02 a.m.

Location: 601 Kamokila Boulevard, Room 577B, Kapolei, Hawaii

Participants: See sign-in sheet

Mel Chung briefed everyone on the following items:

1. Anything said at this meeting is for clarification only, the bid documents shall govern over anything said today and discrepancies shall be clarified by addendum.
2. Meeting agenda, minutes and attendance will be included as part of an addendum.
3. Some items to be aware of:
 - a. The Contractor shall coordinate with City & County of Honolulu, Department of Design and Construction, Wastewater Division project entitled “Dowsett Highlands Relief Sewer” between Nuuanu Avenue and Dowsett Avenue.
 - b. As a first order of business, the Contractor shall work on widening the roadway and installing the traffic control as shown on Sheet CR3 to CR11 and installing the lighting as shown on the Electrical Sheets for the area between Nuuanu Avenue and Dowsett Avenue. This work shall be done first so the “Dowsett Highlands Relief Sewer” project can begin. Median work in this area shall be complete with 5 months of Notice to Proceed and Lighting work within this area shall be complete within 9 months of Notice to Proceed.
 - c. The Contractor shall coordinate with a digital leveling project entitled “Height Modernization Facilities, Digital Leveling, Oahu, Unit 2, Project No. HWY-O-09-14”, in case any USGS monuments are disturbed and to allow the digital leveling consultant access to the work area if needed.
4. Contractor shall comply with the terms and conditions from environmental process and approved permits and responsible to renew the permits as necessary:
 - a. NPDES Permits
 - b. Community Noise Permit (from Vineyard Boulevard to Kamehameha Highway)

- c. Noise Variance (from Waokanaka Street to Kamehameha Highway)
A Noise Variance between Vineyard Boulevard to Waokanaka Street is currently under review.
- d. Woody plants greater than 15 feet tall shall not be disturbed, removed, or trimmed during the bat birthing and pup rearing season from June 1 to September 15.
- e. Night time work shall be avoided during the Hawaii seabird fledgling period from September 15 through December 15. However, if night time work does occur, lights shall be shielded and directed toward the ground.
- f. Contractor shall be responsible to obtain all required City & County permits. A Grading Permit is not required.

5. Open to Questions

Question 1: Are copies of the noise variance on the DOH website?

Response: Noise variance will be included as part of the Addendum.

Question 2: Are the bat birthing and seabird fledgling periods considered in DOT's estimated construction schedule?

Response: Yes. With regard to the bat birthing season, only one tree is to be removed, which will not affect the schedule. Regarding the seabird fledgling season, the Contractor can still work during this period, however any lights used shall be shielded and directed towards the ground.

Question 3: Can DOT's estimated construction schedule be made available as 400 working days seems short for the scope of work?

Response: DOT will not provide their schedule and believes the 400 days is adequate to complete the scope of work.

Question 4: Are the CAD files available for the bid?

Response: HDOT does not release their CAD files.

6. Additional Items

- a. HDOT has portable concrete barriers available for use during construction but are only available for pickup on weekends. Amount available will be included as part of Addendum 1. The portable concrete barriers can be kept for the entire project duration.

UPDATE: 75 barriers will be placed on reserve for this project and will be available for pickup on weekends only, at the HDOT Kaneohe Baseyard, 45-889 Pookela Street, Kaneohe, 96819. The pickup needs to be coordinated. Contractor to coordinate with State Project Engineer. Additional barriers beyond the 75 reserved will not be guaranteed and will be available on a "first come, first serve" basis.

- b. The bid date will not be postponed.

7. The meeting ended when the prospective bidders had no additional questions at 9:12 a.m.

Sign In Sheet

Subject: Pre-Bid Meeting
Project: Pali Highway Resurfacing, Waokanaka Street to Kamehameha Highway and
Pali Highway Lighting Replacement, Vineyard Boulevard to Kamehameha Highway
Project No: NH-061-1(035)
Date: 5/5/2017
Time: 9:00 AM
Location: 601 Kamokila Boulevard, Room 611, Kapolei HI 96707

[illegible]

Sign In Sheet

Subject: Pre-Bid Meeting
Project: Pali Highway Resurfacing, Waokanaka Street to Kamehameha Highway and Pali Highway Lighting Replacement, Vineyard Boulevard to Kamehameha Highway
Project No: NH-061-1(035)
Date: 5/5/2017
Time: 9:00 AM
Location: 601 Kamokila Boulevard, Room 611, Kapolei HI96707

[illegible]