

Attachment C - Construction Schedule (SWPPP Section 7.2.5)

CONSTRUCTION SCHEDULE

The date when the SWPPP, including erosion control measures will be implemented: Sep 1, 2017

All Perimeter Sediment Control, check dams, and Inlet Protection BMPs will be installed prior to construction for the first phase of construction. These BMPs meet Section 5.1.1.3.1 as the inlets protected and the perimeter control BMPs are downstream of the paving work. These BMPs will be installed per the manufacturer's recommendations.

The date when the general contractor will begin the earth-disturbing activities: Sep 16, 2017

Cessation, temporarily or permanently, of construction activities on the site: Apr 16, 2018
Roadway work will be completed on April 16, 2018.

Final or temporary stabilization of areas of exposed soil: Apr 16, 2018
Shoulder resurfacing areas will be stabilized with asphalt.

The date when the general contractor will end site disturbance: Apr 16, 2018

The date when erosion control measures will be removed: Apr 30, 2018

The date when the Notice of Cessation form will be submitted: Apr 30, 2018